
Commercial Building on Side Road

PRESCOTT, ARIZONA





Roject Information Seet Index

Contact:

Prepared by:

Contact:

Deo Iuvante L.L.C.

drscottpusd@gmail.com

W. Alan Kenson & Associates, P.C. P.O. Box 11593

Prescott, AZ 86304

Alan Kenson, 928-443-5812

Jobsite Address: 5416 Side Road Prescott, AZ

Parcel Number: 103-01-038

Lot Area: .39 Acres

Current Code: 2018 International Building Code

Proposed Building 2,765 S.F.

Occupancy: U - Utility and Miscellaneous

Construction Type:

Type II-B

ARCHITECTURAL

Cover Sheet / Project Information

Occupancy / Egress Plan

Civil Cover Sheet

Civil General Notes

Civil General Notes

Topographic Survey

Grading and Drainage Plan

Water and Sewer Plan

Profiles and Sections

Typical Details

Typical Details

Landscape Plan

Landscape Details

Architectural Site Plan

Reference / Dimension / Wall Types / Floor Plan

High Window Plan

Building Sections

Exterior Elevations

Reflected Ceiling Plan, Ceiling Framing Plan and Detail

Door & Window Schedule, Room Finish Plan & Schedule

STRUCTURAL

Foundation Plan

MECHANICAL

Mechanical Floor Plan Mechanical Schedules

Mechanical Details

Plumbing Floor Plan

Plumbing Details and Schedules

Plumbing Schematics

ELECTRICAL

Electrical Symbols, Specifications, One-Line Diagram and Notes

Lighting and Power Floor Plan

NOTE: METAL BUILDING PLANS SUBMITTED UNDER SEPARATE COVER

Caphic Standards EXISTING DOOR NORTH ARROW INDICATOR PROPOSED DOOR DETAIL DESIGNATOR BUILDING SECTION DESIGNATOR GRID LINE DESIGNATOR **REVISION DESIGNATOR ELEVATION DESIGNATOR** DESCRIPTIVE NOTE DESIGNATOR ROOM NUMBER / FINISH DESIGNATOR DOOR NUMBER DESIGNATOR (#)

Project Description

SCOTT HICKS, IS PROPOSING TO BUILD A 2,625 S.F. METAL BUILDING ON HIS EXISTING PROPERTY. IT WILL BE USED AS A PERSONAL STORAGE GARAGE WITH A PORTION TO BE LEASED OUT.

Architect:

DOOR TYPE DESIGNATOR

WALL TYPE DESIGNATOR

WINDOW TYPE DESIGNATOR

W. Alan Kenson & Associates, P.C.

P 928-443-5812 F 928-443-5815 P.O. Box 11593 Prescott, AZ 86304

email: wakaarchitect@gmail.com www.kenson-associates.com

ARCHITECTURE & PLANNING



REVISIONS

L.O. CHECKED BY W.A.K. June 30th, 2023 JOB NO. **777**

EXIT SIGNS:

 PROVIDE A 6"x9" BLUE TACTILE, BRAILLE, 'EXIT' SIGN AS MANUFACTURED BY 'SIMPLY EXIT SIGNS (#SE-1980)' OR EQUAL COMPLYING WITH ICC/ANSI A117.1 SECTION 703.1 AND IBC SECTIONS 1013 & 1111, ADJACENT TO EACH DOOR TO AN EXIT PASSAGEWAY AND THE EXIT DISCHARGE.

Pumbing Calculations OCCUPANCY OCCUPANCY WATER CLOSETS | LAVATORIES CLASSIFICATION COUNT STORAGE .09 TOTAL REQUIRED

TOTAL PROVIDED

FIRE DEPARTMENT NOTES:

- FIRE EXTINGUISHERS SHALL BE PROVIDED IN ACCORDANCE WITH THE INTERNATIONAL FIRE CODE (IFC) AND NFPA 10.
- HAZARDOUS MATERIAL INVENTORY STATEMENTS (HMIS) MUST BE COMPLETED AND SUBMITTED ALONG WITH THE MATERIAL SAFETY DATA SHEETS (MSDS) PROVIDED BY THE MANUFACTURER OF THE PRODUCTS AND MATERIALS FOR ALL HAZARDOUS MATERIALS ONCE THE OCCUPANTS OF THE SUITES ARE IDENTIFIED. THE HMIS FORM MAY BE FOUND ON THE CITY WEB SITE AT WWW.PRESCOTT-AZ.GOV/DOCUMENTS.
- DOOR HARDWARE TO MEET 2018 IFC AND IBC REQUIREMENTS FOR EGRESS.
- PROVIDE ADDRESS NUMBERS IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM THE STREET FRONTING THE PROPERTY. THESES NUMBERS SHALL BE A MINIMUM OF 6 INCHES WITH CONTRASTING BACKGROUND.

Deress Legend:


EXIT ACCESS

ACCESSORY USE (NO OCCUPANCY)

XX

ROOM OCCUPANCY LOAD

SUBTOTAL OCCUPANCY LOAD



OCCUPANCY TOTAL REQUIRED EXIT WIDTH (FACTOR = 0.2) PROVIDED EXIT WIDTH

WORST CASE TRAVEL DISTANCE TO COMMON PATH OF EGRESS TRAVEL

FUNCTION OF SPACE

OCCUPANT LOAD FACTOR

STORAGE

300 GROSS

Ocupant load


GROSS SQUARE FOOTAGE LISTED BELOW DOES NOT INCLUDE ACCESSORY AREAS.

STORAGE AREA TOTAL:

2,472 SQ. FT. 8.24 OCCUPANTS 2,472 SQ. FT. 8.24 OCCUPANTS

Accessibility Notes

- ACCESS TO THESE FACILITIES SHALL BE AT PRIMARY ENTRANCES.
- 2. THE SLOPE OF PUBLIC WALKS SHALL NOT EXCEED A MAXIMUM CROSS SLOPE OF 2%.
- 3. WALKING SURFACES GREATER THAN 2% SHALL BE SLIP RESISTANT.
- 4. PROVIDE A 44"x60" MINIMUM LANDING ON THE STRIKE SIDE OF THE ENTRANCE DOOR WITH 44" MINIMUM WIDTH IN THE DIRECTION OF TRAVEL.
- 5. WALLS SHALL EXTEND 18" TO THE SIDE OF THE STRIKE EDGE OF A DOOR OR GATE THAT SWINGS TOWARDS THE OCCUPANT.
- 6. RAMPS SHALL HAVE A NON-SLIP SURFACE.
- 7. RAMPS SHALL BE A MINIMUM OF 36" WIDE.
- 8. EVERY REQUIRED EXIT DOORWAY SHALL BE SIZED FOR A DOOR NOT LESS THAN 36" WIDE BY NOT LESS THAN 6'-8" HIGH CAPABLE OF OPENING 90 DEGREES AND MOUNTED SO THE CLEAR WIDTH OF THE EXIT WAY IS 32"
- 9. THRESHOLDS TO BE A MAXIMUM OF 1/4" ABOVE ADJACENT FLOOR FINISH. ONE-HALF INCH THRESHOLD MAY BE USED IF BEVELED PER A.D.A. STANDARDS.
- 10. MAXIMUM EFFORT TO OPERATE A DOOR SHALL NOT EXCEED 5 POUNDS.
- 11. THE BOTTOM 10 INCHES OF ALL DOORS EXCEPT AUTOMATIC AND SLIDING DOORS SHALL HAVE A SMOOTH UNINTERRUPTED SURFACE.
- 12. PROVIDE LEVER TYPE HARDWARE, PANIC BARS, PUSH AND PULL ACTIVATING BARS, OR OTHER HARDWARE DESIGNED TO PROVIDE PASSAGE WITHOUT REQUIRING THE ABILITY TO GRASP THE OPENING HARDWARE. (30" TO 44" A.F.F.)







REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C. and may not be reproduced in any way without the written consent of W Alan Kenson & Associates, P.C

ates

Ci

DRAWN BY L.O. CHECKED BY W.A.K.

June 30th, 2023 JOB NO. **777** SHEET

INC.

PER THE YAVAPAI COUNTY INTERACTIVE MAPPING APPLICATION AND THE WARRANTY DEED RECORDED AS INSTRUMENT NO .: 2021-0043908, Y.C.R.O. APN. 103-01-038 IS OWNED BY DEO IUVANTE LLC.

NOTE:

THIS MAP DOES NOT REPRESENT A LAND BOUNDARY SURVEY. THE LOT BOUNDARY LINES, AS SHOWN ARE PER THE WARRANTY DEED LISTED ABOVE, AND THE LIMITED EXISTENT PARCEL CORNER MONUMENTS FOUND IN THE FIELD BY NEXUS SOUTHWEST LLC.

THE CONTOUR INTERVAL DEPICTED HEREON IS 1'.

THE HORIZONTAL AND VERTICAL DATUM FOR THIS SURVEY IS THE CITY OF PRESCOTT SURVEY DATUM.

NO TITLE REPORT FURNISHED, THEREFORE ALL EASEMENTS OF RECORD MAY NOT BE SHOWN HEREON.

UTILITIES AS SHOWN HEREON ARE BASED ON PHYSICALLY APPARENT ABOVE GROUND APPURTENANCES AND LIMITED UTILITY LOCATE MARKINGS BY OTHERS.

PROJECT BENCH MARK:

DATUM: NAVD-88 (CITY OF PRESCOTT SURVEY DATUM)

ELEVATION DEPICTED HEREON ARE BASED ON GPS OBSERVATIONS UTILIZING THE CITY OF PRESCOTT GPS BASE STATION AND THE GEOID-99 MODEL.

SEE THE TEMPORARY SITE BENCH MARKS PLOTTED ON SHEET 4 PER NEXUS SOUTHWEST LLC.

BASIS OF BEARING:

THIS TOPOGRAPHIC SURVEY AND MEASURED BEARINGS, WHERE SHOWN HEREON, ARE BASED ON THE CITY OF PRESCOTT'S SURVEY DATUM. THE LINE AS SHOWN HAS BEEN SELECTED AS THE LOCAL BASIS OF BEARING. THE CITY OF PRESCOTT SURVEY DATUM IS ON FILE WITH THE CITY OF PRESCOTT PUBLIC WORKS DEPARTMENT AND PUBLISHED ON THE CITY OF PRESCOTT WEBSITE AT WWW.PRESCOTT-AZ.GOV.

FEMA FLOODPLAIN:

PER FEMA FIRM PANEL 04025C1693H DATED 03/06/2018, SUBJECT PROPERTY LIES IN ZONE X.

REGISTRANTS:

THESE PLANS WERE PREPARED UNDER THE DIRECTION OF GARY R. KELLEY, PE 22880 AND CHRISTOPHER J. KIMBALL, RLS

TOPOGRAPHIC SURVEY NOTE:

THE TOPOGRAPHIC INFORMATION SHOWN HEREON IS PER A TOPOGRAPHIC SURVEY PERFORMED BY NEXUS SOUTHWEST LLC., MAY 2021. SUPPLEMENTAL OFFSITE TOPOGRAPHIC INFORMATION SHOWN HEREON PERFORMED BY KELLEY/WISE ENGINEERING INC., APRIL 2023.

LEGEND:

•	FIRE HYDRANT
•	WATER VALVE

WATER METER BOX

SEWER BACKWATER VALVE



EXISTING LIGHT EXISTING MAILBOX

8" S	SEWER LINE (SIZE AS NOTE
8" W	WATER LINE (SIZE AS NOTE
G	- GAS LINE
——— Е ———	· ELECTRIC LINE
OHE	OVERHEAD ELECTRIC LINE
—— т ——	TELEPHONE LINE

----4965 ---- EXISTING GRADE CONTOUR

LEGEND:

DENOTES RECORD DIMENSION [---] EXISTING GRADE CONTOUR BY THIS SURVEY. (NAVD-88)

ARIZONA DEPARTMENT OF TRANSPORTATION ASSESSOR'S PARCEL NUMBER BOOK

BACK WATER VALVE EL. OR ELEV. ELEVATION

EXISTING FOUND IRON REBAR LAND SURVEYS

MAPS AND PLATS PAGE

PRESSURE REDUCING VALVE PUBLIC UTILITY EASEMENT RIGHT OF WAY

REDUCED PRESSURE ZONE ASSEMBLY

SEWER CLEAN OUT SHUT-OFF VALVE SANITARY SEWER MANHOLE

> YAVAPAI COUNTY RECORDER OFFICE CENTERLINE

PARCEL BOUNDARY LINE RIGHT-OF-WAY LINE

TOE OF SLOPE TOP OF SLOPE

EX. POWER POLE LIGHT POLE

EX. CONTROL POINTS

EX. SIGN

SPECIAL NOTE:

BEGINNING WORK IN THE R.O.W.

ABBREVIATION LEGEND:

EXISTING CONCRETE ELEVATION

EXISTING GROUND ELEVATION

NEW FINISHED CONCRETE ELEVATION

NEW FINISHED GRADE ELEVATION

NEW FLOWLINE ELEVATION

FINISHED FLOOR ELEVATION

EXISTING PAVEMENT

ETC EXISTING TOP OF CURB

BOC BACK OF CURB

WM WATER METER

THE CITY OF PRESCOTT STANDARD DETAILS AND SPECIFICATIONS MEET MINIMUM DESIGN REQUIREMENTS OF THE EQUIVALENT MAG SPECIFICATIONS AND STANDARD DETAILS.

EX. FIRE HYDRANT

APPROVED TRAFFIC CONTROL PLAN AND R.O.W. PERMIT MUST BE OBTAINED FROM PUBLIC WORKS PRIOR TO

SEWER CLEANOUT



EXISTING POWER POLE

EXISTING SIGN


		H/P	HIGH POINT
8" S	SEWER LINE (SIZE AS NOTED)	INV	INVERT
8" W	WATER LINE (SIZE AS NOTED)	L/P	LOW POINT
G	GAS LINE	Р	PAVEMENT OR FINISHED SURFACE
—— Е ——	ELECTRIC LINE	PUE	PUBLIC UTILITY EASEMENT
———— OHE ————	OVERHEAD ELECTRIC LINE	ROW	RIGHT-OF-WAY
т	TELEPHONE LINE	TC	NEW TOP OF CURB ELEVATION
4" F	FIRE LINE (SIZE AS NOTED)	TYP	TYPICAL
4965	DESIGN FINISH GRADE	TW	NEW TOP OF WALL ELEVATION

COMMERCIAL BUILDING ON SIDE ROAD

APN: 103-01-038 5416 SIDE ROAD

LOCATED IN A PORTION OF SECTION 31, T15N, R1W AND A PORTION OF SECTION 31, T15N, R1W, GILA AND SALT RIVER MERIDIAN, YAVAPAI COUNTY, PRESCOTT, ARIZONA





PROJECT VICINITY MAP

APPROVED BY

CITY ENGINEER Date

UTILITIES MANAGER

UTILITY INFORMATION

Date

COMPANY	CONTACT	TELEPHON
ARIZONA PUBLIC SERVICE CO. 6672 CORSAIR AVE PRESCOTT, ARIZONA 86301	MICHELLE CURLEY	(928)443–6
CENTURYLINK 1445 MASONRY WAY PRESCOTT, ARIZONA 86301	DELL HOWARD	(520)838-3
UNISOURCE GAS CO. 6405 WILKINSON DRIVE PRESCOTT, ARIZONA 86301	JEFF BROWN	(928)771–7
SPARKLIGHT 3801 TOWER RD. PRESCOTT, ARIZONA 86301	DOUG HAMILTON	(928)910–30
CITY OF PRESCOTT UTILITIES 433 NORTH VIRGINIA ST. PRESCOTT, ARIZONA 86301	STEVE OLFERS	(928)777-1

BLUE STAKE CALL TWO WORKING DAYS BEFORE 1-800-STAKE-IT outside Maricopa County

CALL TWO WORKING DAYS BEFORE YOU DIG 1-800-STAKE-I⁻ 1-800-782-5348 OUTSIDE MARICOPA COUNTY)

CONTRACTOR TO VERIFY LOCATION AND ELEVATION OF EXISTING UTILITIES PRIOR TO CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR COORDINATING ANY NECESSARY UTILITY RELOCATION WITH THE APPLICABLE UTILITY.

	SH	IEET INDEX	
SHEET NO.	SHEET	DESCRIPTION	
1	C-001	COVER	
2-3	C-002-003	GENERAL NOTES	
4	TOPO	TOPOGRAPHIC SURVEY	
5	C-101	GRADING AND DRAINAGE PLAN	
6	C-201	WATER AND SEWER PLAN	
7	C-301	PROFILES AND SECTIONS	
8-9	C-501-502	TYPICAL DETAILS	

RECORD DRAWING CERTIFICATION

I HEREBY CERTIFY, TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THIS PROJECT HAS BEEN COMPLETED IN SUBSTANTIAL CONFORMANCE WITH THE APPROVED PLANS, SPECIFICATIONS AND REFERENCED STANDARDS, EXCEPT AS SHOWN HEREON; THAT THESE AS-BUILT PLANS REFLECT THE POSITION OF CONSTRUCTED IMPROVEMENTS BASED ON FIELD MEASUREMENTS; AND THAT THE MATERIALS USED IN CONSTRUCTION ARE AS SHOWN BASED ON FIELD OBSERVATION AND TEST RESULTS.


THIS CERTIFICATION DOES NOT WARRANT MATERIALS, WORKMANSHIP, METHODS OF CONSTRUCTION, OR OTHER ITEMS AFFECTING THE WARRANTY OF THIS PROJECT, TO THE CITY OF PRESCOTT. USERS OF THIS INFORMATION ARE ADVISED TO OBTAIN INDEPENDENT VERIFICATION OF ACTUAL CONDITIONS.

REGISTERED PROFESSIONAL ENGINEER (CIVIL)

DATE

PUBLIC IMPROVEMENT QUANTITIES* *SEE GENERAL NOTE 6 SHEET C-002

NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNIT	
WAT	ER MAIN IMPROVEMENTS			
1	8" CLASS 350 DIP WATER MAIN	210	LF	
3	8"x8"x8" TAPPING SLEEVE W/ 8" G.V.B.&C.	1	EA	
4	FIRE HYDRANT COMPLETE W/ TEE AND 6" G.V.B.&C.	1	EA	
5	1" WATER SERVICE BOX AND COVER	1	EA	



- ALL CONSTRUCTION SHALL CONFORM TO MARICOPA ASSOCIATION OF GOVERNMENTS (MAG), & CITY OF PRESCOTT (COP) CONSTRUCTION STANDARDS & SPECIFICATIONS. LATEST REVISIONS, UNLESS SPECIFICALLY APPROVED BY THE CITY AND MODIFIED ON THE PLANS, IN CONJUNCTION WITH THE LATEST REVISIONS OF THE MARICOPA ASSOCIATION OF GOVERNMENTS STANDARD SPECIFICATIONS AND DETAILS (MAG STANDARDS), UNLESS SPECIFICALLY MODIFIED ON THE PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN COPIES OF MAG AND CITY OF PRESCOTT STANDARDS AND SPECIFICATIONS AS WELL AS ALL OTHER STANDARDS AND SPECIFICATIONS NECESSARY TO COMPLETELY AND ACCURATELY INTERPRET THESE PLANS. ALL PLANS SIGNED BY THE CITY ENGINEER ARE NULL AND VOID ONE YEAR FROM DATE OF SIGNATURE IF CONSTRUCTION HAS NOT STARTED. RESUBMITTAL AND REVIEW SHALL BE REQUIRED, AFTER ONE YEAR.
- AFTER ONE YEAR.

 ALL QUANTITIES SHOWN ON THE PLANS ARE APPROXIMATE, ARE NOT VERIFIED BY THE PUBLIC WORKS DIRECTOR, AND ARE FURNISHED SOLELY FOR THE CONTRACTOR'S CONVENIENCE. THEY DO NOT NECESSARILY CORRESPOND TO BID SCHEDULE ITEMS. PAYMENT SHALL BE BASED ON BID SCHEDULE ITEMS FOR ACTUAL QUANTITIES PROVIDED AND INSTALLED. THE CONTRACTOR SHALL NOT BE RELIEVED OF HIS RESPONSIBILITY FOR INDEPENDENTLY ESTIMATING WORK QUANTITIES
- NOT BE RELIEVED OF HIS RESPONSIBILITY FOR INDEPENDENTLY ESTIMATING WORK QUANTITIES PRIOR TO BIDDING.

 CITY OF PRESCOTT PUBLIC WORKS DEPARTMENT PERMID(S) WILL BE REQUIRED FOR ALL OFF—SITE CONSTRUCTION AND CONSTRUCTION WITHIN THE PUBLIC RIGHT OF WAY.

 IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN, AT HIS OWN EXPENSE, SUCH PERMITS AS ARE REQUIRED FROM THE APPROPRIATE AGENCIES.

 THE PUBLIC WORKS DEPARTMENT SHALL BE NOTIFIED A MINIMUM OF 24 HOURS PRIOR TO BEGINNING ANY CONSTRUCTION IN THE PUBLIC RIGHT OF WAY.

 ANY WORK PERFORMED WITHOUT THE KNOWLEDGE AND APPROVAL OF THE PUBLIC WORKS DIRECTOR AND/OR ALL WORK MATERIALS NOT IN CONFORMATION WITH THE PLANS AND SPECIFICATIONS IS SUBJECT TO REMOVAL AND REPLACEMENT AT THE CONTRACTOR'S EXPENSE.

 A THOROUGH ATTEMPT HAS BEEN MADE TO SHOW THE LOCATION OF ALL UNDERGROUND OBSTRUCTIONS AND UTILITY LINES IN THE WORK AREA. THE ENGINEER AND THE CITY OF PRESCOTT WILL NOT GUARANTEE ANY LOCATIONS OR ELEVATIONS OF EXISTING UNDERGROUND UTILITIES SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE AND SHALL NOT BE RELIEVED OF RESPONSIBILITY FOR MAKING A COMPLETE AND ACCURATE ON—SITE DETERMINATION OF THE LOCATIONS, MATERIAL, AND SIZE OF ALL UTILITIES, STRUCTURES, AND FIELD CONDITIONS WHICH MAY AFFECT THE PROGRESS OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO STRUCTURES AND UTILITIES ENCOUNTERED DURING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING CONSTRUCTION.
- CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING

- CONSTRUCTION AND SHALL FIELD EXPOSE EXISTING UNDERGROUND UTILITIES PRIOR TO TRENCHING IN THEIR VICINITY.

 THE CONTRACTOR IS REQUIRED TO CONTACT BLUE STAKE (1—800—STAKEIT) A MINIMUM OF TWO WORKING DAYS (48) HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION. THE APPROPRIATE UTILITY COMPANIES SHALL BE NOTIFIED BY THE CONTRACTOR PRIOR TO ANY CONSTRUCTION.

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE RELOCATION AND/OR SUPPORT OF ALL UTILITIES, POWER POLES, ETC., THAT MAY BE NECESSARY.

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING TO THE PUBLIC WORKS DEPARTMENT FOR APPROVAL, TRAFFIC CONTROL PLANS PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR SHALL DETERMINE AND SUBMIT FOR APPROVAL THE EXACT SIGNING/TRAFFIC CONTROL DEVICES NECESSARY AND ALL TRAFFIC CONTROL WORK SHALL BE IN ACCORDANCE WITH THE LATEST REVISIONS THEREOF. NO STREET IS TO BE CLOSED, RESTRICTED, OR CONSTRUCTED UPON UNTIL A TRAFFIC CONTROL PLAN IS PREPARED BY THE CONTRACTOR AND SUBMITTED TO THE PUBLIC WORKS DIRECTOR ONE WEEK IN ADVANCE FOR REVIEW AND APPROVAL.

 APPROPRIATE EMERGENCY AGENCIES SHALL BE NOTIFIED A MINIMUM OF 24 HOURS PRIOR TO ANY CLOSING OF STREETS.

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION SURVEYING AND LAYOUT WITH CONTROL PROVIDED BY THE DESIGN ENGINEER OR HIS DESIGNEE.

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR QUALITY CONTROL MEASURES SUFFICIENT TO PRODUCE MATERIALS AND WORKMANSHIP OF ACCEPTABLE QUALITY CONTROL MEASURES SUFFICIENT TO PRODUCE MATERIALS AND WORKMANSHIP OF ACCEPTABLE QUALITY CONTROL MEASURES SUFFICIENT TO PRODUCE SHALL PROVIDE AN INDEPENDENT GEOTECHNICAL FIRM TO PERFORM QUALITY CONTROL TESTING SUCH AS SOILS AND CONCRETE TESTING, AND FULL TIME ASSURANCE TESTING AS IT MAY DEEM NECESSARY.

 THE CONTRACTOR WILL BE RESPONSIBLE FOR QUALITY ASSURANCE TESTING AS IT MAY DEEM NECESSARY.

 THE CONTRACTOR WILL BE RESPONSIBLE FOR SULL COSTS OF TESTING AND INSPECTION. INCLUDING
- NECESSARY.

 THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL COSTS OF TESTING AND INSPECTION, INCLUDING THE PRESENCE OF CITY INSPECTORS, REQUIRED AT NIGHT OR ON WEEKENDS.

 THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RE—WORK AND/OR REMOVAL AND REPLACEMENT OF ALL MATERIALS REPRESENTED BY FAILING TESTS OR SUBSTANDARD
- WORKMANSHIP.

 THE CONTRACTOR SHALL IMPLEMENT BEST—HOUSE—KEEPING MEASURES, AND EROSION AND SEDIMENT CONTROL MEASURES, TO PREVENT THE TRANSPORT OF CONSTRUCTION MATERIALS INTO DRAINAGE INLETS, STORM DRAIN MANHOLES, UTILITY STRUCTURES, OR ONTO ADJACENT STREETS

COP STANDARD DETAIL

- APPROVAL OF A PORTION OF THE WORK IN PROGRESS DOES NOT GUARANTEE ITS FINAL ACCEPTANCE. TESTING AND EVALUATION MAY CONTINUE UNTIL THE WRITTEN FINAL ACCEPTANCE OF A COMPLETE AND WORKABLE UNIT.

 THE CITY OF PRESCOTT MAY SUSPEND THE WORK BY WRITTEN NOTICE WHEN, IN ITS JUDGEMENT, PROGRESS IS UNSATISFACTORY, WORK BEING DONE IS UNAUTHORIZED OR DEFECTIVE, WEATHER CONDITIONS ARE UNSTABLE, OR THERE IS A DANGER TO THE PUBLIC HEALTH AND SAFETY.

 ALL OBSTRUCTIONS IN THE RIGHT OF WAY SHALL BE REMOVED BEFORE ANY CONSTRUCTION IS PERMITTED.
- 21. ALL OBSTRUCTIONS IN THE RIGHT OF WAY SHALL BE REMOVED BEFORE ANY CONSTRUCTION IS PERMITTED.

 22. REMOVAL OF STRUCTURES AND OBSTRUCTIONS AS NECESSARY TO COMPLETE THE WORK, OTHER THAN SPECIFICALLY SCHEDULED IN THE BID, IS INCIDENTAL TO THE CONTRACT. NO SEPARATE MEASUREMENT OF OR PAYMENT FOR UNSCHEDULED REMOVAL ITEMS WILL BE MADE.

 23. CLEARING AND GRUBBING IS CONSIDERED INCIDENTAL TO THE WORK UNLESS SPECIFICALLY IDENTIFIED IN THE BID SCHEDULE. NO SEPARATE MEASUREMENT OF OR PAYMENT FOR CLEARING AND GRUBBING, AND TREE REMOVAL, WILL BE MADE. THE SITE OF ALL EXCAVATION, EMBANKMENTS, AND FILLS SHALL FIRST BE CLEARED OF STUMPS, TRASH, WEEDS, RUBBISH, TOPSOIL, AND LOOSE BOULDERS WHICH SHALL BE REMOVED AND DISPOSED OF. PRIOR TO BIDDING THE CONTRACTOR MUST SATISFY HIMSELF REGARDING THE CHARACTER OF THE SUBSOILS TO INCLUDE THE AMOUNT OF LOAM, CLAY, SAND, QUICKSAND, HARDPAN, GRAVEL, ROCK, WATER, AND ALL OTHER MATERIAL TO BE ENCOUNTERED AND WORK TO BE PERFORMED.

 24. THE CONTRACTOR SHALL GUARD AGAINST DAMAGE DURING CONSTRUCTION TO EXISTING PROPERTIES AND IMPROVEMENTS. ANY ITEMS DAMAGED BY THE CONTRACTOR'S ACTIVITIES SHALL BE REPLACED IN KIND OR BETTER AT THE CONTRACTOR'S EXPENSE.

 25. THE CONTRACTOR SHALL KEEP SUITABLE EQUIPMENT ON HAND AT THE JOBSITE FOR MAINTENANCE DUST CONTROL, AND SHALL CONTROL DUST AS DIRECTED BY THE APPROPRIATE AGENCY.
- AGENCY.

 26. STREET AND TRAFFIC SIGNS SHALL BE RELOCATED BY THE CONTRACTOR IF NECESSARY, AT THE DIRECTION OF THE PUBLIC WORKS DIRECTOR.

 27. BACKFILL COMPACTION SHALL BE TYPE 1 (MAG, SECTION 601) UNLESS OTHERWISE NOTED.

 28. AGGREGATE BASE COURSE SHALL NOT BE PLACED ON SUBGRADE UNTIL SUBGRADE REQUIREMENTS HAVE BEEN ACHIEVED.

 29. NO PAVING CONSTRUCTION SHALL BE STARTED UNTIL ALL UNDERGROUND UTILITIES WITHIN THE ROADWAY PRISM ARE VERIFIED FOR DETAIL CONFORMANCE, COMPLETED AND TESTED (TO INCLUDE BUT NOT LIMITED TO) SEWER TESTING, LOW AIR TESTING OF MAIN LINE AND SERVICES, TRACE WIRE TESTING, DEFLECTION TESTING AND VERIFICATION OF MAIN LINE AND SERVICES PRESSURE
- 420P. WATER TESTING CHLORINATION/DISINFECTING OF MAIN LINE AND SERVICES, PRESSURE TESTING, TRACE WIRE TESTING AND VERIFICATION OF VALVE BOXES CONFORMING TO COP DETAIL
- ALL ASPHALT CONCRETE PAVEMENT SHALL BE PER APPLICABLE MAG SPECIFICATIONS AS AMENDED BY THE CITY OF PRESCOTT. ASPHALT CONCRETE MIX DESIGN SHALL BE SUBMITTED TO THE PUBLIC WORKS DIRECTOR OR HIS DESIGNEE FOR APPROVAL PRIOR TO START OF
- THE PUBLIC WORKS DIRECTOR OR HIS DESIGNEE FOR APPROVAL PRIOR TO START OF CONSTRUCTION.

 31. ALL UTILITY FRAMES, COVERS, VALVE BOXES, MANHOLES, ETC. SHALL BE ADJUSTED TO FINISH ASPHALT GRADE AFTER PLACEMENT OF SURFACE COURSE BY THE CONTRACTOR PER COP STANDARD DETAILS.

 32. ACCEPTANCE OF THE COMPLETED PAVING STRUCTURES WILL NOT BE GIVEN UNTIL REPRODUCIBLE "AS—BUILT" PLANS HAVE BEEN SUBMITTED BY THE CONTRACTOR AND APPROVED BY THE CITY.

 33. ALL CONCRETE TO BE AT LEAST 3000 PSI CLASS "A" PORTLAND CEMENT CONCRETE, UNLESS OTHERWISE SPECIFIED ON THE PLANS, SPECIFICATIONS, OR IN STANDARD DETAILS.

 34. EDGES OF CONCRETE STRUCTURES TO HAVE A ¾" CHAMFER, UNLESS OTHERWISE SPECIFIED ON THE PLANS.

 35. CONCRETE SURFACES TO HAVE A BROOM FINISH UNLESS OTHERWISE NOTED ON THE PLANS.

 36. ALL EXPANSION JOINTS TO BE SEALED WITH ¾" EXPANSION JOINT, PRE—FORMED JOINT FILLER AND SEALER, IN ACCORDANCE WITH MAG SECTION 729.

 37. DRIVEWAY ENTRANCES WILL BE LOCATED AS SPECIFIED ON THE PLANS UNLESS MODIFIED IN THE FIELD BY THE ENGINEER. ALL DRIVEWAY ENTRANCES SHALL BE CONSTRUCTED OVER 6" THICK AGGREGATE BASE COURSE PER MAG SPECIFICATION 702 AND COMPACTED TO 95% OF STANDARD PROCTOR DENSITY, UNLESS OTHERWISE NOTED.

 38. ALL DISTURBED FENCES SHALL BE REPLACED IN KIND. CONTRACTOR SHALL EXTEND FENCE REPLACEMENT TO THE CLOSEST UPRIGHT SUPPORT NECESSARY FOR STABILITY.

 39. MAILBOXES SHALL BE REMOVED AND REINSTALLED AS DIRECTED BY THE U.S. POSTAL SERVICE AND THE CITY OF PRESCOTT TEMPORARY LOCATIONS SHALL BE PER U.S.P.S.

 40. NO JOB WILL BE CONSIDERED COMPLETE UNTIL ALL CURBS, PAVEMENT, AND SIDEWALKS HAVE BEEN SWEPT CLEAN OF ALL DIRT AND DEBRIS.

 41. THE CONTRACTOR SHALL WARRANT ALL WORK FOR A MINIMUM TWO YEAR PERIOD AFTER FORMAL ACCEPTANCE OF THE WORK BY THE CITY.

Monles Andrew

CITY ENGINEER

REVISED: | DETAIL No

REVISED: DETAIL No

07/16

104P

07/16

101P

- 1. ALL WORK SHALL CONFORM TO MARICOPA ASSOCIATION OF GOVERNMENTS (MAG), & CITY OF PRESCOTT (COP) CONSTRUCTION STANDARDS & SPECIFICATIONS, WHICH ARE ON FILE IN THE OFFICE OF THE CITY ENGINEER.

 2. ALL EXISTING FRAMES, COVERS, VALVE BOXES, & MANHOLES SHALL BE EITHER REPLACED OR ADJUSTED TO FINISH GRADE DEPENDING ON PLAN CALL OUT UPON COMPLETION OF PAVING, UTILITY, OR RELATED CONSTRUCTION.

 3. ANY QUANTITIES SHOWN ON PLANS ARE NOT VERIFIED BY THE PUBLIC WORKS UTILITIES DIRECTOR.

 4. ACCEPTANCE OF THE COMPLETED WORK WILL NOT BE GIVEN UNTIL 3 MIL MYLAR & CAD FORMAT DIGITAL 'AS—BUILT' PLANS ON CITY OF PRESCOTT SURVEY DATUM & COORDINATES HAVE BEEN SUBMITTED & SEALED BY A REGISTERED PROFESSIONAL ENGINEER AND APPROVED BY THE PUBLIC WORKS DEPARTMENT.

 5. CITY OF PRESCOTT PUBLIC WORKS UTILITIES SHALL BE NOTIFIED A MINIMUM OF 24 HOURS PRIOR TO THE START OF ANY WORK.

 6. ALL WORK & MATERIALS WHICH DO NOT CONFORM TO THE SPECIFICATIONS ARE SUBJECT TO REMOVAL & REPLACEMENT AT THE CONTRACTOR'S EXPENSE.

 7. ANY WORK PERFORMED WITHOUT THE KNOWLEDGE OF THE CITY INSPECTOR OR HIS REPRESENTATIVE IS SUBJECT TO REMOVAL & REPLACEMENT AT THE CONTRACTOR'S EXPENSE.

 8. THE CONTRACTOR SHALL PROVIDE SUFFICIENT MEN, EQUIPMENT, & MATERIAL ON THE JOB AT ALL TIMES DURING CONSTRUCTION TO COMPLY WITH SPECIFICATIONS & TO COMPLETE THE WORK.

 9. CIP INSPECTION TO BE DONE BY THE CITY OF PRESCOTT PUBLIC WORKS DEPARTMENT OR THEIR REPRESENTATIVE. PRIVATE DEVELOPMENTS SHALL PROVIDE FOR INDEPENDENT 3RD PARTY INSPECTIONS.

 10. CONTRACTOR TO NOTITY PROJECT ENGINEER 72 HOURS (3 WORKING DAYS) IN ADVANCE OF CONSTRUCTION TO SCHEDULE CONSTRUCTION CONTROL STAKING.

 11. THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UNDERGROUND PIPELINES, TELEPHONE & ELECTRICAL CONDUITS & STRUCTURES IN ADVANCE OF ANY CONSTRUCTION & ORDERING MATERIALS.

 12. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UNDERGROUND PIPELINES, TELEPHONE & ELECTRICAL CONDUITS & STRUCTURES IN ADVANCE OF ANY CONSTRUCTION & ORDERING MATERIALS.

 13. CONTRACTOR SHALL NOTIFY BLUE STAKE AT 1-800-STAKEIT

- CONTRACTOR SHALL NOTIFY THE ENGINEER AS SUCH.

 15. ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY REQUIREMENTS MUST BE COMPLIED WITH.

 16. ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY REQUIREMENTS SHALL APPLY WHEN MORE STRINGENT THAN THE MAG OR CITY OF PRESCOTT STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.

 17. ALL PLANS SIGNED BY THE CITY ARE NULL & VOID ONE YEAR FROM DATE OF SIGNATURE IF CONSTRUCTION HAS NOT STARTED AND/OR IS NOT ACTIVELY PROGRESSING.

 18. PROJECT CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING TRAFFIC CONTROL PLANS WHICH SHALL BE MADE A PART OF THE PLAN REVIEW REQUEST TO THE CITY ENGINEER FOR APPROVAL.

 19. ALL WATER LINES & APPURTENANCES SHALL BE PROVIDED WITH TRACE WIRE PER CITY STANDARD DETAIL. TRACE WIRE SHALL BE SUBJECT TO A TRACEABILITY TEST, EASILY ACCESSIBLE, & ANY DEFICIENCIES SHALL BE CORRECTED PRIOR TO PAVING. THE TRACE WIRE SHOULD BE TESTED AND SUBMITTED AS A PACKAGE WITH THE TESTING PACKET.

 20. WATER—SEWER SEPARATION SHALL BE PURSUANT TO AAC R—18—5—502C.

 21. WATER MAINS SHALL BE SUBJECT TO A PRESSURE & LEAKAGE TEST IN ACCORDANCE WITH AWWA C—600 STANDARD.

 22. WATER MAINS SHALL BE DISINFECTED IN ACCORDANCE WITH ADEQ ENGINEERING BULLETIN NO. 8 'DISINFECTION OF WATER SYSTEMS'.

 23. OPERATION OF VALVES TO BE DONE BY CITY PERSONNEL ONLY.

 24. DUCTILE IRON PIPE TO BE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS. ALL MATERIALS USED IN THE INSTALLED PER MANUFACTURER'S REQUIREMENTS.

COP STANDARD DETAIL

- 25. ALL MATERIALS & PRODUCTS THAT COME INTO CONTACT WITH DRINKING WATER OR DRINKING WATER TREATMENT CHEMICALS MUST COMPLY WITH NSF STANDARD 61. ANY 'OR EQUAL SUBSTITUTION SHALL ALSO MEET NSF STANDARD 61.

 26. ALL TRENCHES & BEDDING SHALL BE PER COP DETAIL 200P & TECHNICAL SPECIFICATIONS.

 27. ALL MATERIALS USED IN THE INSTALLATION OF WATER MAINS SHALL BE PURSUANT TO AAC R—18—4 & SHALL BE NSF APPROVED FOR POTABLE WATER.

 28. ALL REVISIONS TO ORIGINAL PLANS MUST BE APPROVED BY THE PUBLIC WORKS DIRECTOR PRIOR TO CONSTRUCTION.

 29. ALL DUCTILE IRON, COPPER, & BRASS FITTINGS SHALL BE ENCASED IN POLYETHYLENE PROTECTIVE WRAPPING IN ACCORDANCE WITH MAG SECTION 610.5 UNLESS COUNTERINDICATED BY GEOTECHNICAL CORROSIVITY TESTING OF BEDDING AND SHADING MATERIALS & APPROVED BY THE PUBLIC WORKS DIRECTOR.

 30. WATER LINES SHALL BE INSTALLED WITH MECHANICAL RESTRAINTS WHERE JOINT RESTRAINTS IS REQUIRED.

 31. WATER SERVICE INTERRUPTION NOTICES SHALL BE GIVEN TO AFFECTED RESIDENTS BY THE CONTRACTOR AT HIS EXPENSE. ADVANCE NOTIFICATION REQUIREMENTS MUST BE APPROVED BY THE PUBLIC WORKS DIRECTOR PRIOR TO SCHEDULING A SHUTDOWN.
- SHUTDOWN.

 32. WATER MAIN TAPS, SERVICE TAPS, SHUTDOWN REQUESTS, AND METER REQUESTS MUST BE INITIATED WITH THE CITY INSPECTOR A MINIMUM OF 5 WORKING DAYS IN

REVISED: DETAIL No. Charles Andrew WATER PLAN GENERAL NOTES 103P 07/16 CITY ENGINEER

GENERAL NOTES

WASTEWATER PLAN

GENERAL NOTES

- ALL WORK SHALL CONFORM TO MARICOPA ASSOCIATION OF GOVERNMENTS (MAG), & CITY OF PRESCOTT (COP) CONSTRUCTION STANDARDS & SPECIFICATIONS, WHICH ARE ON FILE IN THE OFFICE OF THE CITY ENGINEER.
 ALL EXISTING FRAMES, COVERS, VALVE BOXES, & MANHOLES SHALL BE EITHER REPLACED OR ADJUSTED TO FINISH GRADE DEPENDING ON PLAN CALL OUT UPON COMPLETION OF PAVING, UTILITY, OR RELATED CONSTRUCTION.
 ANY QUANTITIES SHOWN ON PLANS ARE NOT VERIFIED BY THE PUBLIC WORKS UTILITIES
- DIRECTOR.

 ACCEPTANCE OF THE COMPLETED WORK WILL NOT BE GIVEN UNTIL 3 MIL MYLAR & CAD FORMAT DIGITAL 'AS-BUILT' PLANS ON CITY OF PRESCOTT SURVEY DATUM & COORDINATES HAVE BEEN SUBMITTED & SEALED BY A REGISTERED PROFESSIONAL ENGINEER AND APPROVED BY THE PUBLIC WORKS DEPARTMENT.

 CITY OF PRESCOTT PUBLIC WORKS UTILITIES SHALL BE NOTIFIED A MINIMUM OF 24 HOURS PRIOR TO THE START OF ANY WORK.

 ALL WORK & MATERIALS WHICH DO NOT CONFORM TO THE SPECIFICATIONS ARE SUBJECT TO REMOVAL & REPLACEMENT AT THE CONTRACTOR'S EXPENSE.

 ANY WORK PERFORMED WITHOUT THE KNOWLEDGE OF THE CITY INSPECTOR OR HIS REPRESENTATIVE IS SUBJECT TO REMOVAL & REPLACEMENT AT THE CONTRACTOR'S EXPENSE.

- REPRESENTATIVE IS SUBJECT TO REMOVAL & REPLACEMENT AT THE CONTRACTOR'S EXPENSE.

 THE CONTRACTOR SHALL PROVIDE SUFFICIENT MEN, EQUIPMENT, & MATERIAL ON THE JOB AT ALL TIMES DURING CONSTRUCTION TO COMPLY WITH SPECIFICATIONS & TO COMPLETE THE WORK.

 CIP INSPECTION TO BE DONE BY THE CITY OF PRESCOTT PUBLIC WORKS DEPARTMENT OR THEIR REPRESENTATIVE. PRIVATE DEVELOPMENTS SHALL PROVIDE FOR INDEPENDENT 3RD PARTY INSPECTIONS.

 CONTRACTOR TO NOTIFY PROJECT ENGINEER 72 HOURS (3 WORKING DAYS) IN ADVANCE OF CONSTRUCTION TO SCHEDULE CONSTRUCTION CONTROL STAKING.

 THE CONTRACTOR IS TO UNCOVER ALL EXISTING LINES BEING TIED INTO AND VERIFY GRADES, MATERIAL, SIZE & ELEVATIONS BEFORE COMMENCING CONSTRUCTION & ORDERING MATERIALS.

 IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL UNDERGROUND PIPELINES, TELEPHONE & ELECTRICAL CONDUITS & STRUCTURES IN ADVANCE OF ANY CONSTRUCTION & OBSERVE ALL POSSIBLE PRECAUTIONS TO AVOID ANY DAMAGE TO SUCH. THE ENGINEER &/OR OWNER WILL NOT GUARANTEE ANY LOCATIONS AS SHOWN ON THESE PLANS, OR THOSE OMITTED FROM SAME.

 CONTRACTOR SHALL NOTIFY 'BLUE STAKE' AT 1—800—STAKEIT (1—800—782—5348) AT LEAST 48 HOURS PRIOR TO CONSTRUCTION.

 CONTRACTOR SHALL VERIFY ALL QUANTITIES SHOWN & MAKE HIS BID BASED UPON THOSE VERIFICATIONS. IF ANY DISCREPANCY IN QUANTITIES IS FOUND, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AS SUCH.

 ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY REQUIREMENTS SHALL APRILY WHEN

- WITH.

 ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY REQUIREMENTS SHALL APPLY WHEN MORE STRINGENT THAN THE MAG OR CITY OF PRESCOTT STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION; MORE SPECIFICALLY WHERE THEY PERTAIN TO MAXIMUM ALLOWABLE SEWER LINE/PRESSURE SEWER LINE EXFILTRATION—INFILTRATION RATES.

 ALL PLANS SIGNED BY THE CITY ARE NULL & VOID ONE YEAR FROM DATE OF SIGNATURE IF CONSTRUCTION HAS NOT STARTED AND/OR IS NOT ACTIVELY
- SIGNATURE IF CONSTRUCTION HAS NOT STARTED AND/OR IS NOT ACTIVELY PROGRESSING.

 PROJECT CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING TRAFFIC CONTROL PLANS WHICH SHALL BE MADE A PART OF THE PLAN REVIEW REQUEST TO THE CITY ENGINEER FOR APPROVAL.

 WATER—SEWER SEPARATION SHALL BE PURSUANT TO AAC R—18—5—502C.

 ALL TRENCHES & BEDDING SHALL BE PER COP DETAIL 200P & TECHNICAL SPECIFICATIONS.
- SPECIFICATIONS.

 21. ALL REVISIONS TO ORIGINAL PLANS MUST BE APPROVED BY THE PUBLIC WORKS DIRECTOR PRIOR TO CONSTRUCTION. ANY UNAPPROVED REVISIONS ARE SUBJECT TO REMOVAL & REPLACEMENT AT CONTRACTOR'S EXPENSE.

 22. SEWER FORCE MAIN LINES SHALL BE DESIGNED AND CONSTRUCTED OF A MATERIAL SUITABLE FOR SANITARY SEWER PRESSURE PIPE AS APPROVED BY THE CITY ENGINEER. SEWER LINES SHALL BE PRESSURE TESTED TO A MINIMUM OF 50 PSI ABOVE DESIGN WORKING PRESSURE AT THE LOWEST POINT IN THE SYSTEM FOR A MINIMUM OF 4 HOURS IN ACCORDANCE WITH AAC R18—9.

 23. SEWER LINE LOW PRESSURE AIR TESTS SHALL BE DONE ON 100% OF ALL LINES AFTER PLACEMENT OF BACKFILL TO PAVEMENT SUBGRADE. TEST EACH SEGMENT OF THE SEWER LINE FOR LEAKAGE USING THE APPLICABLE METHOD BELOW AND RECORD THE RESULTS:
- . "STANDARD TEST METHOD FOR INSTALLATION OF ACCEPTANCE OF PLASTIC GRAVITY SEWER LINES USING LOW-PRESSURE AIR, F1417-92(1998)" PUBLISHED BY THE AMERICAN SOCIETY FOR TESTING AND MATERIALS.

COP STANDARD DETAIL

24. SEWER MANHOLES EXFILTRATION TESTS SHALL BE DONE ON 100% OF ALL MANHOLES. VACUUM TESTING IN ACCORDANCE WITH CITY STANDARDS MAY BE USED IN LIEU OF EXFILTRATION TEST. THE CONTRACTOR SHALL TEST EACH MANHOLE USING ONE OF THE FOLLOWING TEST PROTOCOLS: 24A. WATERTIGHTNESS TESTING BY FILLING THE MANHOLE WITH WATER. THE CONTRACTOR SHALL ENSURE THAT THE DROP IN WATER LEVEL FOLLOWING PRESOAKING DOES NOT EXCEED 0.00034 OF THE TOTAL MANHOLE VOLUME PER HOUR

- PRESOAKING DOES NOT EXCEED 0.00034 OF THE TOTAL MANHOLE VOLUME PER HOUR.

 24B. NEGATIVE AIR PRESSURE TESTING USING THE "STANDARD TEST METHOD FOR CONCRETE SEWER MANHOLES BY NEGATIVE AIR PRESSURE" (VACUUM) TEST, C1244—02e1(2002), PUBLISHED BY THE AMERICAN SOCIETY FOR TESTING AND MATERIALS. THIS MATERIAL IS INCORPORATED BY REFERENCE & DOES NOT INCLUDE ANY LATER AMENDMENTS OR EDITIONS OF THE INCORPORATED MATERIAL, & MAY BE VIEWED AT THE ARIZONA DEPARTMENT OF ENVIRONMENTAL QUALITY, 1110 W. WASHINGTON, PHOENIX, AZ. 85007, OR OBTAINED FROM THE AMERICAN SOCIETY FOR TESTING & MATERIALS INTERNATIONAL, 100 BAR HARBOR DRIVE, WEST CONSHOHOCKEN, PA. 19428—2959.
- INTERNATIONAL, 100 BAR HARBOR DRIVE, WEST CONSHOHOCKEN, PA. 19428—2959.

 25. SEWER LINE DEFLECTION TESTS WITH AN APPROPRIATELY SIZED MANDREL SHALL BE DONE ON 100% OF ALL NON—RIGID PIPE LINES.

 26. THE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL SEWER MAINS AND LATERALS INSTALLED WITHIN THE CITY'S COLLECTION SYSTEM UTILIZING A SEWER CCTV SYSTEM AFTER COMPLETE BACKFILL AND COMPACTION BUT BEFORE INSTALLING ANY PORTION OF THE PAVEMENT STRUCTURAL SECTION. THE INSPECTION SHALL COMPLY WITH THE CITY'S VIDEO ACCEPTANCE PROCEDURE. THE CONTRACTOR SHALL PROVIDE 72 HOURS ADVANCE NOTICE FOR CITY STAFF TO BE PRESENT DURING THE VIDEO OPERATION AND SHALL PROVIDE THE CITY A VIDEO DVD AND HARD COPY OF THE INSPECTION REPORT UPON COMPLETION.

 27. COVER EACH SEWER LINE WITH AT LEAST 3 FEET OF EARTH COVER MEETING THE REQUIREMENTS "TRENCH EXCAVATION, BACKFILLING, & COMPACTION" (SECTION 601) REVISED 2004, PUBLISHED BY THE MARICOPA ASSOCIATION OF GOVERNMENTS; & "RIGID PIPE BEDDING FOR SANITARY SEWERS" (WWM 104) REVISED JULY 2002, PUBLISHED BY PIMA COUNTY WASTEWATER MANAGEMENT.
- PIPE BEDDING FOR SANITART SEWERS (WWW 104) REVISED BOLT 2002, 1 3023.120 0 PIMA COUNTY WASTEWATER MANAGEMENT.
 PRESSURE SEWER MAINS AND SERVICE LATERALS (LPS) SHALL BE SUBJECT TO A PRESSURE & LEAKAGE TEST IN ACCORDANCE WITH AWWA-C-600 STANDARD. TEST PRESSURE SHALL BE A MINIMUM OF 100 PSI, OR 50 PSI OVER WORKING PRESSURE, WHICHEVER IS GREATER. TESTING SHALL BE DONE AFTER BACKFILL TO SUBGRADE.

Charles Andrew

CITY ENGINEER

GENERAL GRADING AND PAVING NOTES:

Borrow material should be free of debris, organic materials, and three inch (3—inch) size particles or larger. We recommend fill material conform to the following general specification or approved equal:

U.S. STANDARD SIEVE PERCENT PASSING

> 3.0-inch NO. 40 NO. 200

40-60 0 - 30

The Plasticity Index should be between 2 and 15 unless otherwise specified in the project soils report.

- 2. All subgrade materials shall be scarified to a depth of eight inches (8"), the moisture content adjusted to near optimum, then compacted to 95 percent of
- 3. Sufficient compaction tests shall be taken to verify compliance with the project specifications.
- 4. Clearing and grubbing shall extend to the limits of grading and construction shall be in accordance with MAG Specifications, Section 201
- 5. Trench excavations, backfilling and compaction shall conform to MAG Specifications, Section 601, Type I, unless noted otherwise.


B. PAVING

- 1. All aggregate base course (ABC) shall be placed in 6 to 8—inch loose lifts, the moisture content adjusted to near optimum, then compacted to 98 percent of ASTM D-698.
- 2. All asphaltic concrete (A.C.) shall be 19 mm as per applicable MAG Specifications. Mix design shall be submitted to the City for approval prior to start of construction.
- 3. A.C. compaction shall be 95 percent of ASTM D-1559, 75 blow Marshall Density test.

GENERAL CONSTRUCTION NOTES:

- 1. The positions of existing underground utilities as shown on the construction plans were determined from site inspection, and other "Best Available" information. The Contractor shall contact "Blue Stake" for utility location and carefully excavate (including potholing if required) to determine the true horizontal and vertical positions of utilities. The contractor is responsible for protecting existing utilities and shall notify the owner of any conflicting conditions.
- 2. All existing underground utilities shown are approximate and are to be verified by each Subcontractor. Owner does not accept any responsibility for the accuracy of the location of existing utilities indicated on the Drawings. Verify location of existing utilities and exercise every precaution when working on or near these areas, to avoid damage to those existing facilities. Utility lines may be encountered in excavations that were not known (or shown to exist), so caution should be taken in all excavations. Active or inactive utilities encountered shall be handled in accordance with the requirements of the utility companies.
- 3. Prior to bidding the work, the Contractor shall thoroughly satisfy himself as to the actual conditions and requirements of the work. No claim shall be made against the Owner or the Engineer for any alleged misunderstanding of the conditions or nature of the work.
- 4. Nothing contained in the construction drawings shall create, nor shall be construed to create, any contractual relationship between the Engineer and the Contractor or any Subcontractor.
- 5. The Engineer will not be responsible for construction means, methods, techniques, sequences or procedures or for safety precautions or programs utilized in connection with the work.
- 6. It shall be the responsibility of the bidder to verify all quantities, including excavation, borrow, embankment, shrink or swell, ground compaction, haul and any other items affecting his bid and to base his bid per the intent of the bid schedule. It shall be the bidder's responsibility to notify the City prior to bidding of any discrepancies.
- 7. Disposal and/or stockpiling of excess material shall be done in such a way that will not create a nuisance. The placing of material on private property of another requires written authorization.
- 8. The contractor shall verify all pipe sizes and material at every point of connection prior to ordering material. Notify the City of any discrepancy in pipe size or material.

APPROVED TRAFFIC CONTROL PLAN AND R.O.W. PERMIT MUST BE OBTAINED FROM PUBLIC WORKS PRIOR TO BEGINNING WORK IN THE R.O.W.



7 ON S 1-038 ROAD , AZ

[C]

BUILDING
N: 103-01
-16 SIDE
PRESCOTT,

IAL AP 54

OMMER

NOTES

INC.

	_				П
ZAJ	ZAJ	GRK	5/8/23	23-014	
DRAWN	DESIGN	СНЕСК	DATE	# BOL 3WX	
HEET					

- ALL GRADING SHALL CONFORM TO THE CURRENT CITY ADOPTED EDITION OF THE INTERNATIONAL BUILDING CODE, AND CITY OF PRESCOTT LAND DEVELOPMENT CODE (REFERENCE CITY OF
- ALL PROVISIONS OF THE PRELIMINARY SOILS REPORT PREPARED BY _______ ETC _____, DATED APRIL 27, 2023 SHALL BE COMPLIED WITH DURING OPERATIONS. THIS PLAN IS FOR GRADING PURPOSES ONLY. APPROVAL OF THIS PLAN DOES NOT CONSTITUTE
- APPROVAL OF DRIVEWAY LOCATIONS OR SIZES, PARKING LOT LAYOUT, SEWER AND WATER FACILITIES, BUILDING LOCATIONS, OFF-SITE DRAINAGE FACILITIES OR OTHER ITEMS NOT RELATED DIRECTLY TO THE BASIC GRADING OPERATION. CERTIFICATION FROM THE REGISTERED CIVIL ENGINEER AND SOILS/GEOLOGICAL ENGINEER STATING THAT THE ROUGH GRADING HAS BEEN COMPLETED PER THE APPROVED PLAN, AND A
- COMPACTION REPORT FROM THE SOILS ENGINEER ON ANY FILL AREAS THAT ARE REQUIRED SHALL BE PROVIDED PRIOR TO BUILDING PERMITS BEING ISSUED. PARTIES NAMED ON ADEQ'S NOTICE OF INTENT (N.O.I.) ARE RESPONSIBLE FOR EROSION, DUST MUD, SILT, DEBRIS, AND TEMPORARY DRAINAGE CONTROL DURING GRADING OPERATIONS AND
- ANY ON-SITE RETAINING WALLS WILL REQUIRE APPROVAL AS PART OF THESE PLANS. ANY NECESSARY RETAINING WALLS ON THE PERIMETER OF THIS SITE MAY BE REQUIRED TO BE IN PLACE AND APPROVED BY THE CITY BUILDING DEPARTMENT PRIOR TO THE START OF GRADING. A SEPARATE PLAN WITH REQUIRED STRUCTURAL CALCULATIONS MAY BE REQUESTED FOR
- ANY INFRASTRUCTURE CONSTRUCTED IN THE PUBLIC RIGHT OF WAY WILL REQUIRE SEPARATE PLAN APPROVAL AND INSPECTION FROM THE CITY ENGINEER
- ANY WALLS, FENCES, STRUCTURES AND/OR APPURTENANCES ADJACENT TO THIS PROJECT SHALL BE PROTECTED IN PLACE. IF GRADING OPERATIONS DAMAGE OR ADVERSELY AFFECT SAID ITEMS IN ANY WAY, THE CONTRACTOR AND/OR DEVELOPER IS RESPONSIBLE FOR WORKING OUT AN ACCEPTABLE SOLUTION TO THE SATISFACTION OF THE AFFECTED PROPERTY OWNER(S).
- THE CONTRACTOR/DEVELOPER IS RESPONSIBLE FOR ENSURING THAT RETAINING WALLS DO NOT INTERFERE WITH PROVISION OF UTILITIES. WALLS MUST BE CONSTRUCTED ON SITE AND OUTSIDE OF THE RIGHT OF WAY. THIS SHALL INCLUDE THE FOOTINGS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT COMPACTION HAS BEEN ATTAINED ON THE ENTIRE GRADING SITE IN ACCORDANCE WITH THE GENERAL ENGINEERING PLAN, INCLUDING
- FILL AREAS OUTSIDE THE BUILDING PADS AND ON ALL FILL SLOPES, AND SHALL BE CERTIFIED BY CITY APPROVAL OF PLANS DOES NOT RELIEVE THE DEVELOPER FROM THE RESPONSIBILITY FOR CORRECTION OR ERROR OR OMISSION DISCOVERED DURING CONSTRUCTION. UPON REQUEST

THE REQUIRED PLAN REVISIONS SHALL BE PROMPTLY SUBMITTED TO THE CITY ENGINEER FOR

- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CALL THE CITY ENGINEER'S OFFICE AT (928) 777-1140 FOR ANY REQUIRED CIVIL INSPECTION 24 HOURS PRIOR TO PERFORMING ANY WORK. WORK PERFORMED WITHOUT CALLING FOR INSPECTION MAY BE REJECTED AND, IF REJECTED, SHALL BE REMOVED SOLELY AT THE CONTRACTOR'S EXPENSE.
- NO GRADING SHALL COMMENCE WITHOUT OBTAINING A GRADING PERMIT AND NOTIFYING THE CITY OF PRESCOTT OR DEVELOPER'S GRADING INSPECTOR TO SCHEDULE A PREGRADING
- MEETING TWO WORKING DAYS PRIOR TO THE START OF WORK. PRIOR TO THE START OF GRADING ALL SWPPP MEASURES SHALL BE IN PLACE, ALL DEBRIS INCLUDING EXISTING STRUCTURES, FOOTINGS, FOUNDATIONS AND RUBBLE SHALL BE REMOVED
- FROM THE SITE TO THE SATISFACTION OF THE SOILS ENGINEER. AFTER REMOVAL OF DEBRIS, ANY EXISTING FILL OR DISTURBED NATURAL SOILS SHALL BE
- EXCAVATED TO THE SATISFACTION OF THE SOILS ENGINEER.
- THE EXPOSED SOILS SHALL THEN BE INSPECTED BY THE SOILS ENGINEER, AND ANY ADDITIONAL OVER-EXCAVATION SHALL THEN BE MADE IN ACCORDANCE WITH THE SOILS ENGINEER'S RECOMMENDATIONS AND AS CONTAINED IN THE SOIL'S REPORT

- THE EXPOSED SOILS SHALL THEN BE SCARIFIED TO PROVIDE A BOND WITH NEW FILL, BROUGHT TO PROPER MOISTURE CONTENT AND COMPACTED TO AT LEAST 90% OF THE MAXIMUM DENSITY, AS DETERMINED BY ASTM D1557-78 OR EQUIVALENT COMPACTION SHALL BE COMPACTED TO AT LEAST
 SPECIFIED BY THE SOILS ENGINEER. ROAD PRISM SUBGRADE SHALL BE COMPACTED TO AT LEAST
- 18. THE SOILS AND DESIGN ENGINEER OF RECORD SHALL ALSO BE RESPONSIBLE TO INSPECT. VERIFY AND REPORT THAT PROPER COMPACTION HAS BEEN OBTAINED BY EARTHWORK CONTRACTOR O SUBCONTRACTOR AND PRIVATE UTILITY FRANCHISES CONCERNING UTILITY LINE BACKFILL, TO INCLUDE ELECTRICAL, GAS, CABLE, FIBEROPTIC AND LANDSCAPE IRRIGATION LINES ADDITIONALLY, WATER AND SEWER LINES TO BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH GENERAL ENGINEERING REQUIREMENTS SECTION AND DETAIL
- GRADING PLAN WITH THE PROPER STAMPS AND SIGNATURES ARE TO BE SUBMITTED TO THE CITY ENGINEER PRIOR TO RELEASE OF GRADING BOND AND PRIOR TO FINAL GRADING INSPECTION. BUILDING PAD CERTIFICATION SHALL BE SUBMITTED TO THE BUILDING DEPARTMENT WHEN
- 20. NO FILL SHALL BE PLACED UNTIL STRIPPING OF VEGETATION, REMOVAL OF UNSUITABLE SOILS, AND INSTALLATION OF SUBDRAINS (IF ANY) HAVE BEEN INSPECTED AND APPROVED BY THE SOILS
- ENGINEER MUST SET GRADE STAKES FOR ALL DRAINAGE DEVICES AND OBTAIN INSPECTION
- 22. GRADING SHALL NOT BE STARTED WITHOUT FIRST NOTIFYING CITY PUBLIC WORKS INSPECTION DEPARTMENT. A PRE-GRADING MEETING ON THE SITE IS REQUIRED BEFORE BEGINNING GRADING ACTIVITIES BY THE FOLLOWING PEOPLE PRESENT: OWNER, GRADING CONTRACTOR, DESIGN CIVIL ENGINEER, SOIL ENGINEER/GEOLOGIST, PUBLIC WORKS INSPECTOR, AND WHEN REQUIRED, THE ARCHAEOLOGIST AND PALEONTOLOGIST. THE REQUIRED INSPECTIONS FOR GRADING WILL BE EXPLAINED AT THE PRE-CONSTRUCTION MEETING.
- 23. ALL EXISTING FILLS SHALL BE APPROVED AND CERTIFIED BY THE SOILS ENGINEER OR REMOVED
- PRIOR TO PLACING ADDITIONAL FILLS. 24. ALL TRENCH BACKFILLS SHALL BE TESTED AND APPROVED BY THE SOIL ENGINEER.
- OF FIELD TESTING PERFORMED. EACH TEST SHALL BE IDENTIFIED WITH THE METHOD OF OBTAINING THE IN-PLACE DENSITY, WHETHER SAND CONE OR NUCLEAR GAUGE, AND SHALL BE SO
- 26. EXPORT SOIL MUST BE TRANSPORTED TO A LEGAL DUMP OR TO A PERMITTED SITE SHOWN
- 27. ALL EXISTING DRAINAGE COURSES THROUGH THIS SITE SHALL REMAIN OPEN UNTIL FACILITIES TO HANDLE STORM WATER ARE APPROVED AND FUNCTIONAL HOWEVER. IN ANY CASE, THE PERMITTEE SHALL BE HELD LIABLE FOR ANY DAMAGE DUE TO OBSTRUCTING NATURAL DRAINAGE

- A COPY OF THE APPROVED GRADING AND DRAINAGE PLAN FOR THIS PROJECT AND EROSION AND SEDIMENT CONTROL (ESC) PLAN OR STORM WATER POLLUTION PREVENTION PLAN (SWPPP) SHALL BE MAINTAINED ON THE SITE AND AVAILABLE FOR REVIEW. THOSE ELEMENTS OF THE GRADING AND DRAINAGE PLAN PERTINENT TO OR REFERENCED ON THE SWPPP SHALL BE CONSIDERED A PART OF THE SWPPP.
- THE ESC/SWPPP AND RELATED RECORDS MUST BE MADE AVAILABLE UPON REQUEST TO ADEQ AND THE CITY OF PRESCOTT.
- THE IMPLEMENTATION OF THESE PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE FACILITIES IS THE RESPONSIBILITY OF THE PERMITTEE/CONTRACTOR UNTIL ALL CONSTRUCTION IS APPROVED AND A NOTICE OF TERMINATION HAS BEEN SUBMITTED.
- THE SCHEMATIC EROSION CONTROL MEASURES SHOWN ON THE PLANS ARE A MINIMUM. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY MEANS TO PROTECT EXISTING FACILITIES AND ADJACENT PROPERTIES FROM NOISE, DUST, AND STORM WATER RUNOFF THROUGHOUT CONSTRUCTION OF THE PROJECT AND BUILDINGS ON LOTS, AND SHALL CONDUCT HIS OPERATIONS IN SUCH A MANNER THAT STORM WATER WILL BE CONTAINED ON SITE OR CHANNELED INTO A STORM DRAIN SYSTEM, PROVIDED THAT IT IS FREE FROM POLLUTANTS AND DEBRIS.
- CONTRACTOR SHALL PERMANENTLY STABILIZE ALL DISTURBED SLOPES AS STATED ON APPROVED CONSTRUCTION PLANS. ALL EROSION CONTROL STRUCTURES SHALL REMAIN IN PLACE UNTIL EXPOSED SLOPES HAVE BEEN PERMANENTLY STABILIZED.
- CONTRACTOR SHALL TAKE MEASURES TO PREVENT OR MINIMIZE THE GENERATION, EMISSION AND/OR TRANSPORT OF FUGITIVE DUST FROM CONSTRUCTION ACTIVITIES.
- THIS PLAN SHALL BE IN EFFECT UNTIL ALL DISTURBED AREAS ARE PERMANENTLY STABILIZED, TRANSFERRED TO NEW OWNERSHIP, OR DEVELOPED UNDER FUTURE PLANS WITH A NEW NOTICE OF INTENT (NOI), SWPPP, AND PERMIT. ONCE THE CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED AND THE SITE HAS MET THE FINAL STABILIZATION REQUIREMENTS OF THE PERMIT, THE AUTHORIZED SITE REPRESENTATIVE MAY FILE A NOTICE OR TERMINATION (NOT) WITH ADEQ, WITH A COPY SUBMITTED TO THE CITY OF PRESCOTT ENGINEERING DIVISION TO TERMINATE COVERAGE UNDER THE PERMIT.
- A CONCRETE WASHOUT SHALL BE INSTALLED FOR ALL PROJECTS THAT PROPOSE CONCRETE TO BE MIXED ON SITE OR BE DELIVERED FROM A BATCH PLANT. THE CONCRETE WASHOUT SHALL BE LOCATED A MINIMUM OF FIFTY (50) FEET FROM ANY DRAINAGE INFRASTRUCTURE OR NATURAL DRAINAGE FEATURES OR WATER BODIES AND INCORPORATE AN IMPERMEABLE LINER TO CONTAIN THE REQUIRED VOLUME. ALL DRIED CONCRETE WASTE SHALL BE BROKEN INTO MANAGEABLE PIECES AND DISPOSED OF OFF-SITE AT AN APPROVED FACILITY.

NOTES CITY ENGINEER 07/16 105P-1

COP STANDARD DETAIL

EROSION AND SEDIMENTATION CONTROL NOTES


Charles Andrew 07/16 CITY ENGINEER

REVISED: DETAIL No. 105P-2

THE CONTRACTOR SHALL SPOT LAYOUT THE ENTIRE PROJECT AND CONTACT THE CITY INSPECTOR TO MAKE ARRANGEMENTS FOR INSPECTION PRIOR TO INSTALLING TRAFFIC SIGNS OR PAVEMENT MARKINGS. ANY SIGNING OR STRIPING INSTALLED BEFORE LAYOUT APPROVAL SHALL BE SUBJECT TO REMOVAL AND REINSTALLATION AT THE CONTRACTOR'S EXPENSE.

- CONTRACTOR'S EXPENSE.
 TRAFFIC SIGN DIMENSIONS, COLORS AND LETTERING SHALL CONFORM TO THE LATEST MUTCD SPECIFICATIONS. TRAFFIC SIGN SIZE SHALL BE STANDARD UNLESS OTHERWISE SPECIFIED ON THE PLANS.
 SIGN LOCATION SHALL BE COORDINATED WITH LANDSCAPING PLANS TO ENSURE SIGN VISIBILITY PER AASHTO STANDARDS.
 ALL R1-1 "STOP" SIGNS AND PEDESTRIAN WARNING SIGNS SHALL BE RETRO-REFLECTIVE WITH SHEETING MATERIAL TO BE DIAMOND VIP GRADE, MEETING OR EXCEEDING ASTM 4956-04
- 4956-04.
 ALL OTHER SIGNS ARE TO BE RETRO-REFLECTIVE WITH SHEETING MATERIAL TO BE HIGH INTENSITY PRISMATIC MEETING OR EXCEEDING ASTM 4956-04.
 SIGN BLANKS SHALL BE 5052-H38 ALLOY TREATED ALUMINUM WITH ALODINE 1200 CONVERSION COATING, 0.080" THICK WITH ROUNDED CORNERS.
 SIGNS SHALL BE MOUNTED ON STREET LIGHT POLES WHENEVER FEASIBLE.
 STRIPING SHALL CONFORM TO THE MOST RECENT EDITION OF THE MUTCD WITH REGARD TO SIZE, COLOR, REFLECTIVITY AND PLACEMENT UNLESS OTHERWISE SPECIFIED ON THE
- THERMOPLASTIC APPLICATIONS SHALL CONFORM TO ADOT SPECIFICATION 704. TRANSVERSE MARKINGS, SYMBOLS AND LEGENDS SHALL BE 90 MIL (0.090 INCH) TO LONGITUDINAL MARKINGS SHALL BE 60 MIL (0.060 INCH) THICK ALKYD EXTRUDED THERMORIASTIC
- LONGITUDINAL MARKINGS SHALL BE 60 MIL (0.060 INCH) THICK ALKYD EXTRUDED THERMOPLASTIC.
 ALL PAINT APPLICATION SHALL CONFORM TO ADOT SPECIFICATION 708.
 ALL CONFLICTING STRIPING, PAVEMENT MARKINGS, AND CURB PAINT SHALL BE REMOVE BY WET SANDBLASTING OR OTHER APPROVED METHOD PRIOR TO THE INSTALLATION OF NEW STRIPING. SLURRY OR PAINT SHALL NOT BE USED TO COVER EXISTING PAINT. PAVEMENT THAT IS DAMAGED DUE TO THE REMOVAL OF MAKERS OR STRIPING SHALL BE REPAIRED TO THE SATISFACTION OF THE CITY ENGINEER OR HIS DESIGNEE.

COP STANDARD DETAIL	SIGNING AND STRIPING NOTES	Charles Andrews CITY ENGINEER	REVISED: 07/16	DETAIL No. 106P-1



1. Temporary straw wattles shall be installed prior to any grading work in the area to be protected. They shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization.

2. Anchors shall be rebar, steel pickets or 2" x 2" stakes, and shall be long enough to extend at least 1.5 to 2.0 feet into the ground when the top is flush.

(10) STRAW WATTLE BARRIER


EROSION CONTROL/SWPPP GENERAL NOTES

1. The Notice of Intent (NOI) shall be completed and submitted to the Arizona Department of Environmental Quality (ADEQ) prior to any construction activity (including clearing & grubbing and grading).

- 2. The prime contractor shall perform, at a minimum, a visual inspection of the construction site once every seven days and within 24 hours of rainfall greater than or equal to a half an inch (1/2-inch). The operator shall prepare a report documenting his/her findings on the conditions of the SWPPP controls and note any erosion problem areas. The operator's report is to be maintained on site by the operator. Facilities shall be maintained as necessary to ensure their continued functioning. In addition, all temporary siltation controls shall be maintained in a satisfactory condition until such time that construction is completed, permanent drainage facilities are operational, and the potential for erosion has passed as determined by the City Engineer or his designee.
- 3. The facilities shown on this plan must be constructed in conjunction with all clearing and grading activities in such a manner as to insure that sediment-laden water does not enter the drainage system or violate applicable water standards. Additionally, they must be installed and in operation prior to any grading or land clearing. Wherever possible, natural vegetation should be retained and maintained for silt and erosion
- 4. The general contractor to whom the "at-risk"/final grading permit will be issued must be included on the approved NOI issued by ADEQ.
- 5. The owner (operator)/contractor of the site must also maintain records with the following information: -The dates when major grading activities occur in a
- The dates when construction activities cease in an area, temporarily or permanently; and

removal of required BMP's.

- -The dates when an area is stabilized, temporarily or permanently; and -The dates when any maintenance/replacement or
- 6. Construction sites are dynamic in nature. The site operator is required to maintain full compliance with the general construction permit, as issued by ADEQ, to maintain an effective SWPPP. As such, this plan must be updated to accurately reflect site features and operations which may become evident during construction, and/or during or after rainfall events.
- The plan must also be amended if it is determined by the Design Engineer, or the City Engineer as not effective at minimizing pollutant discharges from the
- 7. Contractor shall hydro-seed all exposed slopes employing best management practices and/or recommended soil preparation to promote and sustain growth. All erosion control structures shall remain in place until exposed slopes have been permanently stabilized. Contractor shall be responsible for watering and maintaining hydro—seed until stabilized. Any deviation shall be approved by the engineer.
- 8. All site revegetation shall be completed within 90 days of completion of grading work, or prior to release of subdivision guarantee or issuance of Certificate of Occupancy, which ever occurs first. Permanent bank/slope stabilization shall be certified by the Project Engineer or Landscape Architect documenting the bank/slope stabilization was completed according to plan prior to final subdivision release or certificate of occupancy.
- 9. Contractor shall protect all permanent and existing storm water facilities from sediment/silt during
- 10. Silt fencing and/or other sediment control (i.e. straw baffles, hay bales, etc.) shall be used at the toe of any erodible slope, following contours of slope (do not install silt fence across any drainage course).
- 11. Contractor to coordinate erosion control/SWPPP implementation with the City's environmental coordinator.



HARD SURFACE PUBLIC ROAD

STABILIZED CONSTRUCTION ENTRANCE


COMMERCIAL BUILDING ON APN: 103-01-05 5416 SIDE ROA PRESCOTT, AZ

NOTES

INC.

TOPOGRAPHIC SURVEY OF A PORTION OF SEC. 31, T15N, R1W, G&SRB&M YAVAPAI COUNTY, ARIZONA

SITE INFO
APN 103-01-038
CURRENT OWNER: FRANCIS HECKETHORN
DEED RECORDED IN BOOK 464, PAGE 349
PHYSICAL ADDRESS: 5416 SIDE RD
PRESCOTT, AZ 86301



CERTIFICATION

I, G. MICHAEL HAYWOOD, DO HEREBY CERTIFY THAT I AM A REGISTERED LAND SURVEYOR IN THE STATE OF ARIZONA; THAT THIS PLAT REPRESENTS A SURVEY MADE UNDER MY DIRECT SUPERVISION DURING THE MONTH OF MAY 2021; THAT THE SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF; THAT THE BOUNDARY FORMS A MATHEMATICALLY CLOSED FIGURE; AND THAT ALL MONUMENTS SHOWN ACTUALLY EXIST OF THE DATE HEREOF AND THAT SAID MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED



BENCHMARK DATA

ELEVATIONS ESTBLISHED USING CITY OF PRESCOTT MINGO BASE IN NAVD 88 VERTICAL DATUM.

SITE BENCHMARK IS THE SOUTHEAST EASEMENT CORNER OF SUBJECT PARCEL BEING A 1/2" REBAR W/ CAP STAMPED LS 13941 W/ NAVD 88 EL = 5008.40'

NOTES

1' CONTOURS ARE ACCURATE TO ½ CONTOUR INTERVAL SHOWN

SUBECT PARCEL IS CURRENTLY ZONED CITY OF PRESCOTT SF-9. IT IS THE INTENT OF THIS LAND OWNER TO RE-ZONE THIS PARCEL. NO SETBACKS SHOWN ON THIS MAP

THIS SURVEYOR HAS MADE NO INVESTIGATION OR INDEPENDENT SEARCH FOR EASEMENTS, RIGHTS-OF-WAY, ENCUMBRANCES, RESTRICTIVE COVENANTS, OWNERSHIP TITLE EVIDENCE, OR ANY OTHER INFORMATION THAT AN ACCURATE AND CURRENT TITLE REPORT MAY DISCLOSE.


FEMA PANEL 04025C1693H -

SUBJECT PARCEL NOT AFFECTED BY FEMA FLOODPLAIN.

NO BLUE STAKE SERVICES WERE PROVIDED AND UNDERGROUND UTLILITIES MAY NOT BE SHOWN.


LEGEND


- = PROPERTY CORNER AS NOTED
- = EASEMENT CORNER AS NOTED
- (1) = FOUND 1/2" REBAR W/ CAP LS 23383
- (2) = FOUND 1/2" REBAR W/ CAP LS 13941
- (3) = SET 1/2" REBAR W/ CAP LS 13941 (4) = NOTHING FOUND OR SET DURING THIS SURVEY





NEXUS SOUTHWEST LLC REGISTERED LAND SURVEYORS 212 S. MARINA ST. PRESCOTT, AZ 86303 (928)778-5101 INFO@NEXUS-SW.NET


JOB NO. 21-542	DRAWN: PMH - 5/27/2021
CLIENT: HICKS	CHECK: GMH
CREW: JV/BV	CREW: 5/2021
SCALE = 1" : 10'	SHEET SIZE: 24X36"














DETENTION OUTLET STRUCTURE

WATER KEY

CONNECT TO EXISTING WATER MAIN. FURNISH AND INSTALL 8"X8"X8" TAPPING SLEEVE, 8" GATE VALVE, BOX AND COVER PER QC SD 301Q, 340Q-1, AND -2. FIELD VERIFY EXISTING PIPE, SIZE, LOCATION, INVERT, AND MATERIAL PRIOR TO CONSTRUCTION.

FURNISH AND INSTALL FULLY RESTRAINED (AT ALL JOINTS AND BENDS) 8" CLASS 350 PER AWWA C600 DUCTILE IRON PIPE (DIP) WATER MAIN. TRENCH PER QC SD 200Q-1.

FURNISH AND INSTALL COMPLETE FIRE HYDRANT
ASSEMBLY INCLUDING 8"X6"X8" TEE, 6" VALVE, BOX
AND COVER PER QC SD 301Q AND 391Q, HYDRANT
AND PIPING PER QC SD 360Q AND 362Q AND PER
AWWA AND ASTM STANDARDS.

FURNISH AND INSTALL BLIND FLANGE OR MECHANICAL PLUG.

FURNISH AND INSTALL 1" WATER SERVICE CONNECTION
ON NEW MAIN, WATER METER BOX AND COVER PER QC
SD 316P WITH CUSTOMER SHUTOFF AND PRESSURE
REDUCING VALVES. TRENCH EXCAVATION AND BACKFILL
PER QC SD 200Q-1 AND PLAN DETAILS.

FURNISH AND INSTALL COMPLETE 1" BACKFLOW

PREVENTION ASSEMBLY (BPA) ASSEMBLY PER QC SD 324Q-1 AND INTERNATIONAL BUILDING CODE (IBC). NO INTERCONNECTION ALLOWED BETWEEN WATER METER AND BPA ASSEMBLY. THE CONTRACTOR MUST SUBMIT SHOP DRAWINGS OF THE BPA ASSEMBLY AND ABOVE GROUND HOT BOX CLASS 1 PER ASSE 1060 PROTECTIVE ENCLOSURE PER IBC FOR SIGNED APPROVAL BY THE OWNER'S REPRESENTATIVE AND THE CITY OF PRESCOTT PRIOR TO INSTALLATION.

FURNISH AND INSTALL 1" SCHEDULE 40 PVC PRIVATE YARD LINE PER INTERNATIONAL PLUMBING CODE.

TRENCH EXCAVATION AND BACKFILL PER QC SD 200Q-1 AND PLAN DETAILS.

EXACT LOCATION OF 1" BUILDING CONNECTION PER PLUMBING PLANS.

SEWER KEY

CONNECT TO EXISTING SEWER MAIN PER COP SD
440P-1 AND 440P-3 WITH DOUBLE BARREL TWO-WAY
CLEANOUT AND BACKWATER VALVE WITH CAST IRON
COVER PER OC SD 2700. FIFLD VERIEY EXACT PIPE

CLEANOUT AND BACKWAIER VALVE WITH CAST INCINCTON
COVER PER QC SD 270Q. FIELD VERIFY EXACT PIPE
SIZE, INVERT, LOCATION, MATERIAL AND CONDITION
PRIOR TO CONSTRUCTION.

FURNISH AND INSTALL 4" SDR-35 PVC PRIVATE
BUILDING SEWER SERVICE PIPE, TRENCH EXCAVATION
AND BACKFILL PER MAG SPECIFICATION 601 AND QC SD
200Q-1 UTILITY TRENCH DETAIL.

FURNISH AND INSTALL SEWER SERVICE CLEANOUT PER QC SD 441Q AND PER INTERNATIONAL PLUMBING CODE.

FURNISH AND INSTALL DOUBLE BUILDING SEWER
CLEANOUTS PER PLUMBING PLANS AND CITY OF
PRESCOTT REQUIREMENTS WITH CAST IRON COVER PER
QC SD 270Q. EXACT LOCATION OF BUILDING

CONNECTION PER PLUMBING PLANS.

KELLEY/WISE ENGINEERING, INC.

146 GROVE AVENUE
PRESCOTT, ARIZONA 86301
(928) 771-1730
FAX 778-2220
gkelley@kelley-wise.com

(0015)DE MARKOPA COUNTY)


APN: 103-01-038 5416 SIDE ROAD PRESCOTT, AZ


SECTIONS





atsinad				
ZAJ	ZAJ	GRK	5/8/23	23-014
DRAWN	DESIGN	СНЕСК	DATE	KWE JOB #
C-301				


16 SIDE ROAD FILENAME: 23-014 CIVIL BASE.DWG PLOT DATE: 5/8/2023 9:43 AM SHEET SET: 3































L BUILDING ON S PN: 103-01-038 5416 SIDE ROAD PRESCOTT, AZ

COMMERCIAL

DETAILS

STANDARD


INC.


SPECIAL NOTES: THE STANDARD DETAILS AND SPECIFICATIONS SHOWN HEREON HAVE BEEN FORMALLY ADOPTED BY THE CITY OF PRESCOTT. COMPLIANCE WITH THESE STANDARD DETAILS AND SPECIFICATIONS IS REQUIRED IN CONSTRUCTING ALL APPLICABLE PUBLIC IMPROVEMENTS. KELLEY/WISE ENGINEERING IS NOT


ALL CONCRETE USED IN CONSTRUCTION OF THE STANDARD DETAIL CONCRETE IMPROVEMENTS AS SHOWN HEREON SHALL BE MINIMUM 4500 PSI CONCRETE WITH ENTRAINED AIR, WATER/CEMENT RATIO OF 0.45 AND 18% FLY ASH.


RESPONSIBLE FOR THE CONTENT OF THE CITY OF PRESCOTT STANDARD DETAILS AND SPECIFICATIONS.


se se la					
2	ZAJ	GRK	5/8/23	23-014	
	DESIGN	СНЕСК	DATE	KWE JOB #	
ΕE	T				











SPECIAL NOTES:

THE STANDARD DETAILS AND SPECIFICATIONS SHOWN HEREON HAVE BEEN FORMALLY ADOPTED BY THE CITY OF PRESCOTT. COMPLIANCE WITH THESE STANDARD DETAILS AND SPECIFICATIONS IS REQUIRED IN CONSTRUCTING ALL APPLICABLE PUBLIC IMPROVEMENTS. KELLEY/WISE ENGINEERING IS NOT RESPONSIBLE FOR THE CONTENT OF THE CITY OF PRESCOTT STANDARD DETAILS AND SPECIFICATIONS.

ALL CONCRETE USED IN CONSTRUCTION OF THE STANDARD DETAIL CONCRETE IMPROVEMENTS AS SHOWN HEREON SHALL BE MINIMUM 4500 PSI CONCRETE WITH ENTRAINED AIR, WATER/CEMENT RATIO OF 0.45 AND 18% FLY ASH.

meer (Civii)
CARY R. KELLEY KELLEY
Registere

INC.


ENGINEERING,

ROAD

SIDE

DETAILS

9	9	egiste)		
2AU	ZAJ	GRK	5/8/23	23-014
DRAWIN	DESIGN	СНЕСК	DATE	# BOL 3WX
HEE	T	口	<u>_</u>	<u> </u>



Pant Schedule									
SYMBOL	SIZE	QUANTITY	COMMON NAME / SCIENTIFIC NAME						
W.	1 GAL	18	RED YUCCA						
₩	1 GAL	6	PRAIRIE SAGE						
	5 GAL	18	BLUE CHIP JUNIPER						
	15 GAL	3	HONEY LOCUST						

LANDSCAPED AREAS:

SYSTEM.

TOTAL TREES PROVIDED: 3
TOTAL SHRUBS PROVIDED: 42

NOTES:


- LANDSCAPE PLANTINGS SHALL BE WATERED VIA DRIP IRRIGATION SYSTEM ON LANDSCAPE TIME CLOCK.
 PROVIDE BACKFLOW PREVENTOR FOR DRIP IRRIGATION
- 3. SPRAY ALL GROUND COVER AREAS W/ PRE-EMERGENT FOR WEED CONTROL.
- PROVIDE WEED BARRIER IN ALL PLANTER AREAS.
 GROUND COVER IN ALL PLANTER AREAS SHALL BE 3/4"
 COLORED ROCK, UNLESS NOTED OTHERWISE. WHERE
 SLOPES ARE TOO STEEP, PROVIDE 2" 3" FRACTURED RIP
 RAP OF MATCHING COLOR.
- 6. REFER TO CIVIL PLANS FOR GRADING AND DRAINAGE.

Descriptive Keynotes	
----------------------	--

- 1. PROVIDE LANDSCAPE TIMER.
- 2. PROPERTY LINE.
- 3. LANDSCAPE AREA. PROVIDE GROUND COVER. REFER TO PLANT SCHEDULE NOTES.
- 4. DOMESTIC SERVICE WATER METER IN YARD BOX. REFER TO CIVIL PLANS.
- 5. BACKFLOW PREVENTOR FOR LANDSCAPE IRRIGATION SYSTEM. PROVIDE 120V DEDICATED ELECTRICAL CIRCUIT WITH WEATHERPROOF GFCI DUPLEX OUTLET WITHIN ENCLOSURE.
- 6. 3/4" VALVED SCHEDULE 40 PVC STUB-OUT IN BELOW GRADE
- YARD BOX FOR LANDSCAPE IRRIGATION SYSTEM.

 7. ASPHALTIC PAVEMENT, REFER TO CIVIL PLANS.
- CAST-IN-PLACE CONCRETE CURB. REFER TO CIVIL PLANS.
 DETENTION AREA WITH RIP RAP, REFER TO CIVIL PLANS.
- 10. ABOVE GROUND PROPANE TANK.

11. ELECTRICAL TRANSFORMER.



W. Alan Kenson & Associates, P. P. 928-443-5812 P.O. Box 11593

REVISIONS

These drawings are the property of

W. Alan Kenson & Associates P.C.,

and may not be reproduced in any

way without the written consent of

W Alan Kenson & Associates, P.C.

Commercial Building on Side Rd. 1416 Side Rd. Prescott AZ 86301

PROJECT: Comme 5416 Sic

DRAWN BY
L.O.

CHECKED BY
W.A.K.


DATE
June 30th, 2023

JOB NO.
777

T.1.0


NOTE: SEAL ALL THREADED JOINTS / FITTINGS WITH APPROVED SEALANT PRIOR TO ASSEMBLY

Typical Electric Remote Control Valve




NOTE: ALLOW A MINIMUM 6" OF DRIP - LINE TUBING IN VALVE BOX IN ORDER TO DIRECT FLUSHED WATER OUTSIDE VALVE BOX.

B Typical Drip Line Flush Box



POINT AT THE HIGH POINT OF THE PLANTING WELL






NOTE: COIL ADDITIONAL 9" OF TUBING IN EMITTER BOX TO FACILITATE MAINTENANCE.


INSTALL A MINIMUM OF (1) MULTI-PORT EMITTER PER TREE - EQUALLY SPACED AROUND DRIP LINE OF TREE CANOPY TYPICAL. OPEN ADDITIONAL PORTS AND INSTALL SPAGHETTI DISTRIBUTION TUBING TO PROVIDE ADEQUATE WATER AS TREE MATURES, (TYP.)

FOR SLOPED CONDITIONS PLACE DISTRIBUTION POINT AT THE HIGH POINT OF PLANTING WELL.






Typical Shrub Planting on Slope




PLANTS SHALL BE INSPECTED FOR ROOTBOUND CONDITIONS BEFORE PLANTING. ANY ROOTBOUND PLANT SHALL BE REPLACED WITH SUITABLE PLANT.


Typical Shrub Planting



C2 Typical Boulder Detail








NOTE: STAKE TREE PERPENDICULAR TO DIRECTION OF PREVAILING WIND.

PLANTS SHALL BE INSPECTED FOR ROOTBOUND CONDITIONS BEFORE PLANTING.
ANY ROOTBOUND PLANT SHALL BE REPLACED WITH SUITABLE PLANT.

Typical Tree Planting on Slope



NOTE: STAKE TREE PERPENDICULAR TO DIRECTION OF PREVAILING WIND.

PLANTS SHALL BE INSPECTED FOR ROOTBOUND CONDITIONS BEFORE PLANTING. ANY ROOTBOUND PLANT SHALL BE REPLACED WITH SUITABLE PLANT.



Kenson & Associates, P.

812 P.O. Box 11593
815 Prescott, AZ 86304

928-4 928-4

REVISIONS

These drawings are the property of

W. Alan Kenson & Associates P.0

and may not be reproduced in any

way without the written consent of

V_Alan Kenson & Associates, P.0

Commercial Building on Side Rd. 5416 Side Rd. Prescott, AZ 86301

PROJECT: Comm 5416 S

DRAWN BY
L.O.


CHECKED BY
W.A.K.

DATE
June 30th, 2023

JOB NO.
777

SHEET

L1.1



Detention Area Section SCALE: 1/2" = 1'-0"



SCALE: 1/2" = 1'-0"


Descriptive Keynotes

- PROPERTY LINE.
- 2. BUILDING SETBACK LINE.
- 3. EASEMENT LINE.
- 4. THE MAXIMUM SLOPE OF THE A.D.A. ACCESSIBLE PARKING AREA SHALL NOT EXCEED 2% AND THE SLOPE OF THE DOORWAY LANDING AND ACCESSIBLE ROUTE TO PUBLIC ACCESS SHALL NOT EXCEED 2%.
- 5. PROPOSED CONCRETE PAVEMENT OVER COMPACTED A.B.C., REFER TO CIVIL PLANS.
- 6. PROPOSED FIRE HYDRANT, REFER TO CIVIL PLANS.
- PROPOSED ADA ACCESSIBLE PARKING.
- 8. PROPOSED CAST IN PLACE CONCRETE CURB, REFER TO CIVIL
- 9. PROPOSED CONCRETE RETAINING WALL.
- 10. PROPOSED 6'-0" LONG, 4" DIAMETER, CONCRETE FILLED, PROTECTIVE STEEL BOLLARDS, EMBEDDED 2'-0" BELOW GRADE INTO CONCRETE FOOTING, TYPICAL AT EACH ROLL-UP DOOR AND AS INDICATED ELSEWHERE.
- 11. PROPOSED ELECTRICAL SERVICE ENTRANCE SECTION.
- 12. PROPOSED DB 120 ELECTRICAL CONDUIT.
- 13. PROPOSED DB 120 CATV CONDUIT.
- 14. 3/4" VALVED SCHEDULE 40 PVC STUB-OUT IN BELOW GRADE YARD BOX FOR LANDSCAPE IRRIGATION SYSTEM.
- 15. PROPOSED REDUCED PRESSURE BACKFLOW PREVENTION DEVICE IN ASSE HOT BOX.
- 16. PROPOSED DOMESTIC WATER METER.
- 17. PROPOSED WATER SHUT OFF VALVE.
- 18. LANDSCAPE TIMER.
- 19. ABOVE GROUND PROPANE TANK.
- 20. PROPOSED ASPHALTIC PAVEMENT, REFER TO CIVIL PLANS.
- 21. PROPOSED TWO WAY SEWER CLEANOUT AND BACKWATER VALVE.
- 22. PROPOSED ELECTRIC TRANSFORMER.
- 23. 4" COMPACTED ABC.
- 24. PROPOSED DETENTION AREA, REFER TO CIVIL PLANS.
- 25. PROPOSED PARKING SPACE, TYPICAL.
- 26. PROPOSED LANDSCAPE AREA, REFER TO LANDSCAPE PLAN.
- 27. PROPOSED DRIP IRRIGATION SYSTEM BACKFLOW PREVENTOR IN HOT BOX.

PARKING CALCULATIONS

STORAGE 2,625 S.F. / 500 S.F. = 5.2 PARKING SPACES

TOTAL PARKING SPACES PROVIDED =5



Architectural Site Plan



ates Ci

REVISIONS

These drawings are the property of


W. Alan Kenson & Associates P.C.,

and may not be reproduced in any

way without the written consent of

W Alan Kenson & Associates, P.C.

CHECKED BY W.A.K. June 30th, 2023




REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C.,

and may not be reproduced in any way without the written consent of W Alan Kenson & Associates, P.C.

CHECKED BY W.A.K. June 30th, 2023



W. Alan Kenson & Associates, P.C.

P 928-443-5812
P.O. Box 11593
F 928-443-5815
Proceedy A7.86304

High Window Plan

T: Commercial Building on Side Rd

PROJECT: CO


DRAWN BY
L.O.

CHECKED BY
W.A.K.

DATE
June 30th, 2023

JOB NO.
777
SHEET

A2.1



REVISIONS

These drawings are the property of


W. Alan Kenson & Associates P.C., and may not be reproduced in any


way without the written consent of W Alan Kenson & Associates, P.C.

CHECKED BY W.A.K.

June 30th, 2023 JOB NO. **777**

A3.0







1. PROVIDE ELECTRICAL SERVICE ENTRANCE SECTION, REFER TO ELECTRICAL PLANS.

2. HOLLOW METAL DOOR, REFER TO REFERENCE

FLOOR PLAN AND DOOR SCHEDULE.

3. ROLL-UP DOOR, REFER TO REFERENCE FLOOR

PLAN AND DOOR SCHEDULE.
4. PROVIDE SHEET METAL GUTTER, REFER TO METAL

BUILDING PLANS.
5. PROVIDE SHEET METAL DOWNSPOUT, REFER TO

METAL BUILDING PLANS.

6. PROVIDE SHEET METAL CORNER TRIM, REFER TO METAL BUILDING PLANS.7. 4" STEEL CONCRETE FILLED BOLLARDS, 4'-0" ABOVE

CONCRETE WITH 2'-0" EMBEDDED INTO CONCRETE FOOTING BELOW, TYPICAL.

8. EXTERIOR WINDOW. REFER TO HIGH WINDOW PLAN AND WINDOW TYPES.

9. LOCATION OF CROSS BRACING, REFER TO METAL BUILDING PLANS.

10. PROVIDE SHEET METAL SIDING PANELS, REFER TO METAL BUILDING PLANS.

11. PROVIDE SHEET METAL ROOF PANELS, REFER TO METAL BUILDING PLANS.

12. EVAPORATIVE COOLER, REFER TO MECHANICAL PLANS.

13. LIGHT FIXTURE, REFER TO ELECTRICAL PLANS.

enson & Associate
P.O. Box 11593

REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C.,

and may not be reproduced in any

way without the written consent of

P 928-443-5812 F 928-443-5815 email: waka@cab

> mmercial Building on Side Rd. 16 Side Rd. sscott, AZ 86301

ROJECT: Commer 5416 Sic

DRAWN BY
L.O.

CHECKED BY
W.A.K.

DATE
June 30th, 2023

Job No. 777


44.0


Jul 10, 2023 - 12:30pm

Descriptive Keynotes 🔾



- 1. HOLLOW METAL DOOR, REFER TO REFERENCE FLOOR PLAN AND DOOR SCHEDULE.
- 2. ROLL-UP DOOR, REFER TO REFERENCE FLOOR PLAN AND DOOR SCHEDULE.
- 3. PROVIDE SHEET METAL GUTTER, REFER TO METAL BUILDING PLANS.
- 4. PROVIDE SHEET METAL DOWNSPOUT, REFER TO METAL BUILDING PLANS.
- 5. PROVIDE SHEET METAL CORNER TRIM, REFER TO METAL BUILDING PLANS.
- 6. 4" STEEL CONCRETE FILLED BOLLARDS, 4'-0" ABOVE CONCRETE WITH 2'-0" EMBEDDED INTO CONCRETE FOOTING BELOW, TYPICAL.
- 7. LOCATION OF CROSS BRACING, REFER TO METAL BUILDING PLANS.
- 8. RELIEF AIR LOUVERS, REFER TO MECHANICAL PLANS.
- 9. PROVIDE SHEET METAL SIDING PANELS, REFER TO METAL BUILDING PLANS.
- 10. EVAPORATIVE COOLER, REFER TO MECHANICAL PLANS.
- 11. LIGHT FIXTURE, REFER TO ELECTRICAL PLANS.





West Elevation

B East Elevation

REVISIONS

These drawings are the property of


W. Alan Kenson & Associates P.C.,

and may not be reproduced in any

way without the written consent of

DRAWN BY
L.O.
CHECKED BY
W.A.K.

June 30th, 2023 JOB NO. **777**






- 1. LIGHT FIXTURE(S) SHOWN FOR QUANTITY AND LOCATION ONLY. REFER TO ELECTRICAL PLANS.
- 2. PROVIDE PROPANE UNIT HEATER, REFER TO MECHANICAL PLANS.
- 3. PROVIDE EVAPORATIVE COOLER, REFER TO MECHANICAL PLANS.
- 4. ROOF PURLIN, REFER TO METAL BUILDING
- 5. PROVIDE 2x8 CEILING JOIST @ 2'-0" O.C.6. ELECTRICAL PANEL.
- STACKABLE WASHER/DRYER, BY OWNER.
 PROVIDE 5/8" GPDW CEILING.







Reflected Ceiling Plan



REVISIONS


These drawings are the property of W. Alan Kenson & Associates P.C.,

and may not be reproduced in any


way without the written consent of


CHECKED BY W.A.K. June 30th, 2023

JOB NO. **777**




Ardy	Randware Schedule								
<u>HW-01</u>	LEVER ENTRY LOCK, CHAIN STOP, WEATHER STRIP, THRESHOLD, DOOR BOTTOM, HINGES								
HW-02	LEVER PRIVACY LOCK, WALL STOP, HINGES								
<u>HW-03</u>	ROLL-UP DOOR								
HW-04	LEVER PASSAGE LOCK WALL STOP, HINGES								





	STORAGE 101
STORAGE 100	
CORRIDOR 104	STORAGE 102

NO. ROOM NAME	FLOOR	BASE	WALLS	CEILING	HEIGH
100 STORAGE	F1	B1/B2	W1/W2	C1	VARIES
101 STORAGE	F1	B1	W1	C1	VARIES
102 STORAGE	F1	B1	W1	C1	VARIES
103 RESTROOM	F1	B1/B2	W2/W3	C2	8'-0"
104 CORRIDOR	F1	B1/B2	W2	C2	8'-0"
B2 RUBBER BASE			E PEN TO STRI INTED GPDI		



Room Finish Plan



ates Ci

REVISIONS

These drawings are the property of

W. Alan Kenson & Associates P.C., and may not be reproduced in any

way without the written consent of

W. Alan Kenson & Associates, P.C.

HARDWARE TYPE

03

03

01

03

01


03

02

01

04

CHECKED BY W.A.K. June 30th, 2023



WAREHOUSE COMBUSTION AIR CALC

WAREHOUSE VOLUME

1795 FT. SQ. X 16 FT. = 28,720 CU. FT.

TOTAL GAS MBH

UH-1 60 MBH (60,000 BTU/H)

VOLUME PER MBH


28,720 CU. FT. / 60 MBH = 478 FT. CU./MBH

VOLUME PER MBH IS MORE THAN 50 FT. CU./MBH

COMBUSTION AIR DELIVERED VIA INFILTRATION

KEYNOTES

- 1) SIDE DRAFT EVAPORATIVE COOLER MOUNTED ON FIELD FABRICATED WALL BRACKET. UNIT SHALL BE COMPLETE WITH CIRCULATING PUMP AND PUMP/FAN CONTROLS. PROVIDE 3/4" DRAIN AND 1/2" WATER TO EVAP COOLER, SEE PLUMBING PLANS.
- 2 PUMP/FAN EVAPORATIVE COOLER CONTROL(S).
- 3 CEILING MOUNTED EXHAUST FAN WITH BACKDRAFT DAMPER. TRANSITION EXHAUST DUCT FROM UNIT DISCHARGE AND ROUTE TO MANUFACTURER'S WALL DISCHARGE. MAINTAIN A MINIMUM 10' CLEARANCE FROM ALL OUTSIDE AIR INTAKES.
- 4) GAS-FIRED UNIT HEATER SUPPORTED FROM STRUCTURE, WITH TYPE "B" FLUE UP THROUGH ROOF. COORDINATE UNIT HEATER MOUNTING HEIGHT.
- 5 PROVIDE UNIT HEATER WITH LOW VOLTAGE THERMOSTAT WITH INSULATED SUB-BASE.
- 6 48x60 RELIEF LOUVER WITH BAROMETRIC BACKDRAFT DAMPER BALANCED TO OPEN WITH EVAPORATIVE COOLER OPERATION.
- 7) EVAP DUCT OPEN DISCHARGE.
- 8 4" RIGID DRYER DUCT WITH RECESSED DRYER BOX RECEPTACLE. INSTALL PER CODE TO WALL DISCHARGE. MAXIMUM LENGTH SHALL NOT EXCEED 35 FEET (EXCEPT AS ALLOWED BY DRYER MANUFACTURER'S INSTALLATION INSTRUCTIONS). EXHAUST DUCT SHALL BE SECURED TO FRAMING MEMBERS WITH STRAPS AND NOT CONNECTED OR SECURED USING SCREWS OR OTHER FASTENING MEANS WHICH EXTEND INTO DUCT. PROVIDE DRYER DISCHARGE CAP, WITH BACKDRAFT DAMPER. DRYER BOX INSTALLATION SHALL MAINTAIN WALL FIRE RATING.




Mechanical Floor Plan

Design Group, LLC consulting Engineers

REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C.



SS

CHECKED BY **DATE** March 24th, 2023

MECHANICAL SPECIFICATIONS

GENERAL REQUIREMENTS

GENERAL PROVISIONS WHICH MAKE SPECIFIC REFERENCE TO ELECTRICAL DIVISION ONLY ARE INCLUDED HEREIN FOR CLARITY AND PERIOD OF ONE YEAR, FROM DATE OF ACCEPTANCE OF WORK BY SIMPLIFICATION OF SPECIFICATIONS WRITING AND ARE NOT PART OF OWNER IN WRITING, TO BE FREE OF DEFECTS OF MATERIALS AND THE MECHANICAL WORK. THE WORK OF DIVISION 15, MECHANICAL, IS SUBJECT TO THE CONDITIONS OF THE CONDITIONS OF THE CONTRACT, DIVISION 1, GENERAL REQUIREMENTS, AND APPLICABLE EXAMINE AND BECOME FAMILIAR WITH ALL CONTRACT DOCUMENTS AND COORDINATE THE MECHANICAL WORK ACCORDINGLY.

IT IS THE INTENTION OF THE SPECIFICATIONS AND DRAWINGS TO CALL FOR FINISHED WORK, TESTED AND READY FOR OPERATION. ANY APPARATUS, APPLIANCE, MATERIAL OR WORK NOT SHOWN ON THE DRAWINGS. BUT MENTIONED IN THE SPECIFICATIONS OR VICE VERSA, OR ANY INCIDENTAL ACCESSORIES NECESSARY TO MAKE THE WORK COMPLETE AND READY FOR OPERATION, EVEN IF NOT PARTICULARLY SPECIFIED, SHALL BE PROVIDED WITHOUT ADDITIONAL EXPENSE TO THE OWNER. SHALL THERE APPEAR TO BE DISCREPANCIES OR QUESTIONS OF INTENT IN THE CONTRACT. DOCUMENTS, REFER THE MATTER TO THE ARCHITECT FOR HIS DECISION BEFORE ORDERING ANY MATERIALS OR EQUIPMENT OR BEFORE THE START OF ANY RELATED WORK. THE DECISION OF THE ARCHITECT SHALL BE FINAL, CONCLUSIVE AND BINDING.

DRAWINGS ARE GENERALLY DIAGRAMMATIC AND ARE INTENDED TO DRAWINGS ARE GENERALLY DIAGRAMMATIC AND ARE INTENDED TO <u>VERIFICATION OF DIMENSIONS:</u>
CONVEY SCOPE OF WORK AND TO INDICATE GENERAL ARRANGEMENT SCALED AND FIGURED DIMENSIONS ARE APPROXIMATE ONLY. OF EQUIPMENT, DUCTS, CONDUITS, PIPING AND FIXTURES. THEY STRUCTURAL DIFFICULTY THAT MAY BE ENCOUNTERED DURING INSTALLATION OF THE WORK. LOCATION OF ALL ITEMS NOT DEFINITELY FIXED BY DIMENSIONS ARE APPROXIMATE ONLY. EXACT LOCATIONS NECESSARY TO SECURE BEST CONDITIONS AND RESULTS MUST BE DETERMINED AT PROJECT AND SHALL HAVE APPROVAL OF ARCHITECT BEFORE BEING INSTALLED. DO NOT SCALE DRAWINGS. IF SO DIRECTED BY ARCHITECT, WITHOUT EXTRA CHARGE, MAKE REASONABLE MODIFICATIONS IN LAYOUT AS NEEDED TO PREVENT CONFLICT WITH WORK OF OTHER TRADES OR FOR PROPER EXECUTION OF WORK. INCLUDE MINOR DETAILS NOT USUALLY SHOWN OR SPECIFIED, BUT NECESSARY FOR PROPER INSTALLATION AND OPERATION OF A SYSTEM OR PIECE OF EQUIPMENT IN BID

INCLUDE IN WORK, WITHOUT EXTRA COST TO OWNER, LABOR, MATERIALS, SERVICES, APPARATUS, DRAWINGS (IN ADDITION TO CONTRACT DRAWINGS AND DOCUMENTS) REQUIRED TO COMPLY WITH APPLICABLE LAWS, ORDINANCES, RULES AND REGULATIONS. DRAWINGS AND SPECIFICATIONS TAKE PRECEDENCE WHEN THEY ARE COMPLY WITH ALL APPLICABLE CODES, RULES AND REGULATIONS. MORE STRINGENT THAN CODES, ORDINANCES, STANDARDS AND STATUTES. CODES, ORDINANCES, STANDARDS AND STATUES TAKE PRECEDENCE WHEN THEY ARE MORE STRINGENT OR CONFLICT WITH DRAWINGS OR SPECIFICATIONS. FOLLOWING INDUSTRY STANDARDS, SPECIFICATIONS AND CODES ARE MINIMUM REQUIREMENTS:

A. APPLICABLE CITY, COUNTY, AND STATE MECHANICAL, ELECTRICAL, GAS, PLUMBING, HEALTH AND SANITARY CODES, LAWS AND ORDINANCES. B. CITY OR OTHER APPLICABLE BUILDING CODES.

C. 2018 INTERNATIONAL MECHANICAL CODE WITH LOCAL

INSPECTED AND APPROVED BY LOCAL AUTHORITIES.

PRODUCTS HAVE LOCAL REPRESENTATION.

AMENDMENTS. D. REGULATIONS, PERMITS, INSPECTIONS: COMPLY WITH ALL APPLICABLE CODED, RULES AND REGULATIONS. ALL MATERIALS, EQUIPMENT AND WORK MUST CONFORM TO THE INTERNATIONAL MECHANICAL CODE. OBTAIN AND PAY FOR ALL REQUIRED PERMITS AND LICENSES. WHEN REQUIRED BY CODE, ALL WORK MUST BE

MATERIALS AND EQUIPMENT STANDARD PRODUCTS OF A REPUTABLE MINIMUM OF 1/8" PER FOOT. MANUFACTURER REGULARLY ENGAGED IN MANUFACTURE OF THE SPECIFIED ITEMS. WHERE MORE THAN ONE UNIT IS REQUIRED OF ANY ITEM, FURNISHED BY THE SAME MANUFACTURER, EXCEPT WHERE SPECIFIED OTHERWISE. INSTALL MATERIAL AND EQUIPMENT IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. SHOULD VARIANCE BETWEEN PLANS AND SPECIFICATIONS OCCUR WITH THESE, CONTACT ARCHITECT IMMEDIATELY SO THAT VARIATIONS IN INSTALLATION CAN BE KNOWN BY ALL PARTIES CONCERNED. PROVIDE EQUIPMENT FROM MANUFACTURER WHOSE

EXECUTION

PROTECT EXISTING ACTIVE SERVICES (WATER, GAS, SEWER, ELECTRIC) WHEN ENCOUNTERED, AGAINST DAMAGE FROM CONSTRUCTION WORK. DO NOT PREVENT OR DISTURB OPERATION OF ACTIVE SERVICES WHICH ARE TO REMAIN. IF WORK MAKES TEMPORARY SHUTDOWNS OF SERVICES UNAVOIDABLE, CONSULT WITH OWNER AS TO DATES, PROCEDURES, AND ESTIMATED DURATION OF AT LEAST 10 WORKING DAYS IN ADVANCE OF DATE WHEN WORK IS TO BE PERFORMED. ARRANGE WORK FOR CONTINUOUS PERFORMANCE TO ASSURE THAT EXISTING OPERATING SERVICES WILL BE SHUT DOWN ONLY DURING THE TIME REQUIRED TO MAKE NECESSARY CONNECTIONS. IF A SYSTEM CANNOT SHUT DOWN, INSTALL TEMPORARY BYPASSES OR JUMPERS UNTIL CONNECTIONS ARE COMPLETE. CONTRACTOR RESPONSIBLE FOR ALL COSTS INCURRED BY ABOVE SHUTDOWNS, INCLUDING BYPASS OR JUMPER INSTALLATIONS, FOR WORK PERFORMED UNDER THIS SECTION. IF EXISTING ACTIVE UTILITY SERVICES ARE ENCOUNTERED WHICH REQUIRE RELOCATION, MAKE REQUEST TO PROPER AUTHORITIES FOR DETERMINATION OF PROCEDURES. PROPERLY TERMINATE EXISTING SERVICES TO BE ABANDONED IN CONFORMANCE WITH REQUIREMENTS OF AUTHORITIES. WHERE CONNECTIONS OR DISRUPTIONS ARE MADE TO EXISTING SYSTEMS, REACTIVATE, REFILL, AND RECHARGE ALL COMPONENTS AND RESTORE SYSTEMS TO OPERATING CONDITIONS AT TIME OF DISRUPTION.

EACH COMPLETE SYSTEM GUARANTEED BY CONTRACTOR FOR A WORKMANSHIP, AND TO PERFORM SATISFACTORILY UNDER ALL CONDITIONS OF LOAD OR SERVICE. THE GUARANTEES PROVIDE THAT ANY ADDITIONAL CONTROLS, PROTECTIVE DEVICES, OR REQUIREMENTS OF OTHER PORTIONS OF THE CONTRACT DOCUMENTS. EQUIPMENT BE PROVIDED AS NECESSARY TO MAKE THE SYSTEM OF EQUIPMENT OPERATE SATISFACTORILY, AND THAT ANY FAULTY MATERIALS OR WORKMANSHIP BE REPLACED OR REPAIRED. ON FAILURE OF GUARANTOR TO DO THE ABOVE AFTER WRITTEN NOTICE FROM OWNER, THE OWNER MAY HAVE THE WORK DOWN AT THE COST OF GUARANTOR. LOSS OF REFRIGERANT IS CONSIDERED A DEFECT IN WORKMANSHIP AND/OR EQUIPMENT, TO BE CORRECTED AS REQUIRED AT NO EXTRA COST TO THE OWNER. PROVIDE EXTENDED FIVE (5) YEAR FACTORY PARTS & LABOR WARRANTY ON ALL AIR CONDITIONING COMPRESSORS.

AIR CONDITIONING, HEATING AND VENTILATING

WORK UNDER THIS SECTION INCLUDES FURNISHING ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR THE REMODELING, INSTALLATION AND PLACING INTO OPERATION THE HEATING, VENTILATING AND AIR CONDITIONING WORK AS SPECIFIED HEREIN AND INDICATED ON THE DRAWINGS.

BEFORE PROCEEDING WITH WORK, CAREFULLY CHECK AND VERIFY ARE NOT INTENDED TO SHOW EVERY OFFSET OR FITTINGS OR EVERY AT THE SITE, AND RESPONSIBLE FOR PROPERLY FITTING EQUIPMENT AND MATERIALS TOGETHER AND TO THE STRUCTURE IN SPACES PROVIDED. DRAWINGS ARE ESSENTIALLY DIAGRAMMATIC AND MANY OFFSETS, BENDS, SPECIAL FITTINGS AND EXACT LOCATIONS ARE NOT INDICATED. CAREFULLY STUDY DRAWINGS AND PREMISES I ORDER TO DETERMINE BEST METHODS, EXACT LOCATIONS, ROUTES AND BUILDING OBSTRUCTIONS, PRESERVE HEADROOM, AND KEEP OPENINGS AND PASSAGEWAYS CLEAR.

CUTTING AND PATCHING:

CUT EXISTING WORK AND PATCH AS NECESSARY TO PROPERLY INSTALL THE NEW WORK. AS THE WORK PROGRESSES, LEAVE NECESSARY OPENINGS, HOLES AND CHASES, ETC., IN THEIR CORRECT LOCATIONS. IF THE REQUIRED OPENINGS, HOLES AND CHASES ETC., ARE NOT IN THEIR CORRECT LOCATIONS, MAKE THE NECESSARY CORRECTIONS AT NO COST TO THE OWNER. AVOID EXCESSIVE CUTTING AND DO NOT CUT STRUCTURAL MEMBERS WITHOUT CONSENT OF ARCHITECT.

REGULATIONS, PERMITS & INSPECTIONS

ALL MATERIALS, EQUIPMENT AND WORK MUST CONFORM TO THE INTERNATIONAL MECHANICAL CODE. OBTAIN AND PAY FOR ALL REQUIRED PERMITS AND LICENSES. WHEN REQUIRED BY CODE, ALL WORK MUST BE INSPECTED AND APPROVED BY LOCAL AUTHORITIES.

ALL DUCTWORK FABRICATED AS PER LATEST INTERNATIONAL MECHANICAL CODE REQUIREMENTS AND SMACNA MANUAL. EXTENSION OF EXISTING DUCTWORK SHALL BE MADE WITH SOME MATERIAL. DUCTWORK SHALL BE CONSTRUCTED OF NEW HOT-DIPPED GALVANIZED SHEET METAL ASTM A-120 FOR EACH SIDE. TAPE ALL CROSS-JOINTS IN SHEET METAL DUCT WITH HARDCAST. TAKE-OFF FITTINGS SHALL BE CONICAL SPIN-IN WITH QUADRANT DAMPER. TURNING VANES SHALL BE INSTALLED IN ALL

HVAC EQUIPMENT CONDENSATE DRAINS USE TYPE M COPPER TUBING AND WROUGHT COPPER MECHANICAL FITTINGS. EXTEND DRAINS TO NEAREST ROOF DRAIN OR LAVATORY TAIL-PIECE (FURNISHED BY PLUMBER). SLOPE DRAIN AT A

	UNIT HEATER SCHEDULE													
EQUIP.			Е	BLOWER		MO	TOR		HEATER		I	FLUE	WT.	
NO.	MANUFACTURER	MODEL NO.	CFM	ESP	MIN. THROW	HP	VOLTS/ PHASE	PHASE FUEL EFF. INPUT OUT	MIN. OUTPUT MBH	(DIA.)	(LBS)	REMARKS		
1	REZNOR	UDX-75	961	0	x	0.06	120/1	NAT. GAS	83%	60,000	49,800	4" RD	76	1 2 3 4

PROVIDE UNIT HEATER WITH LOW VOLTAGE THERMOSTAT WITH INSULATED SUB-BASE, W/ LOCKING COVER.

PROVIDE UNIT WITH ELECTRONIC SPARK IGNITION.

(3) PROVIDE UNIT WITH 2-POINT SUSPENSION KIT.

INPUT RATINGS SHOWN HAVE BEEN DERATED FOR 5,000 FT ELEVATION. INPUT RATE CHANGES FROM STANDARD CAN BE MADE BY ADJUSTING MANIFOLD PRESSURE (MIN 3.0 - MAX 3.7) OR BY CHANGING ORIFICE.


E	EXHAUST FAN SCHEDULE											
MARK	SERVES	MANUF.	MODEL	CEM	E.S.P.		ELEC		DRIVE	SONES	WEIGHT	DEMADKS
IVIARK	SERVES	MANUF.	MODEL	CFM	(in. wg)	AMPS	HEAT	V/PH	DRIVE	SUNES	LBS	REMARKS
1	RESTROOM	BROAN	BHF80	75	.175	12	1300 W	120/1	DIRECT	1.5	12	1 2
1) UNIT TO	1) UNIT TO OPERATE VIA WALL SWITCH WITH SEPERATE FAN & HEATER CONTROL (2) PROVIDE #JV6 FAMCO ROOF DISCHARGE CAP.											

							ELECTRIC		ELECTRIC			10/7	
MARK	MANUFACT.	MODEL	CFM	EXT. S.P.	НР	VOLTS	PHASE	HERTZ	CIRC. PUMP	WT. (lbs)	REMARKS		
1	РМІ	H8801	6300	0.30	1-1/2	230	1	60	6.8 gpm @ 115V/1ø	476	123		



REVISIONS


These drawings are the property of W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C.



()


()


DRAWN BY CHECKED BY March 24th, 2023 SHEET




RELIEF LOUVER WITH BACKDRAFT DAMPER

NOT TO SCALE








GAS FIRED UNIT HEATER





DRYER BOX DETAIL

NOT TO SCALE


EVAPORATIVE COOLER DETAIL NO SCALE

M3.0



REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C.




ssociates,

PROJECT:

DRAWN BY CHECKED BY **DATE** March 24th, 2023

DR

SHEET



INSTALLED BELOW FROST LINE.

REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C.



SS0

()

en

PROJECT:

DR.

DRAWN BY CHECKED BY

DATE March 24th, 2023 JOB NO. 777 SHEET

GENERAL

1..1 Scope: Work under this section includes coordinating and furnishing all labor and material necessary to install a complete plumbing system as shown and specified and in accordance with the codes. Contractor shall pay for all permits, meters, fees, city inspections, legal notices, etc., as required.

- 1..2 Submittals: Within 15 days after award of contract, submit 8 copies of all items.
- 1...3 Record Drawings: Provide a set to the Architect at completion of project.
- 1..4 Instructions: Provide maintenance manual and instruct Owner in the proper operation and maintenance of the equipment.
- 1..5 Guarantee: One year on labor, material and equipment.
- PRODUCTS
- 2..1 Piping:
- 2..1.1 Water Lines:

2..1.1.1 Copper: Type "L" hard drawn, conforming to ASTM B88, for all water pipe not set under concrete or in the ground.

2..1.1.2 Copper: Type "K" soft drawn, conforming to ASTM B88, for water pipe set in or under concrete or in the ground. Wrap lines below concrete floors with 20 mils of polykon tape.

2..1.1.3 Fittings: Wrought copper conforming to ANSI B16.22.

2...1.1.4 Plastic: If permitted by Administrative Authority, IAPMO approved, NSF-61 listed, crosslinked polyethylene (PEX) tubing, equal to Wirsbo "AQUAPEX" system is acceptable for potable water piping.

2..1.2 Sanitary Waste and Vent Piping:

and fittings installed above and below grade.

2..1.2.1 Cast Iron conforming to CISPI Standard 301-95 and ASTM A-888 for all no-hub pipe

2..1.2.2 Galvanized Iron: Standard weight, Schedule 40 galvanized iron conforming to ASTM A-120 for all vent lines 2-1/2" or smaller.

2..1.2.3 Fittings (Waste and Vent System, no-hub cast iron): No-hub cast iron drainage pattern fittings conforming to CISPI #301-95.

2..1.2.4 Fittings (Waste and Vent, galvanized steel): Threaded cast iron fittings conforming to ANSI B16.4.

2..1.2.5 Couplings (Waste and Vent, above and below grade): Double band, stainless steel couplings conforming to CISPI 310-95, with neoprene gasket conforming to ASTM Standard

2..1.2.6 Plastic: Subject to Architect approval, PVC piping conforming to ASTM D-2665-88 is acceptable for sanitary waste piping installed below grade or slab. Fittings: Drainage fittings to match pipe.

2..1.3 LP Gas (Propane) Piping:

2..1.3.1 (Underground): All pipe, tubing, and fittings shall be polyethylene 2306/2406 conforming to ASTM D-1248 and D-3350 for P.E. 2306/2406.

2..1.3.2 (Above grade, exterior): All pipe sizes, black steel pipe, Schedule 40, wrought steel buttwelded fittings.

2..1.3.3 (Above grade, inside building): Schedule 40 black steel. Pipe fittings shall conform to the following:

Pipe 2" and Smaller: Malleable iron threaded fittings.

Pipe 2-1/2" and Larger: Wrought steel buttwelded fittings.

C564 (NOTE: Screened stainless shield is not approved).

2..1.3.4 Risers: All risers in the system from below grade shall be pre-manufactured anodeless type as manufactured by Central Maufacturing Co., Shawnee, OK, or approved equal.

2..1.4 Tracer Wire: Provide approved 14 gage copper (orange covered) tracer wire along all non metallic underground piping.

2..2 Pipe Hangers and Supports: Fee & Mason Figure 103 clevis hanger for insulated pipe and Figure 104 clevis hanger for cast iron pipe. Install #500 Trisolators on uninsulated copper lines at all hangers and wall penetrations.

2...3 Pipe Insulation: Use fiberglass premolded insulation with all—service jacket, minimum density of 3.5 pcf. Provide an additional 8-ounce canvas jacket with Arabol finish around all exposed pipe insulation. Cover fittings and valves (except unions) with insulation cement worked on in two applications to a smooth, hard surface, flush with pipe covering. Provide 8" long, 20 gauge, galvanized iron metal insulation guards at locations of hanger rods and supports. Provide 12" long rigid insulation blocks on bottom half of pipe 1" and larger at hangers. Insulation wall thickness shall conform to the following schedule:

Domestic Hot Water, Hot Water Recirculating Lines:

Mains and horizontal branches — 1" thickness. Drops in walls and partitions -1/2" thickness.

2..4.1 Gate Valves: Milwaukee 115, 125#, bronze body, solder type gate valve with nonrising stem for all lines up through 3" size.

2..4.2 Check Valves: Milwaukee #1509, 125#, bronze body, solder joint check valve with horizontal bronze disc for all valves up to 2" size. Milwaukee #F2974, 125#, iron body, bronze trimmed, flanged horizontal check valve for all valves larger than 2" size.

2..4.3 Shutoff Valve: Milwaukee BB1-350 bronze body, solder joint valve for all lines up through

2..5 Cleanouts:

2..5.1 Concrete and Tile Floors: J.R. Smith 4023, with scoriated nickel-bronze top.

2..5.2 Cleanouts (exposed vertical piping): J.R. Smith 4512 cast iron branch cleanout tee with bronze plug.

2..5.3 Interior Finished Walls: J.R. Smith 4532.

2..5.4 Exterior Surface Cleanouts: J.R. Smith 4253. Provide 18" x 18" x 6" concrete pad at

landscape areas; provide concrete ring below grade at asphalt areas. 2..5.5 Provide all cleanouts with heavy threaded bronze plugs.

2..6 Plumbing Fixtures: Use polished chrome-plated, adjustable brass P-traps with wall escutcheons at all exposed locations. Use polished chrome-plated faucets with removable trim, brass body and brass handles. Fixtures and supply fitting shall be of one manufacturer. Provide diaphragm type, polished chromeplated flush valves with integral vacuum breakers and screwdriver stops. Provide fixture stops or valves ahead of all equipment or fixtures. After fixtures are set in place and secured to walls, caulk all around between fixtures and wall with either Dow Corning #780 or G.E. Construction Sealant white silicone caulking compound.

2..7 Acceptable Manufacturers: The following is a list of manufacturers whose equipment is acceptable as to manufacturer, subject to conformance with all drawings, specifications and addenda items:

Fixtures: American Standard, Eljer, Kohler.

Electric Water Heaters: Ruud, A. O. Smith, American.

Mop Sinks: Fiat, Mustee, Swan.

Valves: Crane, Kennedy, Stockham, Grinnell, Milwaukee, Wolverine.

Supplies, Stops: Eastman, Kohler, Eljer, Brasscraft, McGuire.

P-Traps: Crane. Kohler, Eljer, Frost, McGuire.

Drains and Cleanouts: J. R. Smith, Zurn, Josam, Wade, Western.

Hangers: Grinnell, Fee & Mason, Elcen, Kin-Line, F & S, B-Line, Michigan.

EXECUTION

3..1 Tests and Inspections:

3..1.1 All work to be tested and approved before covering as directed by Architect. Remake all leaking joints.

3..1.2 Water System: 125 psi hydrostatic pressure held for four hours.

3..1.3 Sanitary Waste and Vent System: Fill with water to highest point in the system and let stand without loss for two hours.

3..1.4 Gas System: Hold at 50 psi pneumatic for four hours with no pressure loss.

3..1.6 Sterilization (Domestic Water System): After tests have been completed, the entire domestic water distribution system shall be thoroughly flushed with water until all entrained dirt and mud have been removed, and shall be sterilized with solutions of either liquid chlorine conforming to Federal Specification BB-B-120 or hypochlorite conforming to Fed. Spec. O-C-114, Type II, Grade G, or Fed. Spec. 0—S—602, Grade A or B. The chlorinating material shall privide a dosage of less than 50 parts per million and shall be introduced into the system in an approved manner, and retained in the system for 8 hours before flushing.

3..2 Flashing, Sleeves and Escutcheon Plates:

3...2.1 Flashing: Supply flashing for all vent pipe and other types of piping through roof to be installed with roofing. Flash vents with Stoneman S1300—4 or with sheet lead weighing not less than 4 pounds per square foot or equal. Extend flashing into roofing at least 10" from vent and turn flashing over and down into vent opening.

3..2.2 Sleeves: Use 20 gauge galvanized steel sleeves around pipes passing through masonry

3..2.3 Escutcheon Plates: Install cast brass split ring with setscrew at all locations where exposed pipes pass through walls, floors and/or ceilings. Provide polished chrome-plated escutcheons in finished rooms, all others polished brass.

3..3 Underground Water Piping: Bury all underground water piping a minimum of 24" below finished grade.Install copper lines below concrete floors so that no joints occur below floor and wrap with 20 mils of polyethylene tape with a minimum of 50% overlap.

3..4 Electrical: Wiring by Electrical Contractor.

PLUMBING FIXTURE SPECIFICATIONS

SYMBOL	DESCRIPTION
<u>₩C−1</u>	WATER CLOSET (HANDICAPPED): FIXTURE: AMERICAN STANDARD "CADET PRO" 215AA.104, 1.28 GALLONS PER FLUSH, 16-1/2" HIGH RIM, FLOOR MOUNTED, VITREOUS CHINA, ELONGATED BOWL. SEAT: CHURCH 9500 WHITE OPEN FRONT SEAT WITH CONCEALED CHECK HINGE AND WITHOUT COVER. SUPPLIES: EASTMAN C5CR-20-LK, 1/2" x 3/8" ANGLE STOP WITH FLEXIBLE TUBE RISER.
<u>L–1</u>	LAVATORY (WALL HUNG- ADA COMPLIANT): FIXTURE: AMERICAN STANDARD, MODEL No. 0355.012, WALL HUNG, 20" x 18" VITREOUS CHINA, FRONT OVERFLOW. PROVIDE CAST-IRON WALL HANGER BOLTED TO WALL. FAUCET: MOEN 8400 SINGLE LEVER DECK MOUNTED FAUCET WITH BLADE TYPE ADA HANDLE. SUPPLIES: EASTMAN C5RC-15-LK, ANGLE STOPS WITH FLEXIBLE TUBE RISERS. WASTE: McGUIRE 155WC OFFSET WHEELCHAIR LAVATORY STRAINER WITH GRID DRAIN, CAST BRASS ELBOW AND OFFSET TAILPIECE. TRAP: McGUIRE 8902, 1-1/4" x 1-1/2" CAST BRASS P TRAP. INSULATE EXPOSED WATER AND WASTE PIPING WITH TRUEBRO LAV-GUARD INSULATION KIT, MODEL 102, WITH ACCESSORY #105.
MS-1	MOP SINK: FIXTURE: FIAT MODEL MSB-2424, 24" x 24" x 10", FLOOR MOUNTED, MOLDED STONE WITH INTEGRAL STAINLESS STEEL STRAINER EXTENSION. FAUCET: CHICAGO FAUCET 897 CHROME-PLATED SUPPLY FITTING WITH INTEGRAL STOPS, VACUUM BREAKER, 3/4" HOSE THREAD, FLEXIBLE 3/4" RUBBER HOSE AND HOSE BRACKET; MOP HANGER; SILICONE SEALANT INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. TRAP: PROVIDE 2" TRAP.
<u>WH-1</u>	ELECTRIC WATER HEATER: PPROVIDE UL LISTED ELECTRIC WATER HEATER OF SIZE, CAPACITY AND MAKE AS SCHEDULED. HEATER SHALL BE WARRANTED FOR A MINIMUM OF 5 FULL YEARS AFTER FINAL ACCEPTANCE OF THE BUILDING. FURNISH HEATER WITH THE FOLLOWING ACCESSORIES: 1. ASME COMBINATION TEMPERATURE AND PRESSURE RELIEF VALVE RATED IN EXCESS OF HEATER INPUT. RUN FULL SIZE DRAIN TO TERMINATE AS SHOWN ON DRAWINGS. 2. AUTOMATIC THERMOSTAT ACTUATED CONTROLS WITH 100% SHUTOFF. 3. HIGH—LIMIT CONTROLS. 4. TANK DRAIN. 5. BRASS NIPPLES FOR PIPE CONNECTIONS. 6. HEATER SHALL BE FACTORY INSULATED AND SHEET METAL JACKETED.
<u>HB</u>	HOSE BIBB (FREEZE PROOF): WOODFORD MODEL No. MB65, CHROME PLATED FINISH, 3/4" HOSE CONNECTION WITH INTEGRAL VACUUM BREAKER, SELF-DRAINING, LOOSE TEE OPERATOR, ENCLOSED IN A FLUSH MOUNTED 14 GAUGE STAINLESS STEEL WALL BOX WITH LOCKABLE COVER.
<u>CWB</u>	CLOTHES WASHER BOX: ACORN MODEL No. 8186-18GA, STAINLESS STEEL BOX WITH WASTE OUTLET AND "FLO-CLOZ" CARTRIDGE OPERATED CONTROL VALVES AND STOPS. COMPLETE WITH INTEGRAL VACUUM BREAKERS.

EXPANSION TANK SHALL BE SUPPORTED INDEPENDANTLY OF THE WATER PIPING. STRAP TO UNISTRUT MOUNTED ON WALL -A.S.M.E. T & P DIELECTRIC UNION — RELIEF VALVE (TYPICAL) -FULL SIZE DRAIN BALL VALVE — TO TERMINATE +2" (TYPICAL) ABOVE DRAIN PAN RIM EXPANSION TANK -WATER HEATER WH-1 AMTROL ST-5 -SEE SCHEDULE INSTALL PER MFR. **RECOMMENDATIONS** -PROVIDE SQUARE 3" DEEP GALVANIZED STEEL DRAIN PAN WITH ALL SEAMS WATER TIGHT. PROVIDE 3/4" DRAIN PIPE CONNECTION TO PAN. PIPE DRAIN PAN LINE TO TERMINATE AS DRAIN VALVE NOTED ON PLANS. W/ HOSE END-RESTROOM CEILING DRAIN

WATER HEATER DETAIL

PLUMBING GENERAL NOTES:

1. ALL PLUMBING WORK SHALL COMPLY WITH THE MOST STRINGENT OF APPLICABLE CODES, ORDINANCES, OR THE SPECIFICATIONS.

2. DETERMINE EXACT LOCATION & MOUNTING HEIGHT OF PLUMBING FIXTURES FROM ARCHITECTURAL DRAWINGS.

3. COORDINATE LOCATION OF ALL PLUMBING LINES WITH DUCTWORK AND ELECTRICAL SERVICES.

4. PRIOR TO SUBMITTING BID, CONTRACTOR SHALL REVIEW THE ARCHITECTURAL DRAWINGS & INCLUDE IN HIS BID AN AMOUNT TO FURNISH & INSTALL ANY FIXTURES SHOWN IN ADDITION TO PLUMBING DRAWINGS.

5. PROVIDE VACUUM BREAKERS ON HOSE BIBBS & ALL HOSE END FITTINGS. 6. LOCATE ALL VENTS THROUGH ROOF 10'-0" FROM ALL AIR INTAKES,

EVAPORATIVE COOLERS, ETC. 7. VERIFY INVERT ELEVATIONS (WASTE LINES), SIZES, & LOCATIONS OF ALL EXISTING GAS, WATER & WASTE LINES TO WHICH NEW PIPING CONNECTS PRIOR

TO MAKING-UP OR INSTALLATION OF PIPING. 8. LOCATE ALL VALVES, UNIONS, THERMOMETERS, GAUGES, OR OTHER EQUIPMENT REQUIRING FREQUENT READING. REPAIRS. ADJUSTMENTS.

REFERENCE TO THE FINISHED BUILDING. 9. ROUGH-IN ALL WATER & WASTE PIPING TO SPECIAL EQUIPMENT IN ACCORDANCE WITH MANUFACTURERS' SHOP DRAWINGS. VALVE ALL SUPPLIES AND MAKE FINAL CONNECTIONS.

INSPECTION, REMOVAL OR REPLACEMENT SO AS TO BE ACCESSIBLE WITH

10. INSTALL APPROVED DIELECTRIC ISOLATORS AT ALL CONNECTIONS OF DISSIMILAR METALS.

11. WHERE POSSIBLE, TIE VENTS TOGETHER SO THAT A MINIMUM NUMBER TERMINATE THROUGH ROOF.

12. CONTRACTOR SHALL NOT CUT HOLES IN STRUCTURAL MEMBERS WITHOUT FIRST SECURING WRITTEN APPROVAL FROM THE ARCHITECT.

WATER CALCULATION:

FIXTURE UNITS = 28 FU / 19 GPM

PIPE LENGTH TAP TO METER PIPE LENGTH METER TO LAST FIXTURE 194 FT. VERTICAL PIPE LENGTH TO HIGHEST FIXTURE 209 FT. 52 FT. OTAL PIPE LENGTH FITTING LOSS (25%)

TOTAL DEVELOPED LENGTH 261 FT.

WATER PIPE SIZING CRITERIA

65.00 PSI* 8.50 PSI 12.00 PSI WATER METER LOSS (1" BACKFLOW PREVENTER LOSS (1") 2.20 PSI 20.00 PSI STATIC LOSS (5' x 0.43) FIXTURE LOSS PRESSURE AVAILABLE FOR PIPING 22.30 PSI

22.30 PSI / 261 FEET x 100 = 8.4 PSI MAXIMUM ALLOWABLE DROP PER 100 FEET PIPE LENGTH

*ASSUMED WATER PRESSURE— CONTRACTOR SHALL VERIFY ACTUAL WATER PRESSURE PRIOR TO CONSTRUCTION. IF PRESSURE IS LESS THAN 65 PSI, CONTRACTOR SHALL CONTACT ENGINEER FOR PIPE SIZING EVALUATION. IF PRESSURE EXCEEDS 80 PSI, A PRESSURE REDUCING VALVE SHALL BE PROVIDED. PIPING VELOCITY NOT TO EXCEED 8 FEET PER SECOND.

BRANCH PIPE	SIZING CHART	FOR 8.4 PSI LOSS
PIPE SIZE	G.P.M.	F.U.(TANK)
1/2"	3	3
3/4"	9	11
1"	18	26
1-1/4"	32	57

DESCRIPTION	QTY	F.U. E	TOT	TOTAL F.U.			
DESCRIP HON	QIT	WASTE	WATER	WASTE	WATER		
WATER CLOSET (F.T.)	1	4	5	4	5		
LAVATORY	1	1	2	1	2		
MOP SINK	1	2	3	2	3		
CLOTHESWASHER BOX	1	3	4	3	4		
ALLOWANCE FOR FUTURE FIXTURES	'	1	1		14		
					28		

	ELI	ECTRIC	WAI	ΓER	HEA	TER S	CHEDU	LE
MARK	MANUFAC.	MODEL	STORAGE CAPACITY IN GALS.	KW INPUT	VOLTAGE/ PHASE	GALLON PER HR. REC. AT 100° F T.R.	WATER OUTLET TEMP F	REMARKS
WH-1	RHEEM	EGSP30	30	4.5/ 4.5	240/1	18.5	140	NON SIMULTANEOUS WIRING


	FIXTURE	CON	INE	CTI	ON	SCI	HEDULE
MARK	DESCRIPTION	TRAP SIZE	WASTE	VENT	COLD WATER	HOT WATER	REMARKS
WC-1	WATER CLOSET	INT.	4"	2"	1/2"	_	TANK TYPE, ADA
L-1	LAVATORY	1-1/4" x 1-1/2"	1-1/2"	1-1/2"	1/2"	1/2"	WALL HUNG, ADA
MS-1	MOP SINK	2"	2"	1-1/2"	1/2"	1/2"	FLOOR TYPE
CWB	CLOTHESWASHER BOX	2"	2"	1-1/2"	1/2"	1/2"	

Design Group, LLC Consulting Engineers 611 West Delano Ave Prescott, AZ 86301 Project Surprise, AZ 85379

(928) 443.7353 #23030 (623) 444-6143

REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C.



6


()

()

S

Comr 5416 Presc

DRAWN BY CHECKED BY March 24th, 2023 JOB NO. 777 SHEET



GAS PIPING DIAGRAM

GAS PIPING NOTES:

1. MINIMUM DEPTH OF GAS PIPING TO BE 18" BELOW

2. GAS PIPING SHALL NOT BE INSTALLED IN OR ON THE GROUND UNDER ANY BUILDING.

3. GAS PIPING SHALL NOT RUN IN HOLLOW CORE OF

4. PROVIDE SHUT—OFF COCK, UNION AND 6" LONG DIRT LEG WITH CAP AT EACH GAS LINE DROP TO APPLIANCE.

5. ALL GAS USING EQUIPMENT TO BE LIQUID PROPANE FUEL.

6. DO NOT USE FLEXIBLE PIPE CONNECTIONS TO EQUIPMENT.

7. ALL GAS PIPING UNDER ASPHALT OR CONCRETE PAVING ADJOINING BUILDING MUST BE SLEEVED IN GAS TIGHT PIPE (SCHEDULE 40 PVC PIPE), SLEEVE SIZE SHALL (MINIMUM) 2 PIPE SIZES LARGER THAN THE GAS PIPE.

8. ALL GAS PIPING, MATERIALS, VALVES, FITTINGS, INSTALLATION AND TESTING SHALL COMPLY WITH CHAP. 4, INTERNATIONAL FUEL GAS CODE.

9. VERIFY ALL GAS BTU/H INPUTS WITH ACTUAL BTU/H INPUT OF APPLIANCE SUPPLIED.

10. ALL GAS LINES INSTALLED THROUGH CMU WALLS, ETC., SHALL BE SLEEVED WITH STEEL PIPE A MINIMUM OF (2) (TWO) PIPE SIZES LARGER THAN THE GAS PIPE.

ALL VENTS 2" U.N.O.

WASTE AND VENT SCHEMATIC

Design Group, LLC consulting Engineers

W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C.

These drawings are the property of

REVISIONS



Associa

enson

CHECKED BY

DATE March 24th, 2023

ELECTRICAL SYMBOLS

NOTE: NOT ALL SYMBOLS ARE USED ON THIS PROJECT

FLUORESCENT FIXTURE. WITH FIXTURE DESIGNATED BY LETTER. SMALL LETTER INDICATES SWITCH LEG

NIGHT LIGHT- NOT SWITCHED

FLUORESCENT STRIP FIXTURE. CEILING OR WALLMOUNTED FIXTURE.

PORCELAIN PULL CHAIN FIXTURE

JUNCTION BOX JUNCTION BOX WITH FLEX CONNECTION.

SINGLE FACE EXIT SIGN- NOT SWITCHED

DOUBLE FACED EXIT SIGN- NOT SWITCHED.

TWO HEAD EMERGENCY LIGHT WITH BATTERY.

POLE-MOUNTED FIXTURE - No. OF LUMINAIRES AS SHOWN & SCHEDULED

SINGLE POLE SWITCH, + 48" A.F.F. (20A-120/277V)

THREE WAY SWITCH, + 48" A.F.F. (20A-120/277V)

4-WAY SWITCH +48" AFF (20A-120/277V) SWITCH AND PILOT LIGHT (20A-120-/277V)

SINGLE POLE SWITCH, KEY OPERATED (20A)

DIMMER CONTROL, + 48" A.F.F. EQUAL TO LUTRON "NOVA" SERIES, SIZED TO MATCH LOAD SERVED VARIABLE SPEED FAN CONTROL, +48" A.F.F.

DUPLEX RECEPTACLE, + 18" A.F.F. (20A)

DUPLEX RECEPTACLE ABOVE COUNTER, VERIFY HEIGHT. (20A)

FOURPLEX RECEPTACLE, + 18" A.F.F. (20A)

SPECIAL RECEPTACLE - SIZE &

POWER FLUSH FLOOR OUTLET

TYPE AS NOTED

TELEPHONE OUTLET PLASTER RING AT + 18" A.F.F. HUBBELL #P12 COVERPLATE. 3/4"C TO CEILING SPACE UNLESS SHOWN WITH HOMERUNS.

DATA SYSTEM OUTLET, 4" SQUARE BOX AND COVERPLATE, 3/4" C. TO CEILING SPACE UNLESS SHOWN WITH HOMERUN, + 18" A.F.F.

TELE/DATA COMBO OUTLET, 4" SQUARE BOX AND COVERPLATE, 3/4" C. TO CEILING SPACE UNLESS SHOWN WITH HOMERUN, + 18" A.F.F.

CABLE TELEVISION (CATV) OUTLET PLASTER RING AT + 18" A.F.F. U.N.O. HUBBELL COVERPLATE, 3/4"C TO CEILING SPACE UNLESS SHOWN WITH HOMERUNS.

TELPHONE SYSTEM CONDUIT HOMERUN WITH NYLON PULLWIRE (1"C MIN UNO)

CLOSED CIRCUIT TV (CCTV) OUTLET SAME AS CATV OUTLET

DOOR CHIME

■ REMOTE CONTROL STATION @ +48" AFF

DISCONNECT SWITCH, FUSE PER EQUIPMENT MANUFACTURERS RECOMMENDATION. OUTSIDE NEMA 3R - N.F. = NON-FUSED.

COMBINATION STARTER AND FUSIBLE DISCONNECT SWITCH SIZE AS NOTED

EQUIPMENT TERMINATION CONNECTION POINT VERIFY EXACT LOCATION LOAD AND VOLTAGE AS NOTED

THERMAL PROTECTED SWITCH

MOTOR STARTER - SHADING INDICATES F.B.O.

DISTRIBUTION PANELBOARD.

BRANCH CIRCUIT PANELBOARD.

CONDUIT BELOW FLOOR OR UNDERGROUND

CONDUIT IN WALL OR ABOVE CEILING HOMERUN TO PANEL, NEUTRAL AND PHASE WIRING DESIGNATION (SEE GROUNDING NOTE)

CONDUIT TURNING UP

CONDUIT TURNING DOWN

CONDUIT STUB-OUT, MARK AND CAP AS DIRECTED

GROUND WIRE (SIZE AS NOTED) EXTENDED AND CONNECTED TO APP'D GROUND

ABBREVIATIONS

ABOVE FINISHED FLOOR (¢ OF OUTLET) ABOVE FINISHED GRADE (¢ OF OUTLET)

EMPTY CONDUIT

G.F.I. GROUND FAULT INTERRUPTER

WEATHERPROOF

UNLESS OTHERWISE NOTED

ELECTRIC DRINKING FOUNTAIN

DUTLET MOUNTING HEIGHTS PER AMERICAN DISABILITY ACT

ELECTRICAL CONTRACTOR SHALL COMPLY WITH THE 2010 ADA SAD REQUIREMENTS FOR ALL SWITCHES. RECEPTACLES, TELE./DATA AND SIDE REACH CONTROL SWITCHES. ALL WALL CONTROLS, SWITCHES AND THERMOSTATS TO BE MOUNTED WITH TOP OF J-BOX AT 48" A.F.F. ALL ABOVE COUNTER CONTROLS, SWITCHES & OUTLETS TO BE MOUNTED WITH HORIZONTAL ORIENTATION WITH TOP OF J-BOX AT 44" A.F.F.. ALL WALL OUTLETS TO BE MOUNTED AT 15" A.F.F. TO BOTTOM OF J-BOX.

SPECIAL REQUIREMENTS PER: THE FAIR HOUSING ACT.

ALL RECEPTACLES AT RESTROOM LAVATORIES TO BE GFCI TYPE. ALL WALL CONTROLS, SWITCHES AND THERMOSTATS TO BE MOUNTED WITH TOP OF J-BOX AT 48" A.F.F. ALL ABOVE COUNTER CONTROLS, SWITCHES & OUTLETS TO BE MOUNTED WITH HORIZONTAL ORIENTATION WITH TOP OF J-BOX AT 44" A.F.F. ALL WALL OUTLETS TO BE MOUNTED AT 15" A.F.F. TO BOTTOM OF J-BOX.

SPECIFICATIONS

- PRIOR TO SUBMITTING BID, SUBCONTRACTORS SHALL EXAMINE ALL GENERAL CONSTRUCTION DRAWINGS AND VISIT THE CONSTRUCTION SITE TO BECOME FAMILIAR WITH EXISTING CONDITIONS UNDER WHICH HE WILL HAVE TO OPERATE AND WHICH IN ANY WAY AFFECTS THE WORK UNDER HIS CONTRACT. NO SUBSEQUENT ALLOWANCE WILL BE MADE IN BEHALF OF THE CONTRACTOR FOR ANY ERROR OR NEGLIGENCE ON HIS PART.
- 2. THE SUBCONTRACTOR SHALL BE HELD FULLY RESPONSIBLE FOR THE PROPER RESTORATION OF ALL EXISTING SURFACES REQUIRING PATCHING, PLASTERING, PAINTING AND /OR OTHER REPAIR DUE TO THE INSTALLATION OF ELECTRICAL WORK UNDER THE TERMS OF THE CONTRACT. CLOSE ALL OPENINGS, REPAIR ALL SURFACES, ETC., AS REQUIRED.
- 3. SEE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS. ELEVATIONS AND BUILDING DETAILS. VERIFY LOCATION OF ALL OUTLETS. SWITCHES. AND WALL MOUNTED LIGHTING FIXTURES WITH ARCHITECTURAL DRAWINGS AND ACTUAL CONDITIONS. VERIFY ALL CEILING TYPES WITH ARCHITECTURAL DRAWINGS BEFORE ORDERING FIXTURES.
- 4. PRIOR TO ROUGH-IN AND FINAL CONNECTION, VERIFY ELECTRICAL CHARACTERISTICS AND EXACT LOCATION OF EQUIPMENT.
- 5. GROUT AND SEAL ALL CONDUIT PENETRATIONS OF WALLS AND FLOOR SLABS TO PRESERVE FIRE RATING AND WATERTIGHT INTEGRITY.
- 6. BRANCH CIRCUIT WIRING SHALL BE THHN/THWN INSULATION. PANEL FEEDERS SHALL BE TYPE XHHW. ALL WIRE SHALL BE COPPER. MINIMUM WIRE SIZE SHALL
- 7. ALL WIRING TO BE INSTALLED IN RACEWAYS. TYPE OF RACEWAY SHALL BE AS REQUIRED BY CODE. MINIMUM CONDUIT SIZE SHALL BE 1/2".
- 8. PROVIDE CODE SIZED BOND WIRE IN ALL EMT, FLEXIBLE CONDUIT
- 9. ALL ELECTRICAL EQUIPMENT SHALL BE NEW, U.L. APPROVED AND COMMERCIAL
- 10. WIRE RATED FOR 150° CENTIGRADE SHALL BE USED FOR ALL INCANDESCENT
- 11. ALL ELECTRICAL WORK SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST NATIONAL CODE, (N.E.C.), AND ALL APPLICABLE FEDERAL, STATE AND LOCAL
- 12. PROVIDE TYPEWRITTEN DESCRIPTIVE PANEL DIRECTORIES

NOTE:

1.) ALL SUB-PANELS, SERVICE EQUIPMENT, AND EQUIPMENT DISCONNECTS SHALL BE PROVIDED WITH THE WORKING CLEARENCES REQUIRED BY THE LATEST ADOPTED NEC.

SITE RELATED WORK

PRIOR TO COMMENSING WORK AND/OR SUBMITTING BASE BID, THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY HIMSELF TO EXISTING WORK RELATED CONDITIONS WITH REGARDS TO THE FOLLOWING:

- 1 TRENCH AND BACKFILL FOR CONDUITS PER UTILITY CO. REQUIREMENTS.
- (FIELD VERIFY) 2 TRANSFORMER MOUNTING PAD PER UTILITY CO. REQUIREMENTS.
- 3 PROVIDE SECONDARY AND/OR PRIMARY CONDUITS. (SEE ONE LINE DIAGRAM).
- 4 SERVICE ENTRANCE SECTION (S.E.S.). VERIFY PROPOSED EQUIPMENT WILL FIT THE SPACE ALLOTED PRIOR TO ORDERING AND/OR CONSTRUCTION.
- 5 P.V.C. TELEPHONE CONDUIT WITH PULL WIRE AND RIGID FACTORY STEEL BENDS PER TELEPHONE CO. REQUIREMENTS. (SIZE AS NOTED OR REQUIRED BY UTILITY VERIFY PRIOR TO INSTALLATION).
- 6 THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR COORDINATION AND COMPLIANCE WITH ALL UTILITY COMPANIES REQUIREMENTS, INCLUDING, BUT NOT LIMITED TO ANY AND ALL ADDITIONAL COSTS FOR MATERIAL AND LABOR FOR WORK WHETHER SHOWN ON THE PLANS OR NOT. ACTUAL ROUTING. CONDUIT. TRENCH AND PAD REQUIREMENTS SHALL BE AS SPECIFIED BY UTILITY COMPANIES. VERIFY REQUIRMENTS WITH UTILITIES PRIOR TO INSTALLATION.
- WHERE APPLICABLE, PROVIDE EQUIPMENT GROUNDING (BOND) CONDUCTOR FOR METALLIC PROCESSING AND FIRE SPRINKLER PIPING PER NEC 250-80 AND SIZED PER NEC 250-95 TABLE.

ONE LINE GENERAL NOTES:

1. SYSTEM SHOWN IS A TWO TIER SERIES RATED

UL LISTED SYSTEM TO MATCH THIS RATING.

ENGINEER AND THE ELECTRICAL INSPECTOR

OF SYSTEM SHORT CIRCUIT AMPS.

SYSTEM 22/10K. MANUFACTURER SHALL PROVIDE A

2. MOTOR SHORT CIRCUIT CONTRIBUTION IS LESS THAN 1%

3. NO DESIGN CHANGES MAY BE MADE TO THE SYSTEM

(1) PROVIDE A PERMANENT LABEL READING "THIS CIRCUIT BREAKER IS PART OF A SERIES RATED SYSTEM WITH

DOWNSTREAM PANELS 22/10K. 22,000 AMPS

(2) PROVIDE A PERMANENT LABEL READING "CAUTION—

SERIES RATED SYSTEM 22/10, IDENTIFIED

REPLACEMENT COMPONENTS REQUIRED

MAXIMUM AVAILABLE FAULT

METER MAIN AND C.T. CABINET

BRACE FOR 22,000 AIC

+ 4 4 +

9

BONDING

JUMPER -

U.G. SERVICE

PROVIDE 2" E.C. TO SERVICE XFMR.

PER POWER CO.

SPEC'S.——

ËQUIP. BOND

CURRENT = 14,318 AMPS SYMM

(VERIFY WITH UTILITY COMPANY

PRIOR TO ORDERING EQUIPMENT)

-NEW SUN VALLEY, EATON RYCO OR EQUAL 200 AMP, 120/240V, 1ø, 3W, NEMA 3R

POWER CO. & U.L. APPROVALS REQUIRED

-#4 CU. BOND TO ALL METALLIC PIPING SYSTEMS

---#4 CU. UFER

– 200A/2P

ELEC. ONE-LINE DIAGRAM - 'SES'

PULL-OUT'S CLASS 'T' FUSES

OR 200/2P

CIRCUIT BREAKERS

WITHOUT THE PRIOR APPROVAL OF THE DESIGN ELECTRICAL

ONE LINE KEYNOTES.

AVAILABLE. IDENTIFIED REPLACEMENT COMPONENT REQUIRED"

ELECTRICAL DESIGN & CADD SERVICES INC. 1600 LAMB LANE

CELL (928) 420-1200 E-MAIL: archie@elecdesign.net

ELEC. FAULT CURRENT CALCULATIONS


 I_{SC} = 14,318 A x .600 = 8,590 AMPS

 $M = \frac{1}{1 + .666} = .600$

PANEL 'A1'

- 3#3/0 CU., 1#6 CU. BOND, IN 2" C.

PRESCOTT, AZ. 86305
PH. (928) 776-4900
CELL (928) 420-1200



REVISIONS

These drawings are the property of

W. Alan Kenson & Associates P.C

and may not be reproduced in any

EXPIRES 12/30/2024

ate C.

S **(**)

0

Ken

an


DR

DRAWN BY CHECKED BY March 24th, 2023 JOB NO. 777

SHEET

NIGHT LIGHT

TELEPHONE MOUNTING BOARD



REVISIONS

These drawings are the property of W. Alan Kenson & Associates P.C., and may not be reproduced in any way without the written consent of W. Alan Kenson & Associates, P.C



•

DRAWN BY CHECKED BY March 24th, 2023

JOB NO. 777 SHEET

BUILDER/CONTRACTOR RESPONSIBILITIES

<u>Drawing Validity</u> — These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

 $\underline{\text{Builder Acceptance of Drawings}} \ - \ \text{Approval of the manufacturer's drawings and design data affirms that the}$ manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer's interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC code of standard practice APR 10 Section 4.4.1)

Code Official Approval - It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

Builder is responsible for State, Federal and OSHA safety compliance — The Builder/Contractor is responsible for applying and observing all pertinent safety rules and regulations and OSHA standards as applicable.

Building Frection - The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector. (AISC Code of Standard Practice APR 10 Section 7.10.3)

<u>Discrepancies</u> — Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC Code of Standard Practice APR 10 Section 3.3)

<u>Materials by Others</u> — All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturers assumptions will govern.

Modification of the Metal Building from Plans — The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a Licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

Foundation Design — The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA MBSM Chapter 4 Section 3.2.2 and Section A3)

Shimming — In accordance with Section 6.10 of Chapter 4, Common Industry Practices in the Metal Building Systems Manual, shimming is a normal part of erection and is not subject to claim.

PROJECT NOTES

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, or ASTM A1011 with 55 ksi min, yield, except flanges wider than 12" and thicker than 3/8", all flanges thicker than 1", and all webs thicker than 3/8" are 50 ksi min. yield. Rod X-bracing conforms to ASTM A529 or ASTM A572 with 50 ksi min. yield. Cable X-bracing conforms to ASTM A475 7 Strand Extra High—Strength grade. Hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with 50 ksi min, vield. Hot rolled angles, other than flange braces, conform to ASTM A36 minimum. Round and rectangular HSS conforms to ASTM A500 Grade B. Cold-formed steel secondary framing Members conform t ASTM A1011 or ASTM A653 Grade 55 with 55 ksi min. yield.

The manufacturer does not assume any responsibility for the erection nor field supervision of the structure and or any special inspections that may be required by the local building authority during erection (including inspection of the high strength bolts or field welds) as required during erection. The coordination and the costs associated for setting up and Special Inspections are the responsibility of the Erector, Owner, Architect, or Engineer of Record

Design is based upon the more severe loading of either the roof snow load or the roof live load.

Loads, as noted, are given within order documents and are applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the manufacture nor the certifying engineer declares or attests that the loads as designated are proper for the local provisions that may apply or for site specific parameters. The manufacturer's Engineer's certification is limited to design loads supplied by an Architect and/or engineer of record for the overall construction project.

This project is designed using manufacture's standard serviceability standards. Generally this means that all stresses and deflections are within typical performance limits for normal occupancy and standard metal building products. If special requirements for deflections and vibrations must be adhered to, then they must be clearly stated in the contract documents.

This metal building system is designed as enclosed. All exterior components (i.e. doors, windows, vents, etc.) must be designed to withstand the specified wind loading for the design of components and cladding in accordance with the specified building code. Doors are to be closed when a maximum of 50% of design wind velocity is reached.

Unless otherwise noted, special inspection of fabricated items is not required. Per IBC section 1704.2.5.1, The fabricator is approved to perform such work without special inspection through maintenance of IAS AC 472 certification MR-136

The design collateral load has been uniformly applied to the design of the building. Hanging loads are to be attached to the purlin web. This may not be appropriate for heavily concentrated loads. Any attached load in excess of 150 pounds shall be accounted for by special design performed by a licensed engineer using concentrated loads and may require separate support members within the roof system.

The metal building manufacturer has not designed the structure for snow accumulation loads at the ground level which may impose snow loads on the wall framing provided by the manufacturer.

Using 7x7 gutter with 4 x 5 downspouts, the roof drainage system has been designed using the method outlined in the MBMA Metal Building Systems Manual. Downspout locations have not been located on these drawings. The downspouts are to be placed on the building sidewalls at a spacing not to exceed 50 feet with the first downspout from both ends of the gutter run within 25 feet of the end. Downspout spacing that does not exceed the maximum spacing will be in compliance with the building code. The gutter and downspout system as provided by the manufacturer is designed to accommodate 4 in/hr rainfall intensity.

BOLT TIGHTENING - All bolted joints with A325 Type 1 bolts are specified as snug-tightened joints in accordance with the with the most recent edition of the RCSC Specification for Structural Joints Using ASTM A325 OR A490 bolts. Pre-tensioning methods, including turn-of-nut, calibrated wrench, twist-off-type tension-control bolts or direct-tension-indicator are NOT required. Installation inspection requirements for snug-tight bolts (Specification for Structural Joints Section 9.1) is suggested.

ENGINEERING DESIGN CRITERIA

Building Code.

Building Risk Category.....

5 d to	Roof	Dead Load 2.360 psf Collateral 5 psf
	Roof	Live Load20.00 psf (Not Reducible)
on rd.	Snow	Ground Snow Load (Pg)
	Wind	

Serviceability Wind Speed..... 71 mph (IBC Section 1609.3.1) Wind Exposure Category... Internal Pressure Coefficient (GCpi) 0.18 / -0.18 Loads for components not provided by building

Ultimate Wind Speed (Vult)...... 101 mph

Nominal Wind Speed (Vasd)...... 78 mph

manufacturer. Wall Edge Zones (within 3.50 ' of corner) 17.00 psf pressure

-22.67 psf suction Other Wall Zones 17.00 psf pressure -18.42 psf suction

These values are the maximum values required based on a 10 square foot area. Components with larger areas may have lower wind loads.

Zones per ASCE 7-16; FIG. 30.3-1 Zones pressures shown are Un-Factored

Seismic

Building ID

Buildina A

BUILDING ID

PHASE

Seismic Importance Fo	actor (le) 1.00
Seismic Design Catego	ry C
Soil Site Class	
Ss 0.338 g	Sds 0.345 g
S1 0.101 g	Sd1 0.162 g
	Equivalent Lateral Force

Location... Int RF Front SW Back SW Left EW Right EW System.... Н H 3 Н Cs.......... 0.115 0.115 0.115 0.115

Design Base Shear in kips (V) Transverse 5.83

Design Base Shear in kips (V) Longitudinal 5.56

System - Basic Force Resisting System H - Steel System not Specifically Detailed for

Seismic Resistance

C4 - Steel Ordinary Moment Frames

B3 - Steel Ordinary Concentric Braced Frames G2 - Steel Ordinary Cantilevered Column Systems

R - Response Modification Coefficient

Cs - Seismic Response Coefficient

JOB NUMBER

19-B-34172

Transverse - Direction Parallel to the Rigid Frames Longitudinal - Direction Perpendicular to the Rigid Frames

Page Description C1 COVER SHEET F1 ANCHOR BOLT PLAN F2 ANCHOR BOLT REACTIONS F3 ANCHOR BOLT DETAILS E1 ROOF FRAMING PLAN E2 ROOF SHEETING PLAN E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS R1-R3 INSTALLATION SHEETS		
F1 ANCHOR BOLT PLAN F2 ANCHOR BOLT REACTIONS F3 ANCHOR BOLT DETAILS E1 ROOF FRAMING PLAN E2 ROOF SHEETING PLAN E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	Page	Description
F2 ANCHOR BOLT REACTIONS F3 ANCHOR BOLT DETAILS E1 ROOF FRAMING PLAN E2 ROOF SHEETING PLAN E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	C1	COVER SHEET
F3 ANCHOR BOLT DETAILS E1 ROOF FRAMING PLAN E2 ROOF SHEETING PLAN E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	F1	ANCHOR BOLT PLAN
E1 ROOF FRAMING PLAN E2 ROOF SHEETING PLAN E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	F2	ANCHOR BOLT REACTIONS
E2 ROOF SHEETING PLAN E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	F3	ANCHOR BOLT DETAILS
E3 FRONT SIDEWALL E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	E1	ROOF FRAMING PLAN
E4 BACK SIDEWALL E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	E2	ROOF SHEETING PLAN
E5 LEFT ENDWALL E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	E3	FRONT SIDEWALL
E6 RIGHT ENDWALL E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	E4	BACK SIDEWALL
E7-8 FRAME CROSS SECTION E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	E5	LEFT ENDWALL
E-9 PARTITION PLAN DET1-22 STANDARD DETAILS	E6	RIGHT ENDWALL
DET1-22 STANDARD DETAILS	E7-8	FRAME CROSS SECTION
	E-9	PARTITION PLAN
R1-R3 INSTALLATION SHEETS	DET1-22	STANDARD DETAILS
	R1-R3	INSTALLATION SHEETS

Drawing Index

DRAWING STATUS

FOR APPROVAL

as complete.

These drawings, being For Approval, are by definition not final, and are for conceptual representation only. Their purpose is to confirm proper interpretation of the project documents. Only drawings issued "For Erector Installation" can be considered

FOR CONSTRUCTION PERMIT These drawings, being for Permit, are by

definition not final. Only drawings issued "For Erector Installation" can be considered as complete.

X FOR ERECTOR INSTALLATION Final drawings for construction.

For questions or assistance Concerning Erection call:

800-784-9795

Monday-Friday 7:30am to 5:00pm

ENGINEERING SEAL

The engineer whose seal appears hereon is an employee for the manufacturer for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.

ctronically signed and sealed by Yuangang (Bill) Li, and/or time stamp shown using a digital signature. ocument are not considered signed and sealed and erified by a 3rd Party Certificate Authority on any

Building	g Descriptio	ns	
Width(ft)	Length(ft)	Height(ft)	This item has been elec S.E., P.E. on the date a
35	79	20	Printed copies of this do the signature must be ve

ISSUF

SHEET NUMBER

C1

SSUE	DATE	DESCRIPTION	BY	CK'D	DSN	
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ	
						7301 FAIRVIEW, HOUSION, TEXAS, P.O. BOX 40338 ZIP 77041 (713) 466-7788 ZIP 77240
						BUILDING SYSTEMS —
						PROJECT: JIM CRAWFORD
						CUSTOMER: STEEL ERECTION & MAINTENANCE OWNER: JIM CRAWFORD
						LOCATION: PRESCOTT,AZ 86301

DATE

4/20/23

SCALE

N.T.S.




Download panel installation manuals from: www.cornerstonebuildingbrands.com/installationmanuals/

Descargue los manuales de instalación del panel desde: www.cornerstonebuildingbrands.com/installationmanuals/

1/	'2"ø A325 BOL	T GRIP TABLE (UNLESS N	NOTED)
GRIP	LENGTH	BOLT LENGTH	NOTE:
0 TO 9/16"	1 1/4" F.T.		FULL THREAD ENGAGEMENT IS DEEMED TO HAVE BEEN MET
Over 9/16" TO 1 1/16"	1 3/4" F.T.		WHEN THE END OF THE BOLT
Over 1 1/16" TO 1 5/16"	2"		IS FLUSH WITH THE FACE OF THE NUT.
Over 1 5/16" TO 1 9/16"	2 1/4"		
Over 1 9/16" TO 1 13/16"	2 1/2"	1 1 V 1 —	REQUIRED ONLY WHEN SPECIFIED.
Over 1 13/16" TO 2 1/16"	2 3/4"	1 1 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	MAY BE LOCATED UNDER HEAD UNDER NUT. OR AT BOTH AT
LOCATIONS OF BOLTS LONGER			NOTED ON ERECTION DRAWINGS.
NOTED ON ERECTION DRAWINGS		ADD 5/32	" FOR EACH WASHER TO MATERIAL
F.T. DENOTES FULLY THRE	EADED	THICKNESS	S TO DETERMINE GRIP.

Rev. 9/29/2022







	FRAME LINES: 2 3 4	
Wind_Left2 Wind_Right2 Press Horz Vert Horz Vert Horz 0.0 -1.0 0.0 -0.7 -1.0 -2.2 -6.5 0.0 1.9 -2.3 0.0 0.8 2.9 -4.1 -1.5	© (A) COL	UMN LINE
Seis Long -MIN_SNOW Vert Horz Vert 0.0 0.0 1.9 0.0 0.0 5.7 0.0 0.0 2.0	<u>H</u>	
	IV IV	
AD DEVOTIONS	RIGID FRAME: ANCHOR BOLTS & BASE PLATES	

NOTES FOR REACTIONS BUILDING REACTIONS ARE BASED ON Base_Plate (in) Width Length Frm Col Anc. Bolt THE FOLLOWING BUILDING DATA: Line Line Qty Dia Width Thick (in) = 35 = 79 = 14.17 / 20 6.000 10.50 10.50 LENGTH (FT) EAVE HEIGHT (FT) EAVE HEIGHT (FT)
ROOF SLOPE (rise/12)
DEAD LOAD (psf)
COLLATERAL LOAD (psf)
ROOF LIVE LOAD (psf)
FRAME LIVE LOAD (psf)
ROOF SNOW LOAD (psf)
MINIMUM ROOF SNOW LOAD (psf) = 2.0:12 / = 2.360 2* Frame lines: 2 3 = 20.00 = 20 = 30.1 = 30.1 RIGID FRAME: ANCHOR BOLTS & BASE PLATES

= 43.00 = 101 = IBC 18

= Closed

= 1.00 = 1.00

5/8" 5/8" 3/4" 5/8"

F1554 F1554 F1554 F1554

"Panel_Shear

(lb/ft) Wind

ANCHOR BOLT SUMMARY

Locate

Jamb

Endwall

Frame

Reactions in plane of wall

Horz

2.7

Vert

± Reactions(k ') — Wind — — Seismic

Qty

O 16

○ 8 Ø 24

Horz Vert

2.2 *

4,3

GROUND SNOW LOAD (psf) WIND SPEED (MPH)

IMPORTANCE - WIND IMPORTANCE - SEISMIC

WIND CODE

CLOSED/OPEN

SEISMIC ZONE

Grout (in) Col Base_Plate (in) Thick Qty Dia __Length´ Line Line Width 0.750 0.750 11.50 11.50 0.375 0.375 6,000 RIGID FRAME:

BASIC COLUMN REACTIONS (k) ------Snow-----Wind_Left1- -Wind_Right1-Horiz Vert Horiz Vert Horiz Vert --Dead-----Collateral-Vert 0.9 1.0 Horiz Vert Horiz Vert
1.1 4.5 1.8 7.3
-1.1 4.7 -1.8 7.5 Horiz Vert 0.3 1.1 -0.3 1.2 Line Line Horiz 4 C 0.2 4 A -0.2 --Wind_Long2---Wind_Long1-Horiz Vert Horiz Vert 0.5 -5.6 0.6 -4.0 0.1 -7.1 -0.6 -4.7 Frame Column -Seismic_Long -MIN_SNOW--

Vert 4.5 Horiz Vert 0.0 -1.4 0.0 -2.1 Horiz Ve 1.1 -1.1 Line C Frame Column -----Dead-----Collateral-----Live-----Snow-----Wind_Left1- -Wind_Right1-Vert 2.4 2.4 Horiz 0.4 -0.4 Vert Horiz 1.6 0.7 1.7 -0.7 Horiz 2.6 –2.6 Vert Horiz Vert 9.3 4.2 15.0 9.6 -4.2 15.5 Line --Wind_Long1- --Wind_Long2-Horiz Vert Horiz Vert 0.6 -9.1 0.9 -6.5 0.1 -10.6 -1.1 -7.0

Horiz 2.6 -2.6 Horiz Vert 0.0 -1.4 0.0 -2.1 Vert 9.3 9.6 Frame lines: 2 3

ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES Grout (in) Anc._Bolt Qty Dia Col Base_Plate (in) Thick Line Width Line Length 0.625 7.000 8.000 0.250 0.0 2 0.625 7.000 8.000 0.250 0.0 0.625 7.000 8.000 0.250 0.0 2 0.625 7.000 8.000 0.250 0.0

This item has been electronically signed and sealed by Yuangang (Bill) Li S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

> Professional Engineer CERTIFICATE NO 49484 YUANGANG (BILL) LI Apr 21, 20

Por Signed

ARIZONA, U.S

Vert -5.5 -4.3

-Seismic_Left Vert -0.5 0.5

Horiz Vert -5.4 -9.8 -1.9 -7.0

-Seismic_Left Horiz Vert -1.1 -0.9

– seisi Horiz – 1.1 – 0.7

Horiz 2.4 2.9

Horiz 3.6 5.1

Seismic_Right Horiz Vert 1.1 0.9 0.7 -0.9

-4.8

Seismic_Right Horiz Vert 0.7 0.5 0.4 -0.5

Horiz -2.8 -0.8

Horiz -0.7 -0.4

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDI			7301 EA	ID\/IE\W	HOUSTON, TEXAS,	D 0 DOV 40338	
							MUGIII	; () [,] [,]		ZIP 7704		(713) 466–7788		
							BUILDING	SYSTE	m s =			(
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	1 & MAINTENANO	CE		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDIN	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A		19-B-34172	F2	0


Proj (in)

2.00 2.00 2.50 2.00

(h)

FLOOR REACTION NOTE:


FOR VERTICAL LOADS, UPWARD IS POSITIVE AND DOWNWARD IS NEGATIVE. FOR HORIZONTAL REACTIONS, TO THE RIGHT IS POSITIVE AND TO THE LEFT IS NEGATIVE. FOUNDATION LOADS ARE IN OPPOSITE DIRECTIONS.




This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN								
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7701 END	TEW HOUSTON TEVAS	D O DOV 40779	
								<u>, </u>		ZIP 77041	IEW, HOUSTON, TEXAS, (713) 466-7788	ZIP 77240	
							BUILDING	SYSTER	as 🖳		,		
						PROJECT:	JIM CRAWFORD						
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E	OW	NER: JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301					
						CAD	DATE	SCALE	PHASE	BUILDING	ID JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A	19-B-34172	F.3	0







MEMBER TABLE										
ROOF PLAN	V									
MARK	PART	LENGTH								
P-1	10X25Z13	29'-5 1/2"								
P-2	10X25Z12	31'-11 1/2"								
P-3	10X25Z13	27'-5 1/2"								
E-1	10ES2H14	26'-11 '1/2"								
E-2	10ES2H14	26'-11 1'/2"								
E-3	10ES2H14	24'-11 1/2"								
E-4	10ES2L14	24'-11 1/2"								
E-5	10ES2L14	26'-11 1/2"								
E-6	10ES2L14	26'-11 1/2"								
CB-5	1/2" DIA. ROD	28'-11" [']								
CB-6	1/2" DIA. ROD	29'-4"								
CB-7	1/2" DIA. ROD	29'-2"								
CB-8	1/2" DIA. ROD	28'-10"								



ROOF FRAMING PLAN

This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

GENERAL NOTES:


- 1. INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
 2. ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
 4. DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING.
- MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.


 5. DO NOT STACK SHEET BUNDLES ON ROOF, ONLY RAISE INDIVIDUAL


SHEETS AS NEEDED.	
6. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF	METAL
SHAVINGS CAUSED BY DRILLING.	

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	CM				[[[]		1 FAIRVIEW, HOUSTON, TEXAS, P.O. BOX 403			
						[]				ZIP 77				
			BUILDING SYST	SYSTER	¶s ─									
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	MER: STEEL ERECTION & MAINTENANCE				OWNER	: JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILD	ING ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1		A	19-B-34172	E1	0









ZIP 77240

SHEET NUMBER

E3

19-B-34172

ISSUE

PW03001/DET13

QUAN

MEMBER TABLE FRAME LINE A MARK

DH-1

G-15 G-16 G-17

8X35C14 8X35C14

10ES2H14 10ES2H14

10ES2H14

8X25Z16 8X25Z16

8X25Z16

8X25Z16 8X25Z16 8X25Z16 8X25Z16 8X25Z16 5/8" DIA.

17'-11 3/4" 26'-11 1/2" 24'-11 1/2" 28'-5 1/2" 7'-1 3/4" 8'-1 3/4" 8'-1 3/4" 29'-11 1/2" 26'-5 1/2" 30'-4"

CONNECTION PLATES
FRAME LINE A

DID MARK/PART
1 CL753
2 CL751

SIDEWALL SHEETING & TRIM: FRAME LINE A

DESCRIPTION

DATE

PANELS: 26 Gauge PBR - TBD

PW02107/DET12

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings

Non-Standard PBR Wall Panel Fasteners

PW03001/DET13

19,

F73

GENERAL NOTES:

- 1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING. 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
- 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL

SHAVINGS CAUSED BY DRILLING.


ISSUE FOR ERECTOR INSTALLATION MDB SN CM 7301 FAIRVIEW, HOUSTON, TEXAS, P.O. BOX 40338 ZIP 77041 (713) 466-7788 └─ BUILDING SYSTEMS └ PROJECT: JIM CRAWFORD CUSTOMER: STEEL ERECTION & MAINTENANCE OWNER: JIM CRAWFORD LOCATION: PRESCOTT,AZ 86301 DATE PHASE BUILDING ID JOB NUMBER SCALE

4/20/23

N.T.S.

BY CK'D DSN





SIDEWALL SHEETING & TRIM: FRAME LINE C

F73

Non-Standard PBR Wall Panel Fasteners

PW02107/DET12

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings

GENERAL NOTES:

- 1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
- SHAVINGS CAUSED BY DRILLING.

l	2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
l	3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE
	CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT
	APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
l	4 AFTER INSTALLATION WIPE ALL PANELS CLEAN OF METAL

PANELS: 26 Gauge PBR - TBD

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ			7 7 7 7	ון שנ	7301 [/	IDV/IEW	HOUSTON, TEXAS, P	O DOV 40339	
]][\			11 1 11	7301 FA ZIP 770		(713) 466–7788		
						، کا	BUILDING	SYSTE	Ms =					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANO	CE		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	1	١ .	19-B-34172	E4	0

This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.



LENGTH

24'-11 1/2"

26'-11 1/2"

26'-11 1/2"

26'-5 1/2"

26'-5 1/2"

29'-11 1/2"

28'-5 1/2"

ROD 27'-4"

10ES2L14 10ES2L14 10ES2L14 8X25Z16 8X25Z16 8X25Z16 8X25Z16 8X25Z16 1/2" DIA.

BEARING FRAME ONLY!


WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN : WASHER NOT NEEDED ON CLIP SIDE.


	BOLT TABLE FRAME LINE 1				
_L	LOCATION	QUAN	TYPE	DIA	LENGTH
SIDE.	Columns/Raf	4	A325	1/2"	1 1/4"

MEMBER T	ABLE	
FRAME LIN	E 1	
MARK	PART	LENGTH
EC-1	8F25C14	12'-7 7/8"
EC-2	8F35C12	15'-5 1/2"
EC-3	8F25C12	18'-3 1⁄8"
ER-1	8F70D12	35'-5 5/16"
G-1	8X25Z16	16'-1 3 [′] /4"
G-2	8X25Z16	4'-8 3/4"
CB-1	1/2" DIA. ROD	24'-6"
CB-2	1/2" DIA. ROD	22'-7"

	FLANGE FRAME	BRACE TABL	E
	\triangle ID	PART	LENGTH
1	FB29.5	L2X2X14G	2'-5 1/2"
2	FB6-1	L2X2X1/8	2'-5 1/2"

CONIN	ECTION PLATES
LERAM	F LINF 1
110 00	
LUIU -	MARK/PART
1	CL 558
	ULJJ0
1 2	SC5
	303





ENDWALL SHEETING & TRIM: FRAME LINE 1 PANELS: 26 Gauge PBR - TBD

Non-Standard PBR Wall Panel Fasteners

-(D4)

(E8)+

EC-1

35'-0" OUT-TO-OUT OF STEEL

(C4)—

EC-2

ENDWALL FRAMING: FRAME LINE 1

D4)-

EC-3

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings

GENERAL NOTES:

12 2"

- 1. INSTALL ALL GIRTS AND FLANCE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
- 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL

SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ				. [m	7301 FAII	D\/IE\M	HOUSTON, TEXAS, P.O) DOV 40339	
								<u> </u>		7501 FAII ZIP 7704	,	(713) 466–7788	ZIP 77240	
							BUILDING	SYSTER	as 🖳			<u> </u>		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E	(OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDIN	G ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А		19-B-34172	E5	0



BEARING FRAME ONLY!

WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLT TABLE FRAME LINE 4 LOCATION Columns/Ra

MEMBER T		
FRAME LIN	E 4	
MARK	PART	LENGTH
EC-4	8f35C14	16'-0 9/16"
DJ-2	8X35C14	13'-11 3/4"
DJ-3	8X35C14	11'-11 3'/4"
G-3	8X25Z16	1'-11 3/4"
G-4	8X25C16	17'-1 3'/4"
G-5	8X25Z16	9'-1 3/8"
G-6	8X25Z16	1'-10"
G-7	8X25Z16	2'-1 3/4"
G-8	8X25Z16	10"
G-9	8X25C16	17'-1 3/4"
G-10	8X25Z16	4'-11,3'/4"
JB-2	8X35C14	2'-10"
JB-3	8X35C14	2'-1 9/16"
JB-4	8X35C14	3'-5 9/16"
JB-5	8X35C14	1'-9 9/16"

	1-9 9/16								
	·								
I CONN	IECTION PLATES								
FRAME LINE 4									
□ID	MARK/PART								
1	SC530								
2	l d2								
2 3	d1								
4	SC484								
4 5	CL753								
6	CL750								
7	CL751								
8	n2								

 \bigcirc B 20'-0 3/4" 19'-8 3/4" F482 17'-8 3/4" 3/4" 17'-2 F482 15'-2 14'-8 F73 PW02107/DET12

ENDWALL SHEETING & TRIM: FRAME LINE 4 PANELS: 26 Gauge PBR - Desert Sand

CL753 at 8" Cold Form Jambs Jamb/Sub Jamb At Cold Form Jamb (Cold Form Shown, (2) $\frac{1}{2}$ $^{\circ}$ Fin Bolts at Hot Rolled Similar) Three Sided Framed Opening. (2) ½"ø Bolts at Four Sided Framed Opening

Jamb to Finish Floor

This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

olessional Eng.

49484

YUANGANG

(BILL)

PIZONA, U.

Non-Standard PBR Wall Panel Fasteners

4 G-

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings

GENERAL NOTES:

- 1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.

35'-0" OUT-TO-OUT OF STEEL

6⁽⁷⁰⁾—

j 5j

ENDWALL FRAMING: FRAME LINE 4

10'-0"

17'-6"

G-10 4

D16 —

4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL

SHAVINGS CAUSED BY DRILLING.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 FA	ID\/IE\W	HOUSTON, TEXAS, P	O ROV 40338	
						[]\				ZIP 770	,		ZIP 77240	
							BUILDING	SYSTER	1 s 🖳					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А		19-B-34172	E6	0

Mark	Qty Top	Bot	Int	Туре	Dia	Lengt	h	Width 6"	Thick	Length	
SP-1	4	4	0	A325	3/4"			б	1/2"	1'-6"	
STIFFENER	TABLE										
Mark	Stiff Mark	Wi		ate Size Thick	Length						
RF1-1 RF1-3	ST1 ST2	2 2	1/2 1/2	1/4" 1/4"	11" 11"						
BASE PLAT	E TABLE					1					
Col Mark	Width		hick	Length							
BP-1	6"	3	/8"	11 1/	2"						
	BRACE; ength(in One Sid 2X2X14G) e; (2)	x (1 c	or 2) iides							3"

MEMBER TAI	BLE			
	Web Depth	Web Plate	Outside Flange	Inside Flange
Mark	Start/End	Thick Length	W x Thk x Length	W x Thk x Length
RF1-1	11.0/11.0	0.134 147.7	5 x 1/4" x 160.4	5 x 1/4" x 147.7
	11.0/11.0	0.156 14.5	5 x 1/4" x 19.7	,
RF1-2	11.0/11.0	0.134 240.0	5 x 1/4" x 240.0	5 x 1/4" x 240.0
	11.0/11.0	0.134 146.1	5 x 1/4" x 144.2	5 x 1 [′] /4" x 144.2
RF1-3	11.0/11.0	0.250 16.5	5 x 1/4" x 19.7	5 x 1/4" x 211.1
	11.0/11.0	0.134 211.1	5 x 1/4" x 227.6	,

CONNECTION PLATES

| ID | Mark/Part | 1 | CL190



This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

GENERAL NOTES:

1. BOLT TIGHTENING — ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIFIED AS SNUG—TIGHTENED JOINTS IN ACCORDANCE WITH THE WITH THE MOST RECENT EDITION OF THE RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS. PRE—TENSIONING METHODS, INCLUDING TURN—OF—NUT, CALIBRATED WRENCH, TWIST—OFF—TYPE TENSION—CONTROL BOLTS OR DIRECT—TENSION—INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG—TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.

- 2. ALL FIELD CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 BOLTS.
- 3. INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 EN	D\/IE\W	HOUSTON, TEXAS,	D O DOV 40339	
]][\	V G G		11 1 11	ZIP 7704	,	(713) 466–7788		
							BUILDING	SYSTER				(, , , , , , , , , , , , , , , , , , ,		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	Œ		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDIN	G ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A		19-B-34172	E7	0



Mark SP-1	Top 4	Bot	Int	Type	Dia 3/4"	Length 2"	Width 6"	Thick 1/2"	Length 2'-0"	
2P-1	4	4	0	A325	3/4		0	1/2	2 -0	
STIFFENER T	TABLE									
Mark	Stiff Mark	Wi		late Size Thick	Length					
RF2-1 RF2-3	ST1 ST2	2 2	1/2 1/2	1/4" 1/4"	18" 24"					
BASE PLATE	TABLE	·				7				
Col Mark	Width	Plate T	Size hick	Length						
BP-1	6"	3	/8"	10 1/2	2"					

MEMBER TAE	BLE				
	Web Depth	Web P	late	Outside Flange	Inside Flange
Mark	Start/Ënd	Thick	Length		W x Thk x Length
RF2-1	10.0/18.0	0.134	163.4	5 x 1/4" x 160.4	5 x 1/4" x 143.1
	, i			5 x 1/4" x 26.8	•
RF2-2	17.0/17.0	0.134	240.0	5 x 1/4" x 240.0	5 x 1/4" x 240.0
	17.0/17.0	0.134	126.8	5 x 1′/4" x 123.9	5 x 1/4" x 123.9
RF2-3	24.0/24.0	0.156	24.7	5 x 1/4" x 32.9	5 x 1/4" x 203.3
	24.0/10.0	0.134	202.9	5 x 1′/4" x 227.6	,

CONNECTION PLATES

□ ID | Mark/Part

1 | CL190

26 Gauge PBR, Desert Sand 27.	35'-10 3/4" 35'-5 13/16" 8 @ 4'-5 1/4" FB33.8M(1) FR2-2	RF2-3 RF2-3 RF2-3 RF2-3 RF2-3 RF2-3 SP-1 SP-1
8 1/4" BP-1 1'-6 1/2"	30'-0 1/2" CLEARANCE +/-	2'-0 1/2" BP-1 8 1/4"
	35'-0" OUT-TO-OUT OF STEEL	
C		A
	RIGID FRAME ELEVATION: FRAME LINE 2 3	

This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


GENERAL NOTES:


1. BOLT TIGHTENING — ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIFIED AS SNUG—TIGHTENED JOINTS IN ACCORDANCE WITH THE WITH THE MOST RECENT EDITION OF THE RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS. PRE—TENSIONING METHODS, INCLUDING TURN—OF—NUT, CALIBRATED WRENCH, TWIST—OFF—TYPE TENSION—CONTROL BOLTS OR DIRECT—TENSION—INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG—TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.


- 2. ALL FIELD CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 BOLTS.
- 3. INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN.

			_											
ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 EA	IDV/IEW	HOUSTON, TEXAS,	D O DOV 40779	
]]	MURIUE			ZIP 770	,	(713) 466–7788		
							BUILDING	SYSTE				(
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANO	Œ		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDIN	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A		19-B-34172	E8	0












SIDEWALL LINER SHEETING & TRIM: FRAME LINE C
PANELS: 26 Gauge PBR - Polar White

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN					7				
A	4/17/23	FOR CONSTRUCTION PERMIT	MDB	SN	СМ]	1 FAIDVIEW	HOHETON TEVAS	D O DOV 407	70
										ZIP	77041	HOUSTON, TEXAS, (713) 466-7788		
								ING SYS	STEMS -	1]		, ,		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANO	Œ	0	OWNER: JIM C	RAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDING	G ID	JOB NUMBER	SHEET NUMBER	ISSUE
						1	4/17/23	N.T.S.	1	А	19	9−B−34172	E-9	0












ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN								
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDE			7701 FAID	/IEW LIQUETON TEVAS	D O DOV 40770	
										ZIP 77041	/IEW, HOUSTON, TEXAS, (713) 466-7788		
						كا	BUILDING	SYSTER	4s —				
						PROJECT:	JIM CRAWFORD						
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E	OV	NER: JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301					
						CAD	DATE	SCALE	PHASE	BUILDING	ID JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А	19-B-34172	DET1	0













ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDI			7301 EA	ID\/IE\W	HOUSTON, TEXAS,	D 0 DOV 40338	
								<u>. </u>	11 1 11	ZIP 770		(713) 466–7788		
							BUILDING	SYSTER	as —			,		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A		19-B-34172	DET2	0












01


														electr	ronic co
ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN										
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENTI	$\Pi\Pi\Pi\Pi$		7701 [, HOUSTON, TEXAS,	D.O. DOV 40339		
]][{		ZIP 77		(713) 466–7788			
							BUILDING	SYSTE				(, , ,)			
						PROJECT:	JIM CRAWFORD								
						CUSTOMER:	STEEL ERECTION	1 & MAINTENANC	Œ		OWNER	: JIM CRAWFORD			
						LOCATION:	PRESCOTT,AZ 8	36301							
						CAD	DATE	SCALE	PHASE	BUILI	DING ID	JOB NUMBER	SHEET NUMBER	ISSUE	
							4/20/23	N.T.S.	1		Α	19-B-34172	DET3	0	


Jun '17

00












ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7701 FA	DV/IEW/	HOUSTON TEVAS	D.O. DOV 40770	
										ZIP 7704		, HOUSTON, TEXAS, (713) 466–7788		
						<u></u>	BUILDING	SYSTER	1s <u></u>					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDIN	IG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А		19-B-34172	DET4	0












ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN								
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 ENI	DIVIEW HOLISTON TEVAS	D 0 DOV 40339	
									. —	ZIP 7704	RVIEW, HOUSTON, TEXAS, 1 (713) 466–7788	ZIP 77240	
-				_				91916	13 —				
						PROJECT:	JIM CRAWFORD						
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E	(OWNER: JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301					
						CAD	DATE	SCALE	PHASE	BUILDIN	G ID JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А	19-B-34172	2 DET5	0











ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7701 F	UDVIEW	HOUSTON TEVAS	D O DOV 40779	
										ZIP 770		, HOUSTON, TEXAS, (713) 466–7788		
							BUILDING	SYSTER	as 🖳					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	: JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILD	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1		١.	19-B-34172	DET6	0








8 GH08 <= 4"

10 GH10 12 GH12



1" Base Plate on JL &

Hot Rolled Jambs

Bolted Clips - Framed Opening Connections - Cold Form and Hot Rolled


This item has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any

Jamb to Finish Floor

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN										
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ				. [m	7301 FA	ID\/IE\M	HOUSTON, TEXAS, P	O DOV 40338		
								; () [4] [4]		7301 TA ZIP 7704	,	(713) 466–7788			
							BUILDING	SYSTER	as =						
						PROJECT:	JIM CRAWFORD								
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD			
						LOCATION:	PRESCOTT,AZ 8	6301							
						CAD	DATE	SCALE	PHASE	BUILDIN	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE]
							4/20/23	N.T.S.	1	A		19-B-34172	DET7	0	





AC01323



Jamb/Sub Jamb to Zee Girt

Jamb/Sub Jamb to Zee Girt





ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 FA	IDV/IEW/	HOUSTON, TEXAS, F	O DOV 40338	
						<u> </u> \		<u> </u>		ZIP 770	,	(713) 466–7788	ZIP 77240	
						اك	BUILDING	SYSTER	as 🖳					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	<i> </i>	١	19-B-34172	DET8	0



Screw Application Page TH06006 Date Rev May '19 01


Standard Grade


Description	Fastener Number	Application
1/4"-14 x 7/8" Type 2	4A	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	17A	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	17B	Member Screw (Up To 6" Insulation)

Long Life

Description	Fastener Number	Application
1/4"-14 x 7/8" Type 1	4	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	3	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	3A	Member Screw (Up To 6" Insulation)









PBR Wall Panel Fastener Location


Page PW05003 Date Rev Aug '15 04




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN										
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 FA	IDV/IEW/	HOUSTON, TEXAS,	D 0 DOV 103	τ Ω	
								<u> </u>		ZIP 770	,	(713) 466–7788			
							BUILDING	SYSTE	иs Ш						
						PROJECT:	JIM CRAWFORD								
						CUSTOMER:	STEEL ERECTION	& MAINTENANO	CE		OWNER:	JIM CRAWFORD			
						LOCATION:	PRESCOTT,AZ 8	36301							
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUM	/BER	ISSUE
							4/20/23	N.T.S.	1	1	4	19-B-34172	DETS)	0









Formed Base Trim Details


This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


olessional Engine


49484 YUANGANG (BILL)

PW02010

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDE			7301 EA	ID\/IE\M	HOUSTON, TEXAS,	D 0 D0V 40338	
								<u>, </u>		ZIP 770		(713) 466–7788		
							BUILDING	SYSTER	as —					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDII	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	Д		19-B-34172	DFT10	0









ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDE			7301 FA	ID\/IE\M	HOUSTON, TEXAS,	D	
						[]		<u>, </u>		ZIP 770	,	(713) 466–7788		
							BUILDING	SYSTER	as 🖳			. ,		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А		19-B-34172	DET11	0











PBR Liner Framed Opening Jamb

Page RL01027 Date Rev Aug '15 05



Wall panel must be held off of base





Channel Closure Trim Piece Mark 8" $8\frac{1}{4}$ " $10\frac{1}{4}$ " 12" $12\frac{1}{4}$ " Member Size 10" Piece Mark F981 F2994 F982 F2993 F169 F2995

Note: The interior leg of the installed Channel Closure Trim is to be orientated $(\pm \frac{1}{8})$ to match the interior leg of the Header or Jamb.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 E	NIDVIEW	HOUSTON, TEXAS,	D.O. DOV 40339	
							MURIUE	;		ZIP 770				
							BUILDING	SYSTER				(1.10)		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	Œ		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILD	ING ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1		4	19-B-34172	DET12	0







(Fluted Only) RBR (Reverse

Rolled PBR)
RBU (Reverse


Rolled PBU)

7.2

HW455

HW459

HW461



PBR Wall Panel

This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDE			7301 FA	ID\/IEW	HOUSTON, TEXAS,	P.O. ROY 40338	
						<u> </u>		<u>, / r/ r/ r/ </u>		ZIP 770		(713) 466–7788		
							BUILDING	SYSTER	as —					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1			19-B-34172	DFT1.3	0

Outside Corner Trim

F830





³age PW03001



PBR Roof - Northern Standard And Northern Large

Page TPR06108





At Lap

Southern Large

F6139/F6081RL

Fastener #14

(9) Required At Lap

Northern Standard

F6140/F6082RL

PBR Roof - Edgecraft High Side Eave Trim Lap Installation

This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any

ISSUE	DATE	DESCRIPTION	BY	CK,D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ			$\Pi\Pi\Pi$		7301 F <i>A</i>	IDV/IEW	HOUSTON, TEXAS,	D	
										7301 17 ZIP 770	,	(713) 466–7788		
							BUILDING	SYSTER				(
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	I & MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	ļ ,	١	19-B-34172	DET14	0

For Roof Runs Greater Than 100'-0"

At Lap

Southern Standard

F6138/F6080RL





(13) Required At Lap


Northern Large

F6141/F6083RL

TPR06012









ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDI			7301 EA	ID\/IE\W	HOUSTON, TEXAS,	D	
						<u> </u>		<u>, </u>	11 1 11	ZIP 7704		(713) 466–7788		
							BUILDING	SYSTER	as 🖳					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDIN	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A		19-B-34172	DET15	0








ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7701 E	NIDV/IEW/	HOUSTON TEVAS	D O DOV 40770	
								;		ZIP 770		HOUSTON, TEXAS, (713) 466-7788		
							UILDING	SYSTER				(1.10)		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANO	Œ		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILD	ING ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1		4	19-B-34172	DFT16	0



PW07022 PBR Wall Panel - Three Sided Framed Opening - Trim Installation with Field Notch Panel at Head Trim Mar '20 05 Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025. Opening Width + 6" (+2" Lap when req'd) Opening Width See PW07023 & PW07027 0 └ Head Trim F481 See PW07030 〈 Note: For "Optional" Channel Closure Trim Fastener #14A $\frac{1}{8}$ " x $\frac{3}{8}$ " Pop Rivet at 1'-8 O.C. at Cold Form OR see PW07028 Fastener #16 12-24 x 1½" SD Pancake DP5 W/O Washer at 1'-8 O.C. at Hot Rolled 1" Bead of HW540 Tube Caulking -- 2" Lap with (2) Fasteners #14 from Header to Floor (see section) 1" x 3" Pop Rivet Typ at Head & Jamb Trim when - Jamb Trim F482 Jamb Trim F482 or Alternate F484 or Alternate F484 required. Field notch as required. See PW07029 - Finish Floor Line Note: All trim is to be Note: Field measure Opening Width installed BEFORE blanket and Height before making field cuts insulation is applied to walls. and adjust cut dimensions accordingly.


PBR Wall Panel - Three Sided Framed Opening Field Notch Panel at Head Trim

Page PW07023 Date Rev Mar '20 05



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN								
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ				. [m	7701 ENIDVII	EW, HOUSTON, TEXAS, P.	O DOV 40339	
						[]\			11 1 11	7301 FAIRVII ZIP 77041		ZIP 77240	
						ا كا	BUILDING	SYSTER	as 🖳				
						PROJECT:	JIM CRAWFORD						
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E	OWN	ER: JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301					
						CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A	19-B-34172	DET17	0






Page PW07024 Date Rev Mar '20 05

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023

OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




and adjust cut dimensions accordingly.

insulation is applied to walls.

PBR Wall Panel - Three Sided Framed Opening - Field Notch and Bend Tabs at Head Trim

Page PW07025 Date Rev Mar '20 05


Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



at Hot Rolled


PBR Wall Panel - Three Sided Framed Opening Jamb Trim Field Cut Details

PW07027
Date Rev
Mar '20 04




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 FA	IDV/IEW	HOUSTON, TEXAS, F	O DOV 40339	
						<u> </u>]\		<u> </u>		ZIP 770	,	(713) 466–7788	ZIP 77240	
							BUILDING	SYSTER	as 🖳			, ,		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILD	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	,	١	19-B-34172	DET18	0






PBR Wall Panel - Three Sided Framed Opening - Jamb Trim Installation




PW07029

Mar '20 05



PBR Wall Panel - Pre-Assembled Walk Door & Glass-Front Walk Door Jamb Trim Installation

Page PW09029 Date Rev Mar '20 05




This if the has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDI			7301 FA	IDV/IEW/	HOUSTON, TEXAS, F	D O DOV 40339	
									11 1 11	ZIP 770	,	(713) 466–7788	ZIP 77240	
							BUILDING							
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDI	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A	١	19-B-34172	DET19	0

PW07030

Oct '19 03








ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ		VIENDE		[m	7301 FA	ID\/IEW	HOUSTON, TEXAS, F	P	
								<u>, 7 [7] [7] </u>		ZIP 7704	,	(713) 466–7788		
							BUILDING	SYSTER	4 S 🖳					
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301						
						CAD	DATE	SCALE	PHASE	BUILDIN	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	A		19-B-34172	DET20	0





This iem has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy. Reciessional Engineer

Recies Sional Engineer

49484

YUAN

ARIZONA, U.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ			7		7701 5	ורועורוע	LIQUICTON TEVAC	D.O. DOV 40770	
								<u>. </u>	J	ZIP 770		HOUSTON, TEXAS, (713) 466-7788		
						L B	UILDING	SYSTER	us 🖳			, ,		
						PROJECT: JI	IM CRAWFORD							
						CUSTOMER: S	STEEL ERECTION	& MAINTENANC	Œ		OWNER:	JIM CRAWFORD		
						LOCATION: P	PRESCOTT,AZ 8	6301						
						CAD	DATE	SCALE	PHASE	BUILD	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	,	١	19-B-34172	DET21	0

Pre-Assembled Door - Girt At 7'-6" With Low / Base Girt Date Rev Nov '18 00 Walk Door Frame Attaching To Bolted Clip Jambs

The Adequacy Of The ½"ø Base Anchor Is Not The Responsibility Of The Building Manufacturer. The Adequacy Of These Base Anchors Should Be Determined By A Qualified Foundation Engineer


Pre-Assembled Door Anchor Placement

AC05280



Horizontal Slide Window

Single Hung Window



Installation Notes:

Window jamb fins are designed for installation at major panel ribs only. Typically windows are located between the 7'-6" girt and the baseline of the applicable wall.

Windows are typically packaged with two PBR Jamb Fins E91 that are not installed on the window unit. Prior to window installation install the jamb fins into the extruded grooves on each side of the window by sliding the fin in from the bottom of the window. The jamb fin should end flush with the top of the window head fin.

As the wall panels are installed, locate the jamb stiffeners at the wall panel major ribs at the desired window locations. Attach the jamb stiffeners to the girt and base members with Fastener #12A, see Jamb Stiffener/Window Isometric. Locate and mark window opening from the outside of the building, see Panel Cutout table for cutout width and height. Make sure the panel cutout height is correct and the panels are cut square. Push the window up until the window head contacts the upper wall panels. Make sure the window is square and level. Attach window unit with jamb fins installed to the jamb stiffeners with Fastener #12A at each corner. Apply Urethane Tube Sealant HW540 to both jamb fins, see Jamb Stiffener/Window Isometric

Apply Urethane Tube Sealant HW540 to both sides of the inside panel closure and insert the closures between the wall panel and insulation at the window head and sill. See Section B.

Attach window head and sill to wall panels with #17A Fasteners at a 5", 7", 5" O.C., see Fastener Spacing at Window Head and Sill. Note: "Fasteners are installed from the inside of the building at the window sill. Attach wall panels to window jamb fins/jamb stiffeners with Fastener #17A at 1'-0" O.C., see Section A.

Apply Urethane Tube Sealant HW540 along both sides between the window jambs and the wall panel to close any gaps. From the outside apply a continuous bead around the outside of the panel profile at the panel base, see Section B.

Install Snap-On Trim E86 at each jamb.

Vinyl Insulation Retainer Notes: The optional Vinyl Insulation Retainer V03 can be installed before or after the window is installed. Install the retainer into the groove on the four interior sides, see Sections A and B. Notch back the tongue of the retainer at least $1\frac{1}{2}$ " on both ends of either the horizontal or vertical retainers, this will allow the retainers to overlap at the four corners.

	Panel Cuto	ut
	Horizontal S	lide
Window ID	Cutout Width	Cutout Height
HS2016	1'-10"	1'-61"
HS3020	2'-10"	2'-01"
HS3030	2'-10"	3'-04"
HS3040	2'-10"	4'-01"
HS4030	3'-10"	3'-01"
HS4040	3'-10"	4'-01"
HS5030	4'-10"	3'-01"
HS6020	5'-10"	2'-01"
HS6030	5'-10"	3'-04"
HS6040	5'-10"	4'-01"
	Single Hu	ng
Window ID	Cutout Width	Cutout Height
H3030	2'-10"	3'-04"
H3040	2'-10"	4'-01"
H3050	2'-10"	5'-0 1 "


	Panel Cutou	ıt
	Fixed	
Window ID	Cutout Width	Cutout Heigh
FW1070	0'-10"	7'-04" (
FW2056	1'-10"	5'-6 1 "
FW2060	1'-10"	6'-0 ¹ "
FW2070	1'-10"	7'-04" (
FW3040	2'-10"	4'-01"
FW4040	3'-10"	4'-0 1 "

(*) Dimension is from baseline


Details shown are for horizontal slide windows. Single hung and fixed window installation details are similar.

Non Thermal Window (C225) Installation Details Horizontal Slide / Single Hung / Fixed Glass PBR Panel With Jamb Stiffeners


AC08310 Date Rev Apr '19 01








Section B - Head/Sill




Section C - Sill at Baseline



Fastener Spacing at Head and Window Sill

Note: Fastener location shown is for the window head, fasteners are installed from the inside at the window sill.



Insulation Section at Window Jamb

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN									
0	4/20/23	FOR ERECTOR INSTALLATION	MDB	SN	СМ					7301 EA	ID\/IE\M	HOUSTON, TEXAS,	D 0 R0V 40338	
						[]		<u>. </u>		ZIP 7704		(713) 466–7788		
							BUILDING	SYSTER	as 🖳			,		
						PROJECT:	JIM CRAWFORD							
						CUSTOMER:	STEEL ERECTION	& MAINTENANC	E		OWNER:	JIM CRAWFORD		
						LOCATION:	PRESCOTT,AZ 8	36301		•				
						CAD	DATE	SCALE	PHASE	BUILDIN	NG ID	JOB NUMBER	SHEET NUMBER	ISSUE
							4/20/23	N.T.S.	1	А		19-B-34172	DET22	0



Field Service Procedures

In Order To Give You Prompt Services And Keep Problems To A Minimum, Please Handle Any Shortages Or Back Charges In The Following Manner:

1. Carefully Check Your Packing List While Unloading.

2. Mark Any Items Which Appear To Be Missing And Notify The Field Service Department At The Number Shown In The Title Block As Soon As Possible. Calling Someone Else Could Delay The Proper Response.

INITIAL CLAIM:

The Event Of An Error. The Customer Must Promotly Make A Written Or Verbal "Initial Claim" to The Manufacturer For The Correction Of Design, Drafting, Bill O Materials Or Fabrication Error. The "Initial Claim" Includes:
1. Description Of The Nature And Extent Of The Errors, Including Quantities

- 2. Description Of The Nature And Extent Of Proposed Corrective Work.
- Including Estimated Man-Hours Materials To Be Purchased From Other Than the Manufacturer, Including
- Mouterials to be Furchased From Other Inan the Manufacturer, Including Estimated Quantities and Cost.
 Maximum Total Cost Of Proposed Corrective Work And Materials To Be Purchased From Other Than The Manufacturer.

SHORT MATERIALS:
Immediately Upon Delivery Of Materials, Quantities Are To Be Verified By The Customer Against Quantities That Are Billed On The Shipping Documents. Neither The Manufacturer Nor The Carrier Is Responsible For Material Shortages Against The Quantities Billed On The Shipping Documents If Such Shortages Are Not Noted On The Shipping Documents When The Material Is Delivered And Acknowledges of the Corner's Agent. If the Customer To The Common Carrier, Claims For Shortages Are To Be Made By The Customer To The Common Carrier, If The Material Quantities Received Are Correct According To The Quantities Billed On The Shipping Documents, But Are Less Than The Quantities Ordered Or The Quantities That Are Necessary To Complete The Metal Building According To The Order Documents, Claim Is To Be Made To The Manufacturer

DAMAGED OR DEFECTIVE MATERIAL:

Damaged Or Defective Material, Regardless Of The Degree Of Damage, Must be Noted On The Shipping Documents By The Customer And Acknowledged By The Carrier's Agent. The Manufacturer Is Not Responsible For Material Damaged In Unloading Of Packages Or Nested Materials, Including, But Not Limited To Fasteners, Sheet Metal, "C" And "Z" Sections And Covering Panels That Become Wet And/Or Damaged By Water While In The Possession Of Others. Packaged Or Nested Material That Become Wet In Transit Must Be Unpacked, Unstacked And Dried By The Customer. If The Carrier Is The Manufacturer, The Customer Mus Make Claim For Damaged Directly To The Manufacturer. If The Carrier Is A Common Carrier, The Customer Must Make The Claim For Damage To The Common Carrier. The Manufacturer Is Not Liable For Any Claim Whatsoever Including, But Not Limited To Labor Charges Of Consequential Damages Resulting From Customer's Use Of Damaged Or Defective Materials That Can Be Detected By Visual Inspection.

EXCESSIVE MATERIAL:
The Manufacturer Reserves The Right To Recover Any Material Delivered In Excess
Of Those Required By The Order Documents.

OIL CANNING IS NOT A CAUSE FOR REJECTION

Authorization For Corrective Work

Normal Erection Operations Include The Correction Of Minor Misfits By Amounts Of Reaming, Chipping, Welding Or Cutting And The Drawing Of Elements Into Line
Through The Use Of Drift Pins. Errors That Cannot Be Corrected By The Foregoing
Means Or Which Require Major Changes In The Member Configuration Should Be
Reported Immediately To The Owner And The Fabricator By The Erector, To Enable Whoever Is Responsible Either To Correct The Error Or Approve The Most Efficient And Economical Method Of Correction To Be Used By Others, (AISC 303-10. Section 7.14). If The Error Is The Fault Of The Manufacturer An "Authorization For Corrective Work" Must Be Issued In Writing By The Manufacturer To Authorize The Corrective Work At A Cost Not To Exceed The Maximum Total Cost Set Forth Alternative Corrective Work Other Than That Proposed In The "Initial Claim" May Be Directed By The Manufacturer In The "Authorization Of Corrective Work" Only The Field Service Department May Authorize Corrective Wor

The "Final Claim" In Writina Must Be Forwarded By The Customer To The Manufacturer Within (10) Days Of The Completion Of The Corrective Work Authorized By The Manufacturer.

THE "FINAL CLAIM" MUST INCLUDE:

- FINAL CLAIM MUST INCLUDE:

 Actual Number Of Man-Hours By Dated Of Direct Labor Use On Corrective
 Work And Actual Hourly Rate Of Pay.

 Taxes And Insurance On Total Actual Direct Labor.

 Other Direct Costs On Actual Direct Labor.
- Cost Of Materials (Not Minor Supplies) Authorized By The Manufacturer To Be Purchased From Other Than The Manufacturer, Including Copies Of

5 Total Actual Direct Cost Of Corrective Work (Sum Of 1 2 3 And 4) The "Final Claims Are Credited To The Customer By The Manufacturer In The Amount Not To Exceed The Lesser Of The Maximum Total Cost Set Forth The "Authorization For Corrective Work" Or The Total Direct Cost Of

** IMPORTANT NOTE **

Cost Of Equipment (Rental Or Depreciation), Small Tools, Supervision, Overhead And Profit Are Not Subjected To Claims.

SHIPMENT ARRIVAL TIME: Every Effort Will Be Made To See That The Carrier Arrives At The Jobsite On The Requested Hour. Manufacturer Makes No Warranty And Accepts No Responsibility For Costs Associated With A Shipment Not Arriving At The Requested Time Unless A Separate Agreement Has Been Made In Writing For A Guaranteed Arrival Time.

Unloading, Handling And Storage

STRUCTURAL:

A Great Amount Of Time And Trouble Can Be Saved If The Building Parts Are Unloaded At The Building Site According To A Pre-Arranged Plan. And Handling Of Components Will Eliminate Unnecessary Handling.

Piece Marks Are Stenciled On The Primary Structural Members At The Lower End. 1'-0" From The End. Inspect All Shipments Prior To Releasing The Tie-downs For Loads That May Have Shifted During Transit.

REMEMBER SAFETY FIRST.
Blocking Under Columns And Rafters Protect The Splice Plates And The Slob From Damage During The Unloading Process. It Also Facilitates The Placing Of Slings And Cobles Around Members For Later Lifting And Allows Members To Be Bolted Together Into Sub-assemblies While On The Ground. Extra Care Should Always Be Exercised In The Unloading Operation To Prevent Injuries From Handling Steel And To Prevent Damage To Materials And The Concrete Slob. If Water Is Allowed To Remain For Extended Periods In Bundles Of Primed Parts Such As Girts, Purlins, c., The Pigment Will Fade And The Paint Will Gradually Soften Reducing Its Bond The Steel. Therefore, Upon Receipt Of A Job, All Bundles Of Primed Parts Should Be Stored At An Angle To Allow Any Trapped Water To Drain Away And Permit Air Circulation For Drying. Puddles Of Water Should Not Be Allowed To Collect And Remain On Columns Or Rafters For Same Reason.

Short Period Of Exposure To Ordinary Atmospheric Conditions. The Coat Of Shop Primer Does Not Provide The Uniformity Of Appearance, Or The Durability And Corrosion Resistance Of A Field Applied Finish Coat Of Paint Over Shop Primer

Roof And Wall Panels


Manufacturer's Roof And Wall Panels Include Color Coated, Galvalume, And Galvanized, Provide Excellent Service Under Widely Varied Conditions. All Unloadir And Erection Personnel Should Fully Understand That These Panels Are Quality Merchandise, Which Merits Cautious Care And Handling

UNDER NO CIRCUMSTANCES SHOULD PANELS BE HANDLED ROUGHLY Packages Of Sheets Should Be Lifted Off The Truck With Extreme Care Taken To Ensure That No Damage Occurs To Ends Of The Sheets Or to Side Ribs. The Packages Should Be Stored Off The Ground Sufficiently High To Allow Air Circulation Underneath The Packages. This Avoids Ground Moisture And Deters People From Walking On The Packages. One End Of The Package Should Be Elevated To Encourage Drainage In Case Of Rain. The Manufacturer Exercises Caution During Fabrication An Shipping Operations To Ensure That All Panel Stock is Kept Dry. However Due To Climatic Conditions, Water Formed By Condensation Of Humid Air Become Trapped Between Sheets. Water Can Also Be Trapped Between The Stacked Sheets When Exposed To Rain. This May Discolaration Caused By Trapped Moisture. The Stain Is Usually Superficial And Has Little Effec On The Appearance Or Service Life Of The Panels As Long As It Not Permitted To Remain On The Panel, However, Moisture In Contact With The Surface Of The panel Over An Extended Period Can Severely Attack The Finish And Reduce The

Care Should Always Be Taken When Walking On Panels. Use Safety Lines And Net When Necessary. Panels Are Slippery, Wipe Dry Any Moisture Or Surface Material That Has Puddle From Bundles Stored On A Slope. Dew, Frost, Or Other Forms Of Moisture Greatly Increase The Slipperiness Of The Panels. Always Assume Panel Surface Is Slippery And Act Accordingly. Never Walk Of Step On Skylights Or Translucent Panels.

Effective Service Life See R1-07 Titled "Damage From Condensation Or Trapped

Use Wood Blocking To Elevate And Slope The Panels In A Manner That Allows Noisture To Drain. Wood Blocking Placed Between Bundles Will Provide Additional Air Circulation. When Handling Or Uncrating The Panels, Lift Rather Than Slide Them Apart. Burred Edges May Scratch The Coated Surfaces When Sheets Are Slid Over One Another. Never Allow Panels To Be Walked On While On The Cround.



Roof And Wall Panel Damage During Construction

The Quality Of Workmanship In Steel Construction Practices And Handling Methods Used During The Construction Of The Metal Building Can Significantly Affect The Appearance And Performance Of The Building Panels, Panel Damage During Construction Can Be The Result Of Faulty Installation Methods And/or

Overdriven Fasteners Cause Indentations Or Shallow Pockets In The Panel Around The Fastener Head. Rain Water Or Condensation Moisture Combined With Atmospheric Pollutants (principally Sulfur Dioxides) And Dirt Particles Collect In These Pockets. The Combination Of Pollutants And Water Creates Acid Solutions That Will Cause Corrosion Damage To The Panel And Fastener. Rain May Wash Some Pollutants Away, But Moisture In Form Of High Humidity Can Keep These Areas Wet And Continue The Problem. Overdriving The Fastener Also Forces The Sealing Washer From Under The Head Creating A Leak At This Point Proper orgue Adjustment Of The Screw Gun Or Preferably The Use Of A Depth Gauge

It is Extremely Important That All Drill Shavings From The Installation Of Panel Fasteners And Fillings From The Sow Cutting Of Panels Be Removed From The Panel Surface. Corrosion Can Occur In A Matter Of Hours When These Shavings Or Fillings Are Not Removed And Are In Contact With Water Or Condensed Moisture. When Panels Are Pre-Drilled Or Cut In The Stack Prior To Erection All Shavings Must Be Cleaned From Both Sides Of The Panel To Prevent Corrosion Of The Must Be Cleaned From Both Sides Of the Monel to Prevent Corrosion Of the Panel By These Particles. It Is Imperative That The Roof Be Swept Clean At Least Daily And Certainly At Job Completion. The Final Cleaning Of The Roof Should Be Done Prior To Installing The Gutter So That The Shavings Are Not Deposited Into The Gutter And Left To Corrode. Any Other Foreign Objects Or Debris Left By Construction Personnel Should Also Be Removed From The Roof During The Erection Of The Roof And The Installation Of Such Equipment As Air Condition

Personnel Walking On The Panel Can Cause Damage, Workmen Should Step Or Walk In The Broad Flat Areas Of The Panel And Avoid Stepping On The Panel Ends And Edges Which Can Be Bent By Careless Handling. If This Damage Is Severe. The Edges Must Be Straighten Prior To Erection Since The Appearance And/or Weather Tightness Of The Panel Could Be Affected. Dragging One Panel Across Another Can Cut Or Abrade The Coating Causing Unsightly Marks On The

Attempts To Erect Panels During Windy Conditions Should Be Avoided To Prevent

Leaving Dirt Piled Against The Exterior Wall Panels At The Foundation Will Cause Panel Damage. This Dirt May Be Wet Or At Least Contain Some Moisture. Mud May Have Splashed Onto The Wall During Construction. Corrosion Damage May Occur Where This Dirt Or Mud Contacts The Panel. In Areas Where Lime Stabilization Of The Soil Is Required, Corrosion Damage From The Soil's Content Will Be Accelerated And Most Likely Be Severe. All Dirt Must Be Removed From The Panel Walls At The Time Of Completion Of Work. Pre-Painted Panels May Require Touch-up If The Coating Has Been Damaged During Handling Or Erection.

The Appearance Of The Building May Re Affected If Damaged Spots Or Scratches Are Located in Highly Visible Places Such As Around Doors, Windows, Etc.. If
Damage is Extensive Then Replacement Of The Entire Panel Should Be Considered.

Types Of Finishes

SHOP PRIMED STEEL:
All Structural Members Of The Metal Building System Not Fabricated Of Corrosion Resistant Material Or Protected By A Corrosion Resistant Coating Are Painted With One Coat Of Shop Primer Meeting The Performance Requirements Of SSPC Paint Specification No.15. The Coat Of Shop Primer Is Intended To Protect The Steel Framing For Only A Short Period Of Exposure To Ordinary Atmospheric Conditions. Shop Primed Steel Which is Stored in The Field Pending Erection Should Be Kept Free Of The Ground And So Positioned As To Minimize Water Holding Pockets, Dust, Mud And Other Contamination Of The Primer Film. Repairs Of Damaged To Primed Surfaces And/Or Removal Of Foreign Material Due To Improper Field Storage Or Site Conditions Are Not The Responsibility Of The Manufacturer. The Manufacturer Is Not Responsible For Deterioration Of The Shop Coat Of Primer Or Corrosion That May Result From Exposure To Atmospheric And Environmental Conditions, Nor The Compatibility Of The Primer To Any Field Applied Coating. Minor Abrasions To The Shop Coat (Including Galvanizing) Caused By Handling, Loading, Shipping, Unloading And Erection After Painting Or Galvanizing Are Unavoidable. (MBMA 2012, Chapter IV 4.2.4).

GALVALUME:

Galvalume Is The Trade Name For A Patented Steel Sheet And Coil Product Having A Coating Of Corrosion Resistant Aluminum—Zinc Alloy. The Mixture Is Balanced To Obtain The Coating That Retains The Corrosion Resistance And Heat Reflectivity Of Aluminum And Galvanic Protection Of Zinc. The Best Properties Of Both Aluminum And Zinc Are Combined In This Coating And Offer Added Service Life For The Building.

<u>Pre-Pointed:</u>
Using Galvalume Steel As A Substrate, Pre-Pointed Steel Is Given An Additional Rust Inhibitor Primer Coat. This Primer Coat Further Increases The Corrosion Resistance. These Coatings Are Applied To The Exterior Surface Of The Panels And A Wash Coat Designed Only For Interior Use, is Applied On The Opposite Sid Galvalume And Pre-Painted Steel Can Give Excellent Service For Many Years If A Few Rules Concerning Their Care And Maintenance Are Observed, All Of These hes Are Equally Subject To Damage And Corrosion When Care Is Not Provided.

PAINT AND COATING MAINTENANCE:

nove Smudge Marks From Bare Galvalume: Formula 409 Has Proven To Be Somewhat Effective. Lightly Rub With A Clean Cloth And Rinse With Water. Do Not Rub More Than Required To Remove Smudge Marks. No Product Will Remove All Smudge Marks. Remove Rust Stains:


Soft Scrub Without Bleach Has Proven To be Somewhat Effective Rub With A Soft Cloth And Rinse With Water. Do Not Rub More Than Required To Remove Stain. No Product Will Completely Remove Rust Stains. To Touch-Up Scratches In Paint (Not Bare Metal):

Clean Area To Be Painted With Mild Detergent. Rinse Thoroughly And Dry. Using A Small Artist's Brush, Lightly Apply A Minimal Amount Of Color Matched Touch-Up Pain Required To Fill/Cover The Scratch. Contact The Building Manufacturer For Assistance With Ordering/Purchasing Touch-Up

Damage From Condensation Or Trapped Water

It is Extremely Important That The Panels Be Monitored For Evidence Or Trapped Water Or Moisture Condensation While Awaiting Erection. High Humidity Conditions With Temperature Cycling Will Cause Condensation Between Panels Within The Bundle. Condensation Can Occur Frequently Near The Sea Coast Or Other Large Bodies Of Water.

If Jobsite Covers Are Used, They Should Be Tied Away From The Bundle At Corners To Allow Air Circulation Around The Bundle. This Will Help Prevent Moisture Evaporating From The Ground Or Building Floor From Condensing On The Panels, Plastic Or Other Impermeable Covers Are Not Recommended, Immediate Action Is Required If The Panels Are Found To Be Wet From Any Cause. The Bundles Must Be Opened And Each Panel Un—Stacked And Throrughly Dried On Both Sides. Re—Stacking The Panel At A Slight Angle To Each Other To Prevent Nesting Will Allow Air Circulation And Assist In Keeping The Panel Dry. In Severe Conditions Large Fans Can Be Used To Circulate Air Between The Un-Stacked Panels And Accelerate Drying, Damage To The panel Coating Occurs When Panels Become Wet And Are Allowed To stay wet, damage Can Occur To Nested Panels Within 24 to 48 Hours. This Damage Shows Corrosion And Discoloration Of The Panel Surface And Is Commonly Called Wet Storage Stain, Zinc Oxidation, Or



A Softening Of The Paint Film Can Occur With Pre-Painted Steel Under Wet Storage Conditions And The Durability Of The Panel Finish Substantially Decrease. Bare Galvanized And Galvalume Panels React More Quickly To Surface Oxidation Since They Lack The Additional Protection Of Paint. Zinc Coated Or Galvalume Panels Under Normal Exposure Form A Zinc Aluminum Oxide Film On Their Surface Allowing A Slow Oxidation Process Called "Weathering" To Occur That Inhibits Further Corrosion. In Nested Bundles Constant Contact Of The Panels With Condensed Or Trapped Water Prevents This Weathering Process.

Rapid Oxidation Of The Zinc or Zinc Aluminum Coating Can Now Occur And May Lead To "Red Rust" In A Short Time. If Discoloration Or Stains Are Minor A Household Cleaner Of The Type Used On Porcelain Sinks And Bathtubs May Be Used To Remove Stains, Wire Brushing Or Abrasive Materials Should be Avoided Since Scratching Or Removal Of The Coating Could Occur. Panel With Significant Damage Should Be Replaced By The Buyer Prior To Erection.

Safety Commitment

The Builder/Contractor Is Responsible For Applying And Observing All Pertinent Safety Rules And OSHA Standards As Applicable

The Building Manufacturer Has A Commitment To Manufacture Quality Building Components That Can Be Safely Erected. However The Safety Commitment And Job Site Practices Of The Erector Are Beyond The Control Of The Building

It Is Strongly Recommended That Safe Working Conditions And Accident Prevention Practices Be The Top Priority Of Any Job Site.

Local, State And Federal Safety And health Standards, Whether Standard Statuary Or Customary, Should Always Be Followed To Help Ensure Worker Safety

Make Sure All Employees Know The Safest And Most Productive Way Of Frecting A Make Sale Air Employees Annual me Salest Aird Most Productive May be Building, Emergency Procedures Should Be Known To All Employees. Daily Meetings Highlighting Safety Procedures Are Also Recommended. The Use Of Hard Hats, Rubber Sole Shoes For Roof Work, Proper Equipment For Handling Material And Safety Nets Where Applicable Are Recom

Manufacturer Will Exceed 4,000 Pounds. For Further Information Also reference
The Bill Of Materials For Individual Member Weights Of Structural Members. If Additional Information Is Required Contact The Field Service Department

Excessive Ice And Snow Removal Should Be Removed From The Roof Immediately To Prevent Damage To Roof And Possible Collapse. Do Not Use Metal Tools To remove The Ice Or Snow As This Can Damage The Paint And/Or Galvalume Coatings. Also Be Careful Around Pipes And Flashing's. Be Extremely Careful If Your Roof Has Light Transmitting Panels. These Panels Will

Not Support A Person's Weight And Will Be Difficult Or Impossible To See If They Are Covered With Ice Or Snow. See MBMA Low-Rise Building Systems Manual, Appendix AB For Details on Snow Removal Procedures. These Procedures Should Commence When Half Of The Design Roof Snow Load Is Realized.

DEBRIS REMOVAL:

Any Foreign Debris Such As Sawdust,Dirt, Leaves, Animal Droppings, Etc. Will Cause Corrosion Of The Roof, Gutters, Trim, Etc. If Left On The Building Surface For A Long Enough Time. The Roof Should Be Periodically Inspected For Such Conditions And If Found. They Should Be Rectified In A Manner Consistent With These Roof Maintenance Guidelines Never Allow Treated Lumber O Concrete/Mortar/Grout To Come In Contact With Roof Panels, Especially Galvalume For Extended Periods Of Time.

PERIODIC INSPECTION:
All High-Strength Shall Be Periodically Be Inspected For Tightness. Particularly In Crane Buildings And After Seismic Or Wind Activity. The Crane Manufacturer Will Specify A Minimum Period But It Should Not Exceed Two Years.

- 1. Keep Roof Free Of Debris And Keep Debris Out Of Gutter To Allow Water
- Quickly Drain From The Roof.

 2. Do Not Use Wood Blocking To Hold Equipment Off The Panel Seams. This Blocks The Flow Of Water And Hold Moisture.

 3. Do Not Allow Rooftop AC Units Or Evaporative Coolers To Drain Onto The
- 4. Anything That Traps Or Holds Moisture On A Roof Will Cause Premature

Roof Maintenance Guidelines

1. Inspect Roof For Damage After Heavy Storms.

2. Inspect And Reseal As Necessary All Roof Curbs And Other Penetrations With

3 Always Get Manufacturer Approval Before Making Any Modifications To The

4. Repaint Any Areas That Are Susceptible To Rust As Required.

- 5. When Performing Roof Maintenance, Always Take The Following Precautions:
 a. Use Fall Protection And Other Safety Protection As Required.
 b. Do Not Walk On Roof Flashing Such As Gutter, Rake, Hip Or Ridge Flash. c. Do Not Walk On Light Transmitting Panels (LTP's). They Will Not Support A
- Person's Weight. d Guard All LTP's And Roof Openings
- Step Only In The Panel Flat Directly On Or In Close Proximity To A Supporting Roof Structural.
- 6. After Other Trades Have Been On The Roof For Any Reason, Inspect The Roof to. Arter Order Toucks Have been of the Royal Processor, inspect the Root For Damage Caused By Workers Including Chemical Or Solvent Spills, Scratches In The Paint Or Galvalume Coating, Excessive Foot Traffic And Punctures. Make Sure That All Debris Or Scrap Left Behind By Workers Is Removed From The Roof Immediately, Avoid Using Cutoff Saws And Welding Equipment Over The Roof, The Roof Must Adequately Protected.

FOOT TRAFFIC: Keep Foot Traffic To A Minimum. Heavy Foot Traffic Can Cause Ponding On Low Pitched Roofs. This Is Particularly True Just Upslope From The Eave And A

Endlaps. Always Walk In The Flat Of The Panel Near A Supporting Roof Structural. Do Not

On Bare Galvalume Roofs, Excessive Foot Traffic May Cause Black Burnish Marks. On Bore Galvalume Roofs, Excessive Foot Traffic May Couse Black Burnish Marks. If Regular Foot Traffic Is Planned For A Roof, Provisions Should Be Made For A Properly Designed And Installed Walkway System. In Order To Limit Access To The Roof, Roof Hatches Or Access Ladders Should Be Locked At All Times. A Sign Posted At The Access Site Stating That Only Authorized Personnel Are Allowed On The Roof. In Addition A Log Book Should Be Kept Of All Visits To The Roof And

Walk On Trim Or In Gutters.

<u>DISSIMILAR METALS:</u>
Never Allow Your Roof To Come In Contact With, Or Water Runoff From Any Never Allow four Noor to Come in Contact with, Or water kunoff from Any Dissimilar Metal Including But Not Limited To:
Copper, Lead Or Graphite, This Includes Copper And Arsenic Salts Used In Treated Lumber, Calcium Used In Concrete, Mortar And Grout. Never Step On Light Transmitting Panels (LTP's) Or Unattended Roof Panels



Panels May Collapse

Roof Panels Must Be Completely Attached To The Purlins And To Panels On Either Side Before They Can Be A Safe Walking Surface. Light Transmitting Panels LTP's) Translucent Panels Can Never Be Considered As A Walking Surface.

Partially Attached Or Unattached Panels Should Never Be Walked On!

- 1. Step On Rib At Edge Of Panel.
- 2. Step Near Crease In Rib At Edge Of Panel.
- 3. Step Within 5 Feet Of Edge On Unsecured Panel.

A Single Roof Panel Must Never Be Used As A Work Platform. An OSHA Approved Runway Should Be Used For Work Platforms. (Consult OSHA Safety And Health Regulations For The Construction Industry), Safety First!

> S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on an




Erection Guide

R1

<u>Building Anchorage</u>

- To Determine That The Foundation Is Square, Measure Diagonal Dimensions To Be Sure They Are Of Equal Length.
 To Determine That The Foundation Is Level, Set Up A Transit Or Level And Use A Level Rod To Obtain The Elevation At All Columns.
- Carefully Check The Location Of All Anchor Rods Against The Anchor Rod Setting Plan Furnished By The Manufacturer. All Dimensions Must Be Identical To Assure A Proper Start-up.




Pre-Erection Notes:

The Following Notes, Procedures And Suggested Recommendations Are Important Parts Of The Pre-Erection Process.


Prior To The Time The Erection Crew Arrives, A Responsible Person Should Check The Job Site For Foundation Readiness, Square, And Accuracy And Anchor Rod Size And Location.

The Drawing Shown Below Indicates A Method Which May Be Used To Check The Foundation And Bolts For Square.




Measure Along Adjacent Sides Of Foundation Using A Pair Of Dimensions Shown. If The Diagonal Distance Between These Points Is As Noted, The Corner Is Saugre. Diagonal Measurements Between Opposite Anchor Rods Will Indicate If These Bolts Are Set Square.

It Is Extremely Important That Anchor Rods Are Placed Accurately And In Accordance With The Anchor Rod Setting Plan. All Anchor Rods Should Be Held In Place With A Template Or Similar Means, So That They Will Remain Plumb And In Correct Location During The Placement Of The Concrete. A Final Check Should Be Made After Completion Of The Concrete Work And Prior To The Steel Installation. This Will Allow Necessary Corrections To Be Made Before Costly Installation Labor And Equipment Arrives.




Projection Of Anchor Rods (D) Given On Anchor Rod Plan



Dimensions A, B, And C Given On Anchor Rod Plan

AISC Code Of Standard Practice For Steel Building And Bridges Tolerances For Setting Anchor Rods


Anchor Rod Diameter, Inches (mm) *Horizontal Variation, Inches (mm)




Erection Tolerances

ERECTION BRACING: It Is The Responsibility Of The Erector To Determine, Furnish And Install All Temporary Supports Such As Temporary Guys, Beams, Falsework, Cribbing, Or Other Elements Required For The Erection Operation (In Accordance With Section 7.10.3 Of ANSI/AISC 303, Code Of Standard Practice For Steel Building And


COLUMN ALIGNMENT TOLERANCES



ALIGNMENT TOLERANCE FOR MEMBERS WITH FIELD SPLICES



MEZZANINE BEAM HEIGHT TOLERANCE




General Erection Notes

- 1,) All Structural Framing Members, Purlins, Girts, Clips, Flange Braces, Bolts Bracing Systems, Roof And Wall Panels, Etc. Must Be Installed As Shown On Erection Drawings.
- 2.) It is Extremely Important, Especially During Construction, That Panels At The Eaves, Rakes And Ridges Be Kept Secure.

Panel Cautions And Notes

- To Minimize Potential Of Corrosive Action At The Bottom Edge Of Wall Panels, The Contractor Must Assure That The Following Procedures Are Followed:
- 1) The Concrete Foundation Should Be Cured For A Minimum Of Seven (7) Days Before Wall Panels Are Installed. (Uncured Concrete Is Highly Alkaline And Metal Panels Can Undergo Varying Degrees Of Corrosive Attack When In Direct Contact With The Concrete.) After The First Week Of The Curing Cycle, The Reaction Between Metallic Coatings On Steel And The Concrete Is Essentially Halted.
- 2.) Top Of Finish Grade At Building To Be A Minimum Of Four (4) Inches Below
- 3.) Finish Grade Is To Slope Away From Building To Ensure Proper Drainage.
- 4.) Upon Completion Of Finish Grading, All Dirt Is To Be Cleaned From Around Base Of Wall Panel Where It May Have Collected In Panel Notch Or On Base Trim.



<u>Fastener Installation</u>

Correct Fastener Installation Is One Of The Most Critical Steps When Installing Roof/Wall Panels. Drive The Fastener In Until It Is Tight And The Washer Is Firmly Seated. Do Not Overdrive Fasteners.

A Slight Extrusion Of Neoprene Around The Washer Is A Good Visual Tightness Check. Always Use The Proper Tool To Install Fasteners. A Fastener Driver (Screw Gun) With A RPM of 1700–2000 Should Be Used For Self-Drilling Screws. A 500–600 RPM Fastener Driver Should Be Used For Self-Tapping Screws. Discard Worn Sockets, These Can Cause The Fastener To Wobble During Installation.

<u>Note:</u> Always Remove Metal Filings From Surface Of Panels At The End Of Each Work Period. Rusting Filings Can Destroy The Paint Finish And Void Any Warranty







Of Sealing Washer

Tape And Tube Sealant

Proper Tape And Tube Sealant Application Is Critical To The Weather Tightness Of A Building. Tape Sedant Should Not Be Stretched When Installed. Apply Only To Clean, Dry Surfaces. Keep Only Enough Sedants On The Roof That Can Be Installed in A Day. During Warm Weather, Store Sedants In A Cool Dry Place. During Cold Weather (below 60°) Sedants Must Be Kept Warm (60°-90°) Until Application. After Tape Sedant Has Been Applied, Keep Protective Paper In Place Until Panel Is Ready To Be Installed.

<u>Important Note</u>

All Details, Recommendations And Suggestions Contained In This Erection Guide Of This Drawings Set Are For General Guidelines Only, And Not Meant To Be All-inclusive. Industry Accepted Installation Practices With Regard To All Areas Not Specifically Discussed In This Section Should Be Followed. Only Experienced, Knowledgeable Installers Familiar With Accepted Practices Should Be Used To Assure A Quality Project.

It is Emphasized That The Manufacturer Is Only A Manufacturer Of Metal Building Components And Is Not Engaged in The Installation Of Its Products. Opinions Expressed By The Manufacturer About Installation Practices Noted in The Erection Guide Are Intended To Represent Only A Guide. Both The Quality And Safety Of Installation And The Ultimate Customer Satisfaction With The Completed Building Are Determined By The Experience, Expertise, And Skills Of The Installation Crews, As Well As The Equipment Available for Handling The Materials. Actual Installation Operations, Techniques And Site Conditions Are Beyond The Manufacturers Control.

This item has been electronically signed and sealed by Yuangang (Bill) Li, S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any




Erection Guide

R2 Sep '17 Rev

PBR Roof Panels

For PBR Roofs With Ridge Panels, It Is Recommended That Both Sides Of The For the Roots with Ridge Ponels, it is recommended into Both Sides Of The Ridge Be Sheeted Simultaneously. This Will Keep The Insulation Covered For The Maximum Amount Of Time And The Panel Ribs Can Be Kept in Proper Alignment For The Ridge Panel. This Is Critical On The PBR Panels So That The Ridge Caps Can Be Properly Installed. Check For Proper Coverage As The Sheeting Progresses.



Install The First Run Of Roof Panels Across The Building From Eave To Eave Or Eave To Ridge. To Allow Proper Installation Of The Roke Trim, The Starting Location For The First Panel Must Be As Shown In The Roke Details Included With The Erection Drawings. When The First Run Is Properly Located And Aligned With The Correct Endlops And Eave Overhangs, Fasten To Purlins. Roof Panels Should Be Installed So That The Sidelap Is In A Direction Away From Prevailing Wind. Refer To Appropriate Lap Details Included With The Erection Drawings.

Install Remaining Roof Insulation And Panels. To Avoid Accumulative Error Due To Panel Coverage Gain Or Loss, Properly Align Each Panel Before It Is Fastened. Occasional Checks Should Be Made To Ensure That Correct Panel Coverage Is Maintained. Special Attention Should Be Given To Fostener, Sealant and Closure Requirements. Refer To Details Included With The Erection Drawings.

At Finishing End Of Roof, The Lost panels May Require Field Modification For Installation Of Roke Trim. Refer To Rake Details Included With The Erection Drawings. DO NOT BACK LAP THROUGH FASTENED ROOF PANELS.

NOTE: Roof Types And Installation Requirements Will Vary. Refer To The

<u>IMPORTANT:</u> Loose Fasteners, Blind Rivets, Drill shavings, Etc.. Must Be Removed From The Roof To Guard Against Corrosion.


Wall Panels

Proper Horizontal And Vertical Alignment Of Supporting Structure (Girts Or Other Framing) Is The Responsibility Of The Installer. Failure To Align The Secondary members Properly Prior To Wall Installation Can Have A Direct Impact On The Final Appearance And Performance Of The Installed Wall System For Which The Metal Building Manufacturer Is Not Responsible.


Before Installing Wall Panels, The Girts Must Be Aligned To A Level Position So That There Is No Visible Sag. This Should Be Done Directly Ahead Of Panel

Girt Leveling May Be Accomplished By Standing A Section Of Gable Angle Vertically Against The Outside Girt Flanges At Approximate Mid-boy Location.
When Girts Are Level, Attach The Girt Flanges To The Angle With Vise Grip Pliers
Or Temporary Screws. Wood Blocking Cut To Fit The Spaces May Also Be Used
For Alignment.

Temporary Girt Blocking Is Not Recommended On Concealed Fastener Panels. The Removal Of The Blocks After Panel Installation Can Cause Oil Canning.





Note: Wall Panel Type And Installation Details Will Vary, Refer To The Erection Drawings And Details For The Specific Panel Used For Your Building.



If Walls Are To Be Insulated With Blanket Insulation Over Girt Girt Flanges, Base And Eave, Place A Continuous Run Of Contact Tape Along The Eave Strut And

At The Base, Cut Off The Insulation A Minimum Of $\frac{1}{2}$ Above The Bottom Of The Wall Panel. This Will Prevent The Insulation From Hanging Below The Wall Panel






Sidewall Panels Should Be Installed So That The Panel Sidelap Is In A Direction Away From The Prevailing Wind. Refer To Appropriate Lap Detail Included With Erection Drawings.)

(See Erection Drawings)


Note: Check Periodically To Ensure That All Panels Are Aligned And Plumb.



Screw Alignment Panel (Through Fastened Panel Only)

<u>Note:</u> After Drilling Panels, It is Important To Clean Metal Filings Off All Panel Surfaces, Including Between Panels That Are Not Installed That Day, To Avoid Rust Stains.

Suggested Method Of Purlin Attachment For Building Accessories



* Denotes Material Not Provided By Metal Building Manufacturer.


The Total Hanger Load Shall Not Exceed The Design Collateral Load For The Building. Example: 5'-0 (Purlin Spacing) X 5'-0 (Hanger Spacing) X 6 PSF (collateral Load)

5 - U (Purlin Spacing) X 5 - U (Hanger Spacing) X 6 PSF (collateral Load) = 150 Lbs.

See Cover Sheet For Design Collateral Load For This Building.

Note: If The Building Is Designed For 0 PSF Collateral Load, Then Adding Any Suspended System (i.e. Duct Work, Piping, Lights, Ceilings, Etc.) Will Correspondingly Reduce The Design Live Load.

Roof Curbs When Not Supplied By Building Manufacturer



The Curb Details Shown Illustrate The Building Manufacturers Recommended Curb Style And Installation Method. It Is The Erector/Installer's Responsibility To Provide The Proper Curb Style And Install Them In Accordance With The Procedures Established By These Details. Failure By The Erector/Installer To Follow These Recommendations May Result In The Curbs Damaging The Roof System Or

- 1. .080 Aluminum Or 18 Ga. Stainless Steel (No Galvalume® Or Galvanized).
 2. Panel Rib To Panel Rib (No Flat Skirt Or Lay—Over Curbs).
 3. Installed With Down Hill End Over Panel And Up Hill End Under Panel Application
- Troubled with Down All 2nd Over Faller And Op All 2nd Order Faller Order Falle
- b. Curb Base Crosses A Purlin.
- 5. Supported on (4) Sides By Primary Or Secondary Framing. 6. Maximum Single Curb Weight Recommended Is 1500 Lbs.

Roof Jack Installation when Not Supplied By Building Manufacturer

Ceneral Installation Notes
 Do Not Use Galvanized Roof Jacks, Lead Hats, Or Other Residential Grade Roof Jacks. These Roof Jacks Do Not Have 20 Year Service Life And In Case Of Lead Hats Will Cause Galvanic Corrosion Of The Roof Panel.
 Use EPDM Rubber Roof Jacks With An Integral Aluminum Band Bonded Into The Perimeter Of The Base. EPDM Roof Jacks Hove A Temperature Range From —65T To 212T. Use Silicone Roof Jacks For High Temperatures. Silicone Roof Jacks Have A Temperature Range Of —100T To 437T.

 Retrofit Roof Jacks Are Available For Applications In Which The Top Of The Pine Is

Retrofit Roof Jacks Are Available For Applications In Which The Top Of The Pipe Is Inaccessible, Eliminating The Possibility Of Sliding The Roof Jack Over The Top Of The

Pipe.


Do Not Use Tube Sealant To Seal The Roof Jack To The Roof Panels. Use Roll Tape Sealer Between The Roof Jack And The Roof Panel And Attach The Roof Jack To The Roof Panel With Fastener #4 \(\frac{1}{4}\) — 14 \(\chi \)\[\frac{8}{6}\] * LL SD \(\tilde{W}\) washer At 1" O.C. Around The Base Of The Roof Jack. See Table Below For Quantities

Trim The Top Of The Roof Jack to Fit Over The Pipe, Roll Down The Roof Jack Over The Pipe And Apply Tape Sealer For The Perimeter Of The Roof Jack Base Between The Roof Jack And The Roof Panel. Apply Tape Sealer Around The Pipe And Install A Stainless Steel Clamp (Not By Bldg, Mfr.) Over The Top Of The Roof Jack And Firmly Tableto. In Express Assets Corporations.


Tighten To Form A Secure Compression Seal.

If The Pipe Diameter Is So Large To Block The Flow Of Water Down The Roof Panel, A Flot Base Roof Curb Must Be installed Into The Roof And The Roof Jack Will Be Sealed To The Curb. A Two Piece Curb May Be Required When The Top Of The Pipe Is

In Northern Climates, The Pipe Penetration Should Be Protected From Moving Ice Or Snow With A Snow Retention System Immediately Up Slope From The Pipe.



Install Pipe In Center To Allow Base Of Roof Jack To Lay Flat on Panel. Cannot Encompass More Than 75% Of Panel.



Tri-Bead Tape Sealer 7" x

This item has been electronically signed and sealed by Yuangang (Bill) Li S.E., P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any



Erection Guide

R3